UNIVERSITY OF KENTUCKY
[redacted]
3 0425 5176854 7

FINAL REPORT

REAL PROPERTY SURVEY

OF

CITY OF OWENSBORO,

KENTUCKY.

1939-1940

Property of W. P. A. State Office
Louisville, Kentucky

DEPOSITORY
UNIV. OF KENTUCKY LIBRARIES

LIBRARY
UNIVERSITY OF KENTUCKY

REAL PROPERTY SURVEY
OF
OWENSBORO, KY.

MADE BY

U. S. WORK PROJECTS ADMINISTRATION. Kentucky.

OFFICIAL PROJECT NO. 665-43-3-424-1

SPONSORED BY

CITY OF OWENSBORO

A STUDY OF
HOUSING
LAND UTILIZATION
POPULATION GROWTH

1939 1940

LIBRARY
U OF KY

226609

kg 331.83 Un32o

United States. Work Projects
Real property survey of Owens
HD7303.K4 .U5510 1940

CITY OF OWENSBORO

KENTUCKY

REAL PROPERTY SURVEY

Honorable Mayor and Commissioners,
City of Owensboro,
City Hall,
Owensboro, Kentucky

Gentlemen:

It is with a great deal of satisfaction that I submit for your approval the completed report of the Real Property Survey of our city.

The report consists of one volume containing a thorough analysis of the residential structures and families occupying them, together with tabulation tables and special maps illustrating the housing and sanitary conditions as related to the homes, or dwelling units of Owensboro.

In addition to the information collected and compiled as a result of some twelve months work, some twenty-five to thirty unemployed men and women were given gainful employment.

The work was performed by the Works Projects Administration, and sponsored by the City of Owensboro, and it is their sincere wish that the maps, tables and other information contained in this report will find an important place in both official and civic groups interested in the growth of our city.

Respectfully submitted,

MAStimson

Maurice A. Stimson
Director of Survey

ACKNOWLEDGEMENT

****

The successful completion of the Real Property Survey was concluded only through the excellent cooperation offered by all the groups connected with this work.

To the Works Projects Administration, who furnished most of the personnel and funds, goes the sincere thanks of the sponsor for making available all necessary facilities incidental to the field work, final tabulation and summary of the survey.

To the Mayor and Commissioners of the City of Owensboro, who furnished the space necessary for the headquarters of the project as well as the assistance of the city engineering staff in drawing up the maps.

To the insurance agency who, so kindly, permitted us the use of their Sanborn Insurance Maps.

We wish, also, to thank others who cooperated with us, particularly the residents of Owensboro, who gave us the necessary information for the survey.

TABLE OF CONTENTS

HISTORY OF OWENSBORO 4
CHART NO. 1, GROWTH OF OWENSBORO 11
MAP NO. 1, ORIGINAL BOUNDARIES OF OWENSBORO 12
PART ONE - INTRODUCTION 13
DWELLING SCHEDULE CARD 19
BLOCK LIST SHEET 20
BLOCK MAP 21
DEFINITIONS 22
DWELLING STRUCTURE TYPES 24
" " " 25
" " " 26
" " " 27
IDENTIFICATION MAP 32
LAND USE MAP - DESCRIPTION 33
LAND USE MAP 34
LAND COVERAGE MAP - DESCRIPTION 35
LAND COVERAGE MAP 36
BLOCK DATA MAP 37
CONVERTED STRUCTURE MAP 38
AVERAGE RENTAL MAP 39
RACE OF HOUSEHOLD MAP 40
CHART NO. 2, RACE OF HOUSEHOLD BY MONTHLY RENT 41
CONDITION OF STRUCTURE MAP 42
CHART NO. 3, CONDITION & MATERIAL 43
SANITARY FACILITIES MAP 44
CHART NO. 4, SANITARY FACILITIES BY CONDITION 45
AGE OF STRUCTURE MAP 46
CHART NO. 5, AGE OF STRUCTURE BY CONDITION 47
PERSONS PER ROOM MAP 48
CHART NO. 6, PERSONS PER ROOM BY EXTRA FAMILIES 49
OWNER OCCUPANCY MAP 50
CHART NO. 7, AVERAGE VALUE OWNER OCCUPIED UNITS 51
MORTGAGE STATUS MAP 52
DURATION OF TENANT OCCUPANCY MAP 53
DURATION OF OWNER OCCUPANCY MAP 54
SUBSTANDARD MAP 55
SUBSTANDARD MAP - DISCUSSION 56

Continued next page

TABLE OF CONTENTS - (Cont.)

TABLE NO. 1 57
TABLE NO. 2 58
TABLE NO. 3 59
TABLE NO. 4 - PAGE 1 60
TABLE NO. 4 - PAGE 2 61
TABLE NO. 5 A 62
TABLE NO. 6 63
TABLE NO. 7 A 64
TABLE NO. 8 A 65
TABLE NO. 9 A 66
TABLE NO. 10 A 67
TABLE NO. 11 68
TABLE NO. 12 69
TABLE NO. 13 70
TABLE NO. 14 71
TABLE NO. 15 72
TABLE NO. 16 A 73
SUMMARY TABLES NO. 1, 2 & 3 74
SUMMARY TABLES NO. 4 & 5 75
SUMMARY TABLES NO. 6, 7 & 8 76
SUMMARY TABLE NO. 9 77
SUMMARY TABLES NO. 10 & 11 78
SUMMARY TABLE NO. 12 79
SUMMARY TABLES NO. 13, 14 & 15 80
SUMMARY TABLE NO. 16 81

HISTORY OF OWENSBORO

Owensboro is located on the south bank of the Ohio River, midway between the falls of the Ohio and the mouth of the river, at what was known to the early flat-boat men as "Big Yellow Banks" usually shortened to "Yellow Banks." This name was derived from the deep yellow color of the river bank which extended for about six miles along the river at a height of ten to twenty feet above the highest floods.

The first settler was Bill Smothers, whose log cabin, at the future site of Owensboro, was erected in 1799 or 1800. He was without family and resided there with his unmarried sister. He supported himself and his sister by hunting wild game, which was plentiful in the unbroken forest, and supplying the passing boatmen with supplies.

By 1810, however, a David Morton had built a modern store stocked with goods of foreign manufacture, brought in over the mountains, which he disposed of at shockingly high prices. This store provided a stopping point for emigrants from Virginia, Maryland and the Carolinas, and hardly a single westward-bound caravan

stopped at the thriving community but what one or two families remained as permanent residents. Meanwhile the demands of trade brought other emigrants and by 1815 the population had grown to more than one hundred persons.

In 1817 this community was incorporated by the Kentucky Legislature under the name of Owensborough in the honor of Colonel Abraham Owen, statesman, soldier and one of the members of the Constitutional Convention. Colonel Owen, as aide to General William Henry Harrison, fell in action at the Battle of Tippecanoe.

Before the charter was granted, a town was laid off on the present site of Owensboro and named Rossboro. This was in recognition of the position of David Ross, innkeeper and largest landowner in the community. It is of interest also to note here that to Frederica, his daughter, went the honor of giving the main - and only - street her name. Thus it is that one of Owensboro's main streets still bears her name.

The growth of the new town was slow but by 1830 its population was 229. In 1850 it had increased to 1215 people. From this date on the town took on new life and almost doubled its population during the ten years following, the 1860 census showing nearly 2308

inhabitants. The growth and prosperity of the town was greatly affected by the Civil War, many of its citizens removing to more secure localities, and others entering the armies of the North and South. The first Court House was a log one. The second, of brick, was constructed in 1858. It was burned during the Civil War by a guerilla named Davidson, in 1865. The town was chartered as a city in 1866 and four years later its population was given as 3,437. In 1880 it contained 6,231 inhabitants and by 1890 had grown to a city of nearly 10,000 people.

Following the turn of the century the tempo of the city quickened. New industries were attracted to the locality and older ones began to expand. The principal industry at this stage was the distilling of whiskey. Tobacco also came in for its share of attention and, for a time, cellulose was manufactured in large quantities. By 1910 the city had grown to 16,011. This growth has continued and at the present time has almost doubled the 1910 figures, the 1940 census showing more than 30,000 people.

With the advent of prohibition most of the distilleries were abandoned, only one remaining in existence. This one operated at intervals manufacturing medicinal whiskey and alcohol. In the early 1920's

the Kentucky Lamp Company, manufacturers of incandescent light globes was founded. With the tremendous growth of the radio industry, the lamp company began the manufacture of radio tubes and today it is the largest single industry in the town, employing at peak approximately 3500 persons. With the demise of the Eighteenth Amendment Owensboro's long-dormant distilling industry was reborn. Today there are three distilleries with a total capacity of 1100 barrels of whiskey a day.

The first or original town was laid off in 1817 when the first charter was received. These boundaries were as follows: The Ohio River was the northern boundary and this extended from Lewis Street on the east to Frederica on the west, then it ran south-west along a deep ravine to Walnut Street, then south on Walnut to Fourth Street and from this point back east to Lewis Street.

Owensboro in 1872 had a population of approximately 8,000, and was one of three princiapl cities on the Ohio River between Louisville and Cairo. The city at this time had the following businesses:

31 Lawyers
15 Physicians
9 Ministers of the Gospel
3 Dentists
6 Drug Stores

6 Express Wagons
15 Drays
25 Grocery Stores
16 Dry Goods Stores
10 Merchant Tailors
2 Boot and Shoe Stores
1 Queen's Ware Store
1 Carpet Store
2 Tinware and Stove Establishments
3 Hardware Stores
3 Bakeries
11 Confectioneries
2 Book and Stationary Stores
5 Barber Shops
6 Meat and Vegetable Shops
6 Millinery Stores
2 Furniture Stores
2 Gunsmiths
2 Photograhpers
3 Jewelry Establishments
35 Liquor Saloons
6 Beer Saloons
10 Livery Stables
3 Cigar Makers
3 Undertakers
9 Shoemakers
7 Clothing Stores
4 Saddlers
8 Blacksmiths and Wagonmakers
1 Hide and Fur House
1 Dye House
1 Real Estate Agent
15 Tobacco Stemmeries
2 Planing Mills
1 Woolen Mill
1 Foundry
1 Broom Factory
2 Breweries
3 Corn and Wheat Mills
6 Hotels
7 Distilleries
1 Furniture Factory
4 Brick Kilns
2 Large Wharf Boats
1 Gas Works
2 Public Schools
3 Private Schools
1 Opera House

It was during this year that the first Fire Department was organized. For several years this need had been discussed but up until this time nothing had been done. An excellent steam fire-engine was purchased and was manned by a crew of four. The first telephones were installed in 1880, local citizens organizing a company known as the Owensboro Telephone Exchange.

The first Mayor, a Mr. E. S. Ayers, was elected in 1866. He died in less than a week after taking office and his unexpired term was filled by S. D. Kennady, a member of the City Council.

Prior to the automobile age Owensboro was well known for its three large buggy plants, two large wagon factories and a factory manufacturing buggy and wagon wheels. One of the buggy plants survived until there were only three of these plants in the whole country. One of the wagon plants is still in operation. Lumber has also played its small part in the industrial life of the city, as the largest hardwood band mill in western Kentucky has been manufacturing lumber here for forty years.

Old residents of Owensboro are agreed that while no single industry or development can claim all the credit for the rapid growth of the city following the World War, perhaps the two largest contributing factors

have been the Ken-Rad Tube & Lamp Company and Oil Industry. While it was generally known that there was oil in this territory it was not until the middle 20's that it was found in paying quantities. Development of the oil fields south and west of Owensboro together with the rapid expansion of the Ken-Rad have been important factors in the building up of the city.

The construction of new homes has been going on at a rapid rate since 1934 and in 1939 over 1200 homes were built. This is readily explained by the 1940 census which shows an increase in population of over 8,000 since 1930.

Owensboro is ideally situated for the location of manufacturing industries. It is close to the western Kentucky coal fields, has exceptionally good water, natural gas and reasonable power rates. There is plenty of good labor and transportation facilities. In selecting a place to settle Bill Smothers used exceptionally good judgment, for Owensboro was one of the few cities along the Ohio River that was located high enough to be safe from the flood waters of 1937.

CHART NUMBER 1



POPULATION GROWTH
OWENSBORO, KENTUCKY



Knockers House

PART 1

REAL PROPERTY SURVEY

INTRODUCTION

PURPOSE * SCOPE * PROCEDURE

PURPOSE

The Real Property Survey of Owensboro was conducted in an effort to make the city a healthier and happier place in which to live. This, it is hoped by the Sponser, the City of Owensboro, will be achieved in the immediate future as a result of the survey which:

(1) Gives an authentic picture of the housing needs of the city, particularly among the low-income groups now living in substandard conditions.

(2) Furnished employment to citizens of the professional and clerical classifications on the rolls of the Work Projects Administration.

SCOPE

The survey was planned to cover all of the dwelling structures and dwelling units in the city and its out-lying districts, and was conducted in accordance with the suggested technique of the Work Projects Administration and Federal Housing Authority.

For example, there are approximately 7111 dwelling structures and 8729 dwelling units in Owensboro. Each of these is broken down to reveal the number of persons per dwelling unit, number of bathrooms, the race and number of persons per room, whether the structure is owner or tenant occupied and other data of interest to particular groups.

Naturally, the picture as a whole furnished invaluable information to those officials engaged in the future zoning and planning of the city; those weighting the need for housing projects to alleviate the needs of the low income groups, and to many persons seeking data on questions of population shifts, overcrowding, sanitation within the home, child welfare agencies and the like.

To attempt to include all potential benefits which may be developed from a survey of this type is futile. If only some of the major problems of the city can be solved the sponsors will feel that it was not made in vain.

DEFINITION OF A REAL PROPERTY SURVEY

A real property survey is an inventory of all residential structures and dwelling units within a city, together with an account of the use to which all the land is put.

With respect to structures, statistics dealing with the various types of houses, the material used in construction, the percent which are mortgaged, the age of the building and their condition, as it relates to occupancy, are presented.

Concerning dwelling units, data revealing whether or not the unit is vacant, if occupied whether by a tenant or the owner, the monthly rent, number of persons per room per unit, number of bathrooms and toilets per occupant, the heating, lighting, cooking and refrigeration facilities is obtained.

RESULTS OF A REAL PROPERTY SURVEY

It is the hope of the sponsor that a study of the facts brought to light by this survey will result in an alleviation of poor housing conditions within the city; that future housing movements in Owensboro will recognize the need to eliminate many conditions which now exist.

The various phases of the survey present such a wide field for improvement in the city that to go into the details of them all in this limited report would be impractical. One thing, however, stands out when the information herewith presented is studied:

In a city which has always prided itself upon its progress, many of our citizens are living in homes which, by present day American standards, are inadequate. Expansion of the town through the years has left several areas of slums wherein conditions prevail which can be believed only after they are seen.

That there is a vital need for the elimination of these "boils" within the city seems to the sponsor self evident. And if this survey provides the spark needed to take this forward step, then it will not have been made in vain.

The number of dwelling units in Owensboro which do not have flush toilets or private bathing facilities is a definite menace to health - not only to the occupants of the units but to the general public. This is but one of the conditions brought out by the survey.

USES OF A REAL PROPERTY SURVEY

A partial list of the agencies, to which a detailed study of the information gathered during the survey may prove of value, follows. At the same time this list may serve to inform the layman of a few of the wide uses to which the material may be put.

1. PUBLIC AGENCIES

   A. Local Housing Bodies.
   B. City and County Engineers and Planning Boards.
   C. City Health Departments.
   D. Real Estate and Re-zoning Agencies.
   E. Departments of Education.
   F. Police Departments.
   G. Fire Departments.
   H. Welfare Agencies.
   I. Federal Agencies.
      (a) Federal Housing Administration.
      (b) United States Housing Authority.
      (c) Home Owners Loan Corporation.
      (d) Department of Commerce.
      (e) Department of Labor.

2. SEMI-PUBLIC AGENCIES

   A. Real Estate Boards.
   B. Chamber of Commerce.
   C. Public Utilities.
   D. Professional Societies.
   E. Colleges and Universities.

3. PRIVATE AGENCIES.

A. Real Estate Operators.
B. Financial Agencies
C. Newspapers.
D. Radio Stations.
E. Marketing Agencies.
F. Insurance Companies.
G. Architects and Construction Companies.

This information, if properly used, will be of untold value and assistance in making the city of Owensboro a better city in which to live.

PROCEDURE

The first step in beginning a survey of such magnitude and which, by its nature, depended on absolute accuracy, was to make an identification map. This was done by taking an ordinary standard map of Owensboro and then numbering every block. The city was then divided into thirteen districts, each of which contained approximately forty-five blocks.

Workers were then requisitioned from the rolls of the Work Projects Administration and a field staff and office force were organized. While workers were being schooled in the proper use of forms provided and the exact meaning of all terms to be used during the enumeration, maps for each block were drawn.

These maps were assigned numbers corresponding with those on the identification map mentioned above. Whenever available, these maps were taken from the Sanborn Insurance maps and in cases where not available, the block was traced from a master map and the structures filled in as the enumeration progressed. All structures falling into this group were measured by a field survey crew but where a Sanborn map was used originally the measurements thereon were accepted.

This made it possible to show every structure, including business, industrial, public and residential, on the block.

The field force was divided into squads of seven men each with a squad leader to act as foreman for each squad. It was the squad leader's responsibility to see that the enumeration made by his men was accurate and included every dwelling unit. A system of spot checking was employed to insure the accuracy and conscientiousness of each squad.

During the enumeration of a block count was started at the northwest corner of the area and the workers proceeded clockwise until they reached their respective starting points. A night crew, detailed specifically to contact families who were not at home during the day, also was set up. This assured the tabulators that no structures were omitted until every effort to establish a contact had been exhausted. The number of dwelling units on which no report could be obtained was of such a fractional percentage as to be negligible and in no way affects the statistical value of the survey.

Before any field work was attempted all enumerators were instructed and thoroughly schooled in the proper technique. Accuracy and the need of a rapid enumeration were stressed. Terms such as residential structure and dwelling unit were explained and the difference in types were pointed out to eliminate all chance of confusion.

Cards to be used by the field crew were distributed and the importance of all data stressed. These cards dealt with the type of structure, exterior material, year built, number of stories, condition, whether owner or tenant occupied, monthly rent, sanitary conditions, heating, number of persons and race of occupants. Each enumerator checked the structures with his block map and then entered the information on the card and listed the structure on a block list sheet.

As the cards and block lists were completed they were turned in to the office where a crew checked all entries, after which they were coded for tabulation. From these cards and block lists the block tabulation sheets were made out.

The block survey crew ascertained the area of each block, the area of all major structures, the area of all land in permanent use but not occupied by structures and all land not in permanent use. Structures not shown on the Sanborn maps were measured by the field crew.

As the survey advanced, each block, upon completion, was colored on the identification map in the office. This permitted a constant check as to the progress of the survey and the percentage of the city enumerated at any given time.

Each procedure was thoroughly checked before starting the table tabulation which consisted of compiling all the data on approximately 60 tabulation sheets of eighteen different tables.

Date 8/29/39
Enumerator [illegible]

DWELLING SCHEDULE

CITY OF OWENSBORO, KENTUCKY

E. D. 5 Block No. 234
Structure Number 13

Street Frederica Street No. 2224 Apartment No. or Location

I. ENTIRE STRUCTURE

A. Type of Structure
1. Single Family Detached X
2. Single Family Attached O
3. Two Family Side by Side O
4. Two Family Two Decker O
5. Three Family Three Decker O
6. Four Family Double Two-Decker O

No. of Units
7. Apartment ----
8. Business with Dwel. Units ----
9. Other Non-Converted ----
10. Partially Converted ----
11. Completely Converted ----

B. If Converted
1. Orig. Type ----
2. Yr. Converted ----

C. Business Units
1. None X
2. No. of Units ----

D. Exterior Material
1. Wood X
2. Brick O
3. Stone O
4. Stucco O
5. Other O

E. Stories
Number 1½

F. Basement
1. No O
2. Yes X

G. Year Built 1920
D

H. Garage
1. No O
2. Yes X

I. Condition
1. Good Condition O
2. Minor Repairs X
3. Major Repairs O
4. Unfit for Use O
5. Under Const. O

If Owner Occupied

J. Value of Entire Property $7500

K. No. Major Structures Included in value 1

L. Encumbrance
1. Mortgage or Land Contract X
2. No Encumbrance O

M. For Office Use
Persons per Room A
1. — 4.
2. — 5.
3. D 6.

II. THIS DWELLING UNIT

A. Occupancy
1. Owner X
2. Tenant O
3. Vacant O

B. Duration
1. Time Lived here
Yrs 11 Mos.
2. Length of Vacancy
Yrs. Mos.

C. Monthly Rent
$ 50.00

D. Included in Rent

	No	Yes
1. Furniture	X	O
2. Garage	X	O
3. Heat	X	O
4. Hot Water	X	O
5. Light	X	O
6. Cook Fuel	X	O
7. Mch. Refrig	X	O
8. Refrig. Fuel	X	O

E. Total Rooms
Number 9

F. Flush Toilets T
Number 2 S

G. Bathing Units
Number 1

H. Running Water
1. Hot and Cold X
2. Cold Only O
3. None O

I. Heating
1. Cent. Steam or Hot Water O
2. Cent. Warm Air X
3. Other Installed O
4. None Installed O

J. Lighting
1. Electric X
2. Gas O
3. Other O

K. Cooking
1. Electric O
2. Gas X
3. Other Installed O
4. None Installed O

L. Refrig Equipment
1. Electric X
2. Gas O
3. Ice O
4. None O

M. Number and Age of All Persons
TOTAL 4

Under 1 year	----
1—4	----
5—9	----
10—14	1
15—19	1
20—64	2
65 and over	----

N. Race of Household
1. White X
2. Negro O
3. Other O

O. Roomers
Number 0

P. Extra Families
1. No. Extra Fam 0
2. No. Persons ----

BLOCK LIST

OWENSBORO KENTUCKY

Form A
Enumerator [illegible] Date 7/14/39
Office Surveyor [illegible] Date 10/23/39
Field Surveyor [illegible] Date 10/15/39
Check [illegible]

Item		Sq. Ft.	Percent
Area of Block	1	81726	100 %
Not in Perm. Use	2		% of 1
In Permanent Use	3	81726	100% of 1
Area of Struct's.	4	26787	32% of 3

E.D. 6 Block No. 298
Sheet No. 1 A, of 1 Sheets
Number of Major Structures 20
No. of Cards for Block 41
Form B 17 Form C 24 Total
Form D ____ Form E ____

Street Name	Street Number	Residential Structures: Type	No. of Dwelling Units	Resident. Struct. No.	Description of Non-Residential Uses (Including Non-Residential Uses Mixed with Residential)	No. Business Units: Occupied	Vacant	No. of Stories	Area of Land Not In Permanent Use	Area of Structure	Continuous Frontage In One Use: Use	Feet
1	2	3	4	5	6	7	8	9	10	11	12	13
W. 4th St.	122	1	1	1	Dr. Office	1	0	2		1250	A	130
	118	1	1	2		0	0	2		1250	A	
	118R	1	1	3		0	0	2		756	A	
	114	1	1	4		0	0	2		1250	A	
	110	11	8	5		0	0	2		2160	C	135
					Side of 406 Allen						C	
Allen St.	406-10	11	11	6		0	0	3		3600	C	115
	416	1	1	7		0	0	2		1215	A	145
	416R	1	1	8		0	0	2		500	A	
	420	1	1	9		0	0	1		1440	A	
	424	1	1	10		0	0	2		1500	A	
	428	11	4	11		0	0	2		1200	B	55
					Side of 428 Allen						B	60
W. 5th St.	107	1	1	12	Dr. Office	1	0	2		750	A	35
	109				Beauty Parlor	2	0	1		1530	F	160
	111				Restaurant						F	
	113				Paint Store	1	0	1		1050	F	
					Side of 427 St. Ann						F	
St. Ann St.	427				Filling Station	1	0	1		340	F	50
	425	11	3	13		0	0	3		1824	B	180
	423-21	11	2	14	Beauty Parlor	1	0	2		1800	B	
	417	11	2	15		0	0	2		1404	B	
	415	8	1	16	Dr. Office	1	0	2		1375	E	30
	415R	1	1	17		0	0	2		693	A	
					Side of 122 W 4th						A	105
TOTALS			41	17		8	0			26787		1150


FOURTH ST.
122
118
114
110
1"
50'
410-06
ST.
ALLEN
416
420
424
428
107
111-09
113
FIFTH ST.
425
423-21
417
415
ST. ANN ST.

DEFINITIONS

ENUMERATION SCHEDULE

PART 1

MAJOR STRUCTURES. By major structures are meant buildings which include dwelling units or business units, industrial, public and institutional buildings. Barns and private garages without dwelling units are not considered.

RESIDENTIAL STRUCTURES. By residential structure is meant any major structure containing one or more dwelling units. A business unit with dwelling quarters is a residential structure in that it is enumerated. This does not include commercial or institutional structures such as hotels, Y. M. C. A., hospitals, asylums and so forth. Rooming houses are included as residential as also are private garages with living quarters.

DWELLING UNIT. By dwelling unit is meant a room or group of rooms intended to be occupied by one family or household as their home and where they sleep. A residential structure may contain one dwelling unit (single family house) or may contain several dwelling units (two family house, apartment and so forth). In general, a dwelling unit, when in a multi-family house or building is closed off from the other units.

BUSINESS UNIT. By a business unit is meant any piece of property, any building, or any portion of a building (provided it has a seperate out-door entrance) which is used for one business purpose.

TYPE 1. Single Family - Detached. A single family structure with open space on all four sides containing only one dwelling unit.

TYPE 2. Single Family - Attached. A structure build directly against an adjoining structure (whether residential or non-residential) without open space between and containing one dwelling unit extending from basement to roof. Such as row or terrace houses.

TYPE 3. Two Family - Side by Side. A structure containing two dwelling units, each of which extends from basement to roof.

TYPE 4. Two Family - Two Decker. A structure containing two dwelling units, one of which occupies the first floor and the other the second floor. This applies only to a structure built originally as this type. An original one family, two story structure, converted into this type is classified as Type 9.

TYPE 5. Three Family - Three Decker. A structure containing three dwelling units each of which occupies a complete floor.

TYPE 6. Four Family - Double Two Decker. A structure containing four dwelling units, with two units each occupying half of the first floor and two units each occupying half the second floor. An original one family, two story structure, converted into this type is classified as Type 9.

TYPE 7. Apartment. Any other non-converted structure which is primarily residential and which contains five or more dwelling units.

TYPE 8. Business with Dwelling Units. A non-converted structure which is primarily business in character, but which also contains dwelling units. A structure is of this type only when the business uses are more important than its residential uses.

TYPE 9. Other Non-Converted. All non-converted structures with four or less dwelling units which can not be classified as Types 1 to 8 inclusive.

TYPE 10. Partially Converted. A structure is partially converted when it is arranged to provide a different number of dwelling units than was intended when it was originally built and when the alterations involved in making these changes were so slight that the structure could be changed back to its original type without a substantial expenditure of time and money.

TYPE 11. Completely Converted. A structure is completely converted when it is arranged to provide a different number of dwelling units than was intended in its original construction and when the change involved substantial structural alterations to the building such as new entrances, halls, bathrooms and partitions. In complete conversion it would cost considerable money to turn the structure back to its original arrangement.



TYPE 1
SINGLE FAMILY DETACHED



TYPE 2
SINGLE FAMILY ATTACHED



TYPE 3
TWO FAMILY SIDE BY SIDE



TYPE 4
TWO FAMILY TWO DECKER



TYPE 5
THREE FAMILY-THREE DECKER



TYPE 6
FOUR FAMILY-DOUBLE TWO DECKER



TYPE 7
APARTMENT



TYPE 8
BUSINESS WITH DWELLING UNITS

EXTERIOR MATERIAL. This is the principal material used in the exterior walls.

STORIES. This section refers to the total number of stories in the structure, not including the basement.

BASEMENT. By basement is meant the space underneath the first principal floor. To count as a basement the space must be high enough for a person to stand upright and must extend under at least half of the structure and there must be enclosing walls of some kind.

YEAR BUILT. By this is meant the year in which the construction of the building was completed. This refers to the original construction and not to any later remodeling or conversion.

GARAGE. This applies to any private garage on the same parcel of land as the residential structure, whether it is a separate building or attached to the residence itself.

CONDITION. (1) "Good Condition" refers to all structures which are in good condition and need no repairs or paint.

(2) "Minor Repairs" refers to all structures which, while structurally sound, need painting or some small repair work.

(3) "Major Repairs" refers to all structures which need major repairs such as a new roof, foundation, new porch or general overhauling.

(4) "Unfit for Use" refers to a building which is in such bad condition that it is unfit for human habitation.

(5) "Under Construction" refers to a residential structure under construction and not yet occupied as a dwelling.

VALUE OF ENTIRE PROPERTY. This question refers to the value of the structure and the land on which it is built.

NUMBER OF MAJOR STRUCTURES INCLUDED IN VALUE. The owner of a single family attached structure will often own other similar structures attached to his own. (In this survey each unit is a row house or terrace house is considered as a separate unit.)

ENCUMBRANCE. Refers to property encumbered by a mortgage or land contract.

ENUMERATION SCHEDULE

PART 2

OCCUPANCY. Refers to the occupancy of either a structure or a dwelling unit by an owner or tenant.

DURATION. If the dwelling unit is occupied, the number of years and months which the present occupant has lived there is noted. Vacancies are similarly noted.

MONTHLY RENT. This section is filled out for all dwelling units. If tenant occupied the rent is stated and if owner occupied the rent he would ask is given.

INCLUDED IN THE RENT. This refers to the facilities which are furnished with the dwelling unit and which are included in the monthly rent. If owner occupied this section is not filled in.

1. FURNITURE. By furniture is meant tables, chairs, beds and so forth, but does not include necessarily linen, silver and such things.

2. GARAGE. This refers to any garage which is included in the rent.

3. HEAT. This refers to the furnishing of fuel required for the heating of this dwelling unit, whether or not the firing of the furnace is included.

4. HOT WATER. This refers to the furnishing of fuel required for the supply of running hot water for the dwelling unit when it is included in the rent.

5. LIGHT. This refers to the furnishing of electricity or gas for lighting when this is included in the rent.

6. COOKING FUEL. This refers to the furnishing of gas or other fuel for cooking when this is included in the rent.

7. MCH. REFRIGERATION. This refers to the furnishing of a mechanical refrigerator (operated either by electricity, gas or kerosene) when the furnishing of the refrigerator is included in the rent.

8. REFRIGERATION FUEL. This refers to the furnishing of the fuel (electricity, gas or kerosene) for running a mechanical refrigerator when the furnishing of such fuel is included in the rent.

TOTAL ROOMS. Includes all permanently enclosed major rooms in a dwelling unit. Bathrooms, pantries etc. not included.

FLUSH TOILETS. A flush toilet is an indoor toilet with running water.

BATHING UNITS. A bathing unit is a bathtub or a shower; if a bathtub or shower in the same room they count as one unit.

RUNNING WATER. Refers to hot and cold running water with the dwelling unit, not a hydrant on the outside.

HEATING. This refers to the principal equipment employed for heating the dwelling unit.

1. CENTRAL STEAM OR HOT WATER. Refers to a central furnace from which steam or hot water is piped to the various rooms in this dwelling unit.

2. CENTRAL WARM AIR. This refers to a central furnace from which warm air is piped to the various rooms in this dwelling unit.

3. OTHER INSTALLED. This refers to heating equipment which is installed in different rooms of the dwelling unit but which do not heat the unit from a central source. This includes Arcolas, base burners, gas radiators and fire-places.

4. NONE INSTALLED. This refers to dwelling units in which no heating is permanently installed.

LIGHTING. Refers to the principal type of lighting equipment installed in this dwelling unit.

COOKING. Refers to the principal equipment for cooking installed in this dwelling unit.

REFRIGERATION EQUIPMENT. This refers to the type of refrigeration installed in the dwelling unit.

NUMBER & AGE OF ALL PERSONS. This refers to the number and age of all persons who regularly sleep in the dwelling unit, whether they have their meals there or not.

RACE OF HOUSEHOLD. Race of persons occupying the dwelling unit.

ROOMERS. The persons living in the dwelling unit but not related to the principal family and who have agreed to pay specific rent for certain rooms.

EXTRA FAMILIES. Refers to individuals or groups of persons who are doubled up or are roomers because of present economic conditions, but who will probably move into seperate dwelling units of their own when conditions improve.

SUBSTANDARD DWELLING UNITS. A dwelling unit is considered substandard because of (1) the physical condition of the dwelling; and (2) occupancy conditions as related to the persons per room, presence or absence of extra families, and rental.

1. Substandard as to Physical Condition. A dwelling unit is considered as substandard if it:

1. Needs major repairs.

2. Unfit for use.

3. Has no private flush toilet.

4. Has no private bathing unit.

5. Has no running water.

6. Has no installed heating.

7. Has no electricity or gas for lighting.

2. Substandard as to Occupancy. A dwelling unit is considered substandard if:

1. There are more than 1.5 person per room.

2. If the monthly rental is less than $22.50; however, if a dwelling unit has the other qualifications it can not be considered substandard on account of a lower rental than listed here.

LAND USE

Probably the most interesting of the series of maps made by the Real Property Survey is the Land Use Map. This map gives a clear picture of the use to which every parcel of land is put. It shows the location of every commercial, industrial and public or semi-public institution, also the type of all residential structures. The available land for residential and industrial expansion can quickly and easily be found by referring to this map. All railroads, switches and so forth, which are essential to industry, are clearly shown.

A study of this map will show that single family residences predominate. It also points out that proper zoning of the city has been neglected in that numerous commercial establishments are promiscuously scattered thru the residential districts which is detrimental to the sections in which they are located.

While there are still a great many available building lots within the city limits most of the large scale residential developments are in the suburban area. The present trend of better class homes is to the south and south west, where the possibilities for expansion are unlimited. The construction of new homes continues with unabated speed and one large scale development is particularly worthy of mention. This development was planned to benefit the low income group and consists of three projects. Two of them, with 60 homes in one and 41 in the other other, are already under way; the third, which will have 60 homes, will be started shortly.

The past 15 years has seen a large increase in multi-family homes, mostly thru conversion of single family structures. This has been partially due to economic conditions, but probably the main contributing factor has been the need of small dwelling units due to the number of people coming into Owensboro to develop the large oil territory south and west of the city. Converted structures are scattered over the city but most of them are in the districts immediately adjacent to the business section of town.

The possibilities for both residential and industrial expansion are unlimited as the surrounding territory is high, level and well drained. A good supply of labor, water, cheap fuel and excellent transportation facilities, together with the new bridge connecting Owensboro with Indiana are advantages which should materially assist the city in securing new industries.

OWENSBORO, KY.
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
CAMPBELL
CHAUNCEY
PARK
CHAUNCEY
PARK
CHRISTIAN
CEMETERY
ELMWOOD
CEMETERY
OAK HILL
CEMETERY
CLEVELAND
PARK
COUNTRY
CLUB
LAND USE MAP
LEGEND
REAR DWELLING
SINGLE FAMILY
TWO FAMILY
MULTI-FAMILY
HOTEL
COMMERCIAL
INDUSTRIAL
COMMERCIAL WITH RESIDENCE
COMMERCIAL WITH INDUSTRIAL
RAILROAD
PUBLIC AND SEMI-PUBLIC
PARKS AND PLAY GROUNDS
CEMETERY
CITY PROPERTY
VACANT
TEMPORARY

LAND COVERAGE MAP

This map was prepared to show in a clear manner the actual amount of land in the area surveyed not in permanent use, the land in permanent use and the portion of permanent use land covered by major structures.

The area covered by the Real Property Survey totals up to 177,607,290 square feet, which is approximately 6 square miles.

Of this total area 34% of the land is vacant or not in permanent use. 66% is in permanent use and of this amount in permanent use 19.9% is covered by major structures, which leaves 80.1% of the land in permanent use not covered by major structures.

The land coverage is divided as follows: There are, in the city of Owensboro and its suburban area 7106 residential structures in which there are 8821 dwelling units.

Of this total amount of structures 253 are residential connected with business units, such as dwellings over drug stores, groceries, etc.

There are 408 commercial structures, 267 industrial structures and 134 public and institutional structures.

This sums up to a total of 7914 major structures, which includes all types of buildings excepting private garages, barns and other small structures.



LAND COVERAGE MAP

LEGEND

SHADED AREAS REPRESENT PERCENTAGE COVERED - NOT ACTUAL LOCATION OF THE LAND USE

LAND NOT IN PERMANENT USE - UNUSED LAND, PARKING LOTS, USED CAR LOTS AND LAND WITH OTHER TEMPORARY BUSINESS USES

LAND IN PERMANENT USE - BUT NOT COVERED BY MAJOR STRUCTURES

AREA COVERED BY MAJOR STRUCTURES

BLOCK DATA MAP

BLOCK DATA FIGURES ARE LISTED IN THE FOLLOWING ORDER FROM TOP TO BOTTOM

1. AVERAGE MONTHLY RENTAL OF ALL DWELLING UNITS.
2. TOTAL NUMBER OF DWELLING UNITS.
3. PERCENT OF ALL RESIDENTIAL STRUCTURES BUILT IN 1919 OR BEFORE.
4. PERCENT OF TOTAL NUMBER OF DWELLING UNITS OCCUPIED BY OWNERS.
5. PERCENT OF ALL RESIDENTIAL STRUCTURES NEEDING MAJOR REPAIRS OR UNFIT FOR USE.
6. TOTAL NUMBER OF STRUCTURES USED FOR BUSINESS OR COMMERCIAL PURPOSES.
7. PERCENT OF TOTAL NUMBER OF DWELLING UNITS WITH NO PRIVATE TOILET OR BATH.
8. PERCENT OF TOTAL NUMBER OF HOUSEHOLDS OF A RACE OTHER THAN WHITE.

OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
0 400 800 1200 1600 FEET
OHIO RIVER
SECOND
FOURTH
MORELAND PARK
CHAUTAUQUA PARK
ELMWOOD CEMETERY
ROSE HILL CEMETERY
LEGION PARK
EIGHTEENTH
CONVERTED STRUCTURE MAP
LEGEND
A DOT REPRESENTS ONE CONVERSION
○ COMPLETELY CONVERTED STRUCTURE
● PARTIALLY CONVERTED STRUCTURE


OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1936
OHIO
RIVER
AVERAGE RENTAL MAP
LEGEND
AVERAGE MONTHLY RENTAL VALUE
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
$9.99 OR LESS
$10.00 — $14.99
$15.00 — $19.99
$20.00 — $29.99
$30.00 — $39.99
$40.00 — $49.99
$50.00 OR MORE
Elmwood Cemetery
Rose Hill Cemetery
Park
Owensboro Country Club

OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
RACE OF HOUSEHOLD MAP
LEGEND
PERCENT OF DWELLING UNITS OCCUPIED BY NEGRO RACE
NON RESIDENTIAL USE
INSUFFICIENT REPORTS OR 0%
1% — 19%
20% — 49%
50% — 89%
90% — 100%
CATHOLIC CEMETERY
MORELAND PARK
CHAUTAUQUA PARK
ELMWOOD CEMETERY
ROSE HILL CEMETERY
OWENSBORO COUNTRY CLUB

-40-

CHART NO. 2

ALL DWELLING UNITS BY RACE OF HOUSEHOLD BY MONTHLY RENT



SERVICE REPORT

Merchants of Owensboro

NAME	ADDRESS	WHERE FROM	BUSINESS

MARKS:




OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
SECOND
FOURTH
FIFTH
GRIFFITH
FOURTEENTH
FIFTEENTH
MARCLAIR
PARK
FAIRVIEW
PARK
ELMWOOD
CEMETERY
POST WAR
CEMETERY
LEGION
PARK
CONDITION
OF
RESIDENTIAL STRUCTURES
LEGEND
PERCENT OF RESIDENTIAL STRUCTURES
IN NEED OF MAJOR REPAIRS
OR UNFIT FOR USE
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
OR 0 %
1 % — 9 %
10 % — 19 %
20 % — 29 %
30 % — 39 %
40 % — 59 %
60 % — 79 %
80 % — 100 %

CHART NO. 3

ALL RESIDENTIAL STRUCTURES BY CONDITION AND MATERIAL




OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
SANITARY FACILITIES MAP
LEGEND
PERCENT OF DWELLING UNITS
WITH NO PRIVATE TOILET OR BATH
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
OR 0 %
1 % — 19 %
20 % — 39 %
40 % — 59 %
60 % — 79 %
80 % — 100 %
HIGHLAND
PARK
CHAUTAUQUA
PARK
ELMWOOD
CEMETERY
ROSE HILL
CEMETERY
LEGION
PARK
OWENSBORO
COUNTRY CLUB

CHART NO. 4

SANITARY FACILITIES BY CONDITION OF STRUCTURE




OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
Elmwood Cemetery
Rose Hill Cemetery
Catholic Cemetery
Oakwood Cemetery
Catholic Plot
UNDESIGNED
GRAVEY CLAP
AGE OF STRUCTURE
MAP
LEGEND
MEDIAN YEAR BUILT
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
1930 —— 1939
1925 —— 1929
1920 —— 1924
1905 —— 1919
1885 —— 1904
1860 —— 1884
1859 OR BEFORE

CHART NO. 5

AGE OF STRUCTURE BY CONDITION




OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
SECOND
ST.
PARK
AVE.
GREEN
HILL
ELMWOOD CEMETERY
ROSE HILL CEMETERY
OWENSBORO COUNTRY CLUB
PERSONS PER ROOM
MAP
LEGEND
PERCENT OF OCCUPIED DWELLING UNITS
WITH 1.51 OR MORE PERSONS PER ROOM
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
OR 0 %
1 % — 9 %
10 % — 19 %
20 % — 29 %
30 % — 39 %
40 % — 100 %

CHART NO. 6

PERSONS PER ROOM BY EXTRA FAMILIES




OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
Columbia Park
Elmwood Cemetery
Rose Hill Cemetery
Cemetery
Park
Owensboro Country Club
OWNER OCCUPANCY MAP
LEGEND
PERCENT OF DWELLING UNITS OCCUPIED BY OWNER
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
0 % — 19 %
20 % — 39 %
40 % — 59 %
60 % — 79 %
80 % — 100 %

CHART NO. 7

AVERAGE VALUE OWNER OCCUPIED UNITS



226609

OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
MORTGAGE STATUS MAP
LEGEND
PERCENT OF SINGLE FAMILY
OWNER OCCUPIED STRUCTURES
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
0 % — 19 %
20 % — 39 %
40 % — 59 %
60 % — 79 %
80 % — 100 %
OLIVET CEMETERY
ROSE HILL CEMETERY
ADAIR PARK
OWENSBORO COUNTRY CLUB


OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
MARCIAL PARK
CUMBERLAND PARK
CUMBERLAND CEMETERY
ELMWOOD CEMETERY
POLK HILL CEMETERY
CRAWFORD PARK
OWENSBORO COUNTRY CLUB
DURATION
OF
TENANT OCCUPANCY MAP
LEGEND
MEDIAN DURATION OF OCCUPANCY
OF TENANT-OCCUPIED UNITS
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
LESS THAN 1 YEAR
1 YEAR – 1 YEAR 11 MONTHS
2 YEARS – 2 YEARS 11 MONTHS
3 YEARS – 4 YEARS 11 MONTHS
5 YEARS – 9 YEARS 11 MONTHS
10 YEARS – 19 YEARS 11 MONTHS
20 YEARS OR MORE

OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
DURATION
OF
OWNER OCCUPANCY MAP
LEGEND
MEDIAN DURATION OF OCCUPANCY
OF OWNER-OCCUPIED UNITS
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
LESS THAN 1 YEAR
1 YEAR - 1 YEAR 11 MONTHS
2 YEARS - 2 YEARS 11 MONTHS
3 YEARS - 4 YEARS 11 MONTHS
5 YEARS - 9 YEARS 11 MONTHS
10 YEARS - 19 YEARS 11 MONTHS
20 YEARS OR MORE
Elmwood Cemetery
Rose Hill Cemetery
Elmwood Park
Owensboro Country Club

OWENSBORO KY
REAL PROPERTY SURVEY
BY
WORKS PROGRESS ADMINISTRATION
JUNE 1939
OHIO
RIVER
SUBSTANDARD MAP
LEGEND
PERCENT OF DWELLING UNITS
WHICH ARE SUBSTANDARD
NON RESIDENTIAL USE
INSUFFICIENT REPORTS
OR 0 %
1 % — 14 %
15 % — 29 %
30 % — 49 %
50 % — 69 %
70 % — 84 %
85 % — 100 %
Cemetery
Maceland
Park
Cemetery
Cemetery
Rose Hill
Cemetery
Cemetery
Park

SUBSTANDARD MAP

As previously explained, page 31, a dwelling unit may be considered substandard (1) because of physical condition, that is, need of major repairs, unfit for use, lack of toilet and bathing facilities, running water, installed heating, gas or electricity for lighting; (2) because of crowded living conditions, too many persons per room, or due to a monthly rental below a set standard.

The standard set for Owensboro was $22.50 per month. Any house renting for less than this was considered a substandard. This is perhaps too high a figure, although there are probably houses renting for more than this that are substandard for other reasons. It is difficult to arrive at an absolutely correct figure for the substandard rental scale because there are no doubt some houses renting for less than $22.50 that are standard in all other respects.

For this reason the map may be misleading as to the actual number of substandard dwelling units. It does, however, give a true picture of the location of substandard units and the districts in which the largest percentage of these units prevail. Location within a block with a high percentage of substandard houses of course does not mean that all houses in that block are substandard.

A study of the Average Rental Map, Sanitary Facilities Map, Condition of Structure Map and Persons Per Room Map will show that in the low rental districts more houses need major repairs, have less sanitary facilities and that more people are living in less room. If these maps were laid one over the other the conditions named above would predominate just about as they do on the Substandard Map.

CITY Owensboro
STATE Kentucky
5-4-36

STRUCTURES UNDER CONSTRUCTION BY TYPE OF STRUCTURE
DWELLING UNITS UNDER CONSTRUCTION
BY TYPE OF STRUCTURE, BY NUMBER OF ROOMS, BY MONTHLY RENT
General Survey Tables

TABLE I
Under Construction

UNDER CONSTRUCTION		Line No.	Total Structures All Types	Number of Structures by Type of Structure: X. No Report on Type	1. Single Family Detached	2. Single Family Attached	3. Two Family Side by Side	4. Two Family Two Decker	5. Three Family Three Decker	6. Four Family Double Two Decker	7. Apartment: A. Total	B. 5 to 9 Units	C. 10 to 19 Units	D. 20 to 39 Units	E. 40 Units or More	8. Business with Dwelling Units	9. Other Non-Converted
TOTAL NUMBER OF STRUCTURES		1	88		80		2	3		1						1	1
TOTAL NUMBER OF DWELLING UNITS		2	96		80		4	6		4						1	1
DWELLING UNITS UNDER CONSTRUCTION BY NUMBER OF ROOMS	No Report	3	1		1												
	Total Reports on Rooms	4	95		79		4	6		4						1	1
	1 Room	5															
	2 Rooms	6															
	3 Rooms	7	7		3		4										
	4 Rooms	8	34		24			6		4							
	5 Rooms	9	29		28												1
	6 Rooms	10	12		12												
	7 Rooms	11	5		4											1	
	8 Rooms or More	12	8		8												
DWELLING UNITS UNDER CONSTRUCTION BY MONTHLY RENT	X. No Report on Rent	13	9		7											1	1
	Total Reports on Rent	14	87		73		4	6		4							
	A. $4.99 or Less	15															
	B. $5.00 to $9.99	16															
	C. $10.00 to $14.99	17	6		4		2										
	D. $15.00 to $19.99	18	6		4		2										
	E. $20.00 to $24.99	19	7		7												
	F. $25.00 to $29.99	20	9		7			2									
	G. $30.00 to $39.99	21	23		22			1									
	H. $40.00 to $49.99	22	18		18												
	I. $50.00 to $74.99	23	5		1					4							
	J. $75.00 to $99.99	24															
	K. $100.00 to $149.99	25	2		2												
	L. $150.00 or More	26	11		8			3									

6005

CITY Owensboro
STATE Kentucky
5-4-50

CONVERTED STRUCTURES BY TYPE OF CONVERSION
BY YEAR CONVERTED

General Survey Tables

TABLE 2
Converted Structures
Not under Construction

Type of Structure	Year Converted	Line No.	Total, Converted Structures	Number of Structures Converted from Single Family Detached or Single Family Attached into Structures with: 1 Dwelling Units, No Business Units	3 Dwelling Units or more, no Business Units	1 Dwelling Unit, With Business Units	2 Dwelling Units With Business Units	3 Dwelling Units or more, with Busin Units	No. of Structures Converted from other Types of Structure into Structures with: No Business Units	With Business Units
10. PARTIALLY CONVERTED	Total	1	457	358	80		2		17	
	No Report on Year Converted	2	114	74	31				9	
	Total Reports on Year Converted	3	343	284	49		2		8	
	1955	4	209	185	17		1		6	
	1930 - 1954	5	69	54	13				2	
	1925 - 1929	6	44	30	13		1			
	1920 - 1924	7	13	9	4					
	1915 - 1919	8	4	4						
	1905 - 1914	9	2	1	1					
	1895 - 1904	10	1		1					
	1885 - 1894	11	1	1						
	1860 - 1884	12								
	1859 or Before	13								
11. COMPLETELY CONVERTED	Total	14	77	30	35	2	2		8	
	No Report on Year Converted	15	19	6	8	2	2		1	
	Total Reports on Year Converted	16	58	24	27				7	
	1955	17	18	9	6				3	
	1930 - 1954	18	15	9	5				1	
	1925 - 1929	19	7		6				1	
	1920 - 1924	20	8	2	5				1	
	1915 - 1919	21	2	1	1					
	1905 - 1914	22	4		3				1	
	1895 - 1904	23	2	2						
	1885 - 1894	24	2	1	1					
	1860 - 1884	25								
	1859 or Before	26								

8006

CITY Owensboro
STATE Kentucky
5-4-35

STRUCTURES BY TYPE OF STRUCTURE BY NUMBER OF STORIES, BASEMENT, GARAGE, AND YEAR BUILT
General Survey Tables

TABLE 3
Structures not under Construction

Number of Structures By:		Line No.	Total Structures All Types	Number of Structures by Type of Structure															
				1. No. Report on Type	1. Single Family Detached	2. Single Family Attached	3. Two Family S. by Side	4. Two Family S Decker	5. Three Family S Decker	6. Four Family Double 2 Decker	7. Apartments A. Total	B. 5 to 9 Units	C. 10 to 19 Units	D. 20 to 39 Units	E. 40 or more Units	8. Business with Dwelling Units	9. Other Non-Converted	10. Partially Converted	11. Completely Converted
TOTAL	All Structures	1	7030		5492	1	476	156	4	40	8	8				244	75	457	77
NUMBER OF STRUCTURES BY NUMBER OF STORIES	No Report on Stories	2																	
	Total Rept's on Stories	3	7030		5492	1	476	156	4	40	8	8				244	75	457	77
	1 Story	4	5306		4444	1	402									97	54	283	25
	1-1/2 Stories	5	613		490		43	18								9	2	51	
	2 Stories	6	1063		542		31	137		40	7	7				121	19	118	48
	2-1/2 Stories	7	24		13			1	1							4		5	
	3 or 3-1/2 Stories	8	24		3				3		1	1				13			4
	4 or 4-1/2 Stories	9																	
	5 to 9-1/2 Stories	10																	
	10 Stories or More	11																	
NUMBER OF STRUCTURES BY BASEMENT	No Rept on Basement	12	3		2													1	
	Total Rept's on Basement	13	7027		5490	1	476	156	4	40	8	8				244	75	456	77
	No Basement	14	4955		3854	1	412	54		15	5	5				177	67	330	40
	With Basement	15	2072		1636		64	102	4	25	3	3				67	8	126	37
NUMBER OF STRUCTURES BY GARAGE	No Report on Garage	16	7		6													1	
	Total Rept's on Garage	17	7023		5486	1	476	156	4	40	8	8				244	75	456	77
	No Garage	18	3670		2812		318	43		16	4	4				167	60	213	37
	With Garage	19	3353		2674	1	158	113	4	24	4	4				77	15	243	40
NUMBER OF STRUCTURES BUILT 1920 - 1935 BY YEAR BUILT	Total Built 1920 - 1935	20	1599		1394		70	19		7	2	2				35	24	47	1
	1935	21	135		124		1									4	2	4	
	1934	22	90		80			3								3	3	1	
	1933	23	36		33		1										1	1	
	1932	24	58		48		3									3	1	3	
	1931	25	52		46					1						1	3	1	
	1930	26	199		173		9	3		1						4	5	4	
	1929	27	64		58		2	2										2	
	1928	28	72		65		4	1								1	1		
	1927	29	59		49		3									3		4	
	1926	30	48		44		1									1	2		
	1925	31	194		197		5	2			1	1				4		5	
	1924	32	82		72		2	1			1	1				2		3	1
	1923	33	50		45		2									1	1	1	
	1922	34	23		22			1											
	1921	35	21		19			2											
8007	1920	36	416		339		37	4		5						8	5	18	

CITY Owensboro

STATE Kentucky

3-5-36

OWNER OCCUPIED STRUCTURES BY VALUE OF PROPERTY BY TYPE OF STRUCTURE BY CONDITION, DEBT STATUS, AND NUMBER OF ROOMS IN STRUCTURE

General Survey Tables

TABLE 4, PAGE 1 OF 2.

Owner Occupied Structures Not Under Construction

Type of Structure	Number of Owner-occupied Structures by:		Line	Total Owner-Occupied Struct.	Number of Owner-occupied Structures by Value of Property: I. No Rept on Value	A. $499 or Less	B. $500 to $999	C. $1,000 to 1,499	D. $1,500 to 1,999	E. $2,000 to 2,499	F. $2,500 to 2,999	G. $3,000 to 3,999	H. $4,000 to 4,999	I. $5,000 to 5,999	J. $6,000 to 7,999	K. $8,000 to 9,999	L. $10000 to 14999	M. $15000 to 19999	N. $20000 to 29999	O. $30000 or More
1. SINGLE FAMILY DETACHED STRUCTURES	Owner Occupied	Total Structures	1	2588	3	47	225	337	286	287	200	458	301	154	171	60	44	12	3	
	Number of Structures by Condition	X. No Report on Condit'n	2																	
		Total Repts on Condit'n	3	2588	3	47	225	337	286	287	200	458	301	154	171	60	44	12	3	
		1. Good Condition	4	1697	3	6	57	144	161	199	150	375	240	132	126	49	41	11	3	
		2. Minor Repairs	5	714		15	99	143	111	81	48	78	59	21	45	11	2	1		
		3. Major Repairs	6	153		13	62	48	14	6	2	4	2	1			1			
		4. Unfit for Use	7	24		13	7	2		1		1								
	Number of Structures by Number of Rooms in Structure	No Report on Rooms	8																	
		Total Repts on Rooms	9	2588	3	47	225	337	286	287	200	458	301	154	171	60	44	12	3	
		1 Room	10	6		5	1													
		2 Rooms	11	42		16	23	1		1		1								
		3 Rooms	12	219		21	92	58	31	7	4	4	1	1						
		4 Rooms	13	702		5	88	179	125	124	73	76	20	5	5	2				
		5 Rooms	14	659			15	62	84	84	80	182	84	31	28	8	1			
		6 Rooms	15	409	1		6	27	33	50	27	97	77	32	47	6	6			
		7 Rooms	16	227	2			4	11	9	12	42	56	38	26	12	11	3	1	
		8 Rooms or More	17	324				3	2	8	7	51	58	56	65	35	25	10	3	
	Number of Structures by Encumbrance	X. No Report on Encumbr.	18	9	2			2		3	2									
		Total Repts on Encumbr.	19	2579	1	47	225	335	286	284	198	458	301	154	171	60	44	12	3	
		1. Mortgaged	20	715		5	51	73	87	84	67	137	105	41	49	9	5	1	1	
		2. Free of Encumbrance	21	1864	1	42	174	262	199	200	131	321	196	113	122	51	39	11	2	
2. SINGLE FAMILY ATTACHED STRUCTURES	Owner Occupied	Total Structures	22	1					1											
	Number of Structures by Condition	X. No Report on Condit'n	23																	
		Total Repts on Condit'n	24	1					1											
		1. Good Condition	25	1					1											
		2. Minor Repairs	26																	
		3. Major Repairs	27																	
		4. Unfit for Use	28																	
	Number of Structures by Number of Rooms in Structure	No Report on Rooms	29																	
		Total Repts on Rooms	30	1					1											
		1 Room	31																	
		2 Rooms	32																	
		3 Rooms	33																	
		4 Rooms	34																	
		5 Rooms	35	1					1											
		6 Rooms	36																	
		7 Rooms	37																	
		8 Rooms or More	38																	
	Number of Structures by Encumbrance	X. No Report on Encumbr.	39																	
		Total Repts on Encumbr.	40	1					1											
		1. Mortgaged	41																	
		2. Free of Encumbrance	42	1					1											
3. TWO FAMILY SIDE BY SIDE STRUCTURES	Owner Occupied	Total Structures	43	128		2	9	21	13	14	15	26	10	6	9	3				
	Number of Structures by Condition	X. No Report on Condit'n	44																	
		Total Repts on Condit'n	45	128		2	9	21	13	14	15	26	10	6	9	3				
		1. Good Condition	46	72				2	10	8	11	20	9	4	6	2				
		2. Minor Repairs	47	47		1	6	15	3	6	3	6	1	2	3	1				
		3. Major Repairs	48	9		1	3	4			1									
		4. Unfit for Use	49																	
	Number of Structures by Number of Rooms in Structure	No Report on Rooms	50																	
		Total Repts on Rooms	51	128		2	9	21	13	14	15	26	10	6	9	3				
		2-3 Rooms	52	5				2	2			1								
		4-5 Rooms	53	34		1	7	8	1	4	2	7	4							
		6-7 Rooms	54	59		1	1	10	9	7	8	14	3	4	1	1				
		8-9 Rooms	55	22			1	1	1	2	4	3	2	1	5	2				
		10-11 Rooms	56	7						1	1	1	1	1	2					
		12-13 Rooms	57	1											1					
		14-15 Rooms	58																	
		16 Rooms or More	59																	
	Number of Structures by Encumbrance	X. No Report on Encumbr.	60																	
		Total Repts on Encumbr.	61	128		2	9	21	13	14	15	26	10	6	9	3				
		1. Mortgaged	62	20		1	1	1	3	4	1	7	1			1				
		2. Free of Encumbrance	63	108		1	8	20	10	10	14	19	9	6	9	2				

8796

CITY Owensboro
STATE Kentucky
S-8-35

OWNER OCCUPIED STRUCTURES BY VALUE OF PROPERTY BY TYPE OF STRUCTURE BY CONDITION, DEBT STATUS, AND NUMBER OF ROOMS IN STRUCTURE

General Survey Tables

TABLE 4, PAGE 2 OF 2.

Owner Occupied Structures Not under Construction

Type of Structure	Number of Owner-occupied Structures by:		Line No.	Total Owner-Occupied Struct.	Number of Owner-occupied Structures by Value of Property: X. No Rept on Value	A. $499 or Less	B. $500 to 999	C. $1,000 to 1,499	D. $1,500 to 1,999	E. $2,000 to 2,499	F. $2,500 to 2,999	G. $3,000 to 3,999	H. $4,000 to 4,999	I. $5,000 to 5,999	J. $6,000 to 7,999	K. $8,000 to 9,999	L. $10000 to 14999	M. $15000 to 19999	N. $20000 to 29999	O. $30000 or More
4. TWO FAMILY TWO DECKER STRUCTURES	Owner Occupied	Total Structures	64	93				1	3	5	4	18	18	10	16	6	12			
	Number of Structures by Condition	X. No Report on Condit'n	65																	
		Total Repts on Condit'n	66	93				1	3	5	4	18	18	10	16	6	12			
		1. Good Condition	67	67					1	2	2	11	17	7	12	5	10			
		2. Minor Repairs	68	25				1	2	3	2	7	1	2	4	1	2			
		3. Major Repairs	69	1										1						
		4. Unfit for Use	70																	
	Number of Structures by Number of Rooms in Structure	No Report on Rooms	71																	
		Total Repts on Rooms	72	93				1	3	5	4	18	18	10	16	6	12			
		2-3 Rooms	73																	
		4-5 Rooms	74	6						2		3			1					
		6-7 Rooms	75	16				1			1	5	5	1	2	1				
		8-9 Rooms	76	40					3	2		9	9	5	5	3	4			
		10-11 Rooms	77	20						1	3	1	3	4	4		4			
		12-13 Rooms	78	10									1		3	2	4			
		14-16 Rooms	79	1											1					
		16 Rooms or More	80																	
	Number of Structures by Encumbrance	X. No Report on Encumbr.	81																	
		Total Repts on Encumbr.	82	93				1	3	5	4	18	18	10	16	6	12			
		1. Mortgaged	83	17						1		4	4	3	3		2			
		2. Free of Encumbrance	84	76				1	3	4	4	14	14	7	13	6	10			
5. THREE FAMILY, THREE DECKER STRUCTURES	Owner Occupied	Total Structures	85	3												2	1			
	Number of Structures by Condition	X. No Report on Condit'n	86																	
		Total Repts on Condit'n	87	3												2	1			
		1. Good Condition	88	2												1	1			
		2. Minor Repairs	89	1												1				
		3. Major Repairs	90																	
		4. Unfit for Use	91																	
	Number of Structures by Number of Rooms in Structure	No Report on Rooms	92																	
		Total Repts on Rooms	93	3												2	1			
		3-5 Rooms	94																	
		6-8 Rooms	95	1												1				
		9-11 Rooms	96																	
		12-14 Rooms	97																	
		15-17 Rooms	98	1													1			
		18-20 Rooms	99	1												1				
		21-23 Rooms	100																	
		24 Rooms or More	101																	
	Number of Structures by Encumbrance	X. No Report on Encumbr.	102																	
		Total Repts on Encumbr.	103	3												2	1			
		1. Mortgaged	104																	
		2. Free of Encumbrance	105	3												2	1			
6. FOUR FAMILY, DOUBLE TWO DECKER STRUCTURES	Owner Occupied	Total Structures	106	12							1	1			4	1	4	1		
	Number of Structures by Condition	X. No Report on Condit'n	107																	
		Total Repts on Condit'n	108	12							1	1			4	1	4	1		
		1. Good Condition	109	8							1				3		3	1		
		2. Minor Repairs	110	3											1	1	1			
		3. Major Repairs	111	1								1								
		4. Unfit for Use	112																	
	Number of Structures by Number of Rooms in Structure	No Report on Rooms	113																	
		Total Repts on Rooms	114	12							1	1			4	1	4	1		
		4-7 Rooms	115																	
		8-11 Rooms	116	1								1								
		12-16 Rooms	117	6							1				3		1	1		
		18-19 Rooms	118	5											1	1	3			
		20-23 Rooms	119																	
		24-27 Rooms	120																	
		28-31 Rooms	121																	
		32 Rooms or More	122																	
	Number of Structures by Encumbrance	X. No Report on Encumbr.	123																	
		Total Repts on Encumbr.	124	12							1	1			4	1	4	1		
		1. Mortgaged	125	3							1				1			1		
		2. Free of Encumbrance	126	9								1			3	1	4			

6794

CITY Owensboro
STATE Kentucky
8-4-35

STRUCTURES BY TYPE OF STRUCTURE, BY CONDITION, BY YEAR BUILT

General Survey Tables

TABLE 5A, ALL STRUCTURES

A complete set includes: Table 5A, All Structures; Table 5B, Non-Owner Occupied Structures; Table 5C, Owner Occupied Structures -Total; Table 5D, Owner Occupied Structures - Mortgaged; Table 5E, Owner Occupied -Free of Encumbrance; 5F, Owner Occupied Struct. -No Rept on Type Status

Condition	Structures by Year Built	Line No.	Total Structures	X. No Report on Type	1. Single Family Detached	2. Single Family Attached	3. Two Family S. by Side	4. Two Family S Decker	5. Three Family S Decker	6. Four Fam. Double 2 Decker	7. Apartment A. Total	B. 6 to 9 Units	C. 10 to 19 Units	D. 20 to 29 Units	E. 40 or more Units	8. Business with Dwelling Units	9. Other Non-Converted	10. Partially Converted	11. Completely Converted
			Number of Structures by Type of Structure																
TOTAL STRUCTURES ALL CONDITION	Total	1	7030		5492	1	476	156	4	40	8	8				244	75	457	77
	X. No Report on Yr. Built	2	3														3		
	A. 1935	3	1026		936		11	13		7	2	2				22	22	12	1
	B. 1930 - 1934	4	440		386		13	6		2						10	13	10	
	C. 1925 - 1929	5	437		394		15	5			1	1				8	3	11	
	D. 1920 - 1924	6	597		499		43	8		5	1	1				12	5	23	1
	E. 1915 - 1919	7	299		243		15	9		1						8	4	18	1
	F. 1905 - 1914	8	972		768		65	20	2	1						30	6	77	3
	G. 1895 - 1904	9	2040		1498		193	50	1	12	3	3				76	6	182	19
	H. 1885 - 1894	10	765		497		85	24	1	7	1	1				47	7	73	23
	I. 1880 - 1884	11	403		254	1	32	18		5						19	5	45	24
	J. 1879 or Before	12	48		17		4	3								12	1	6	5
X. STRUCTURES WITH NO REPORT ON CONDITION	Total	13																	
	X. No Report on Yr. Built	14																	
	A. 1935	15																	
	B. 1930 - 1934	16																	
	C. 1925 - 1929	17																	
	D. 1920 - 1924	18																	
	E. 1915 - 1919	19																	
	F. 1905 - 1914	20																	
	G. 1895 - 1904	21																	
	H. 1885 - 1894	22																	
	I. 1880 - 1884	23																	
	J. 1879 or Before	24																	
1. STRUCTURES IN GOOD CONDITION	Total	25	3703		2930		188	104	3	24	7	7				138	36	234	39
	X. No Report on Yr. Built	26	3														3		
	A. 1935	27	863		791		10	11		7	2	2				21	11	9	1
	B. 1930 - 1934	28	312		272		11	5		2						6	9	7	
	C. 1925 - 1929	29	316		285		9	5			1	1				6	1	9	
	D. 1920 - 1924	30	358		289		25	7		2	1	1				10	4	19	1
	E. 1915 - 1919	31	145		116		7	6								4	1	10	1
	F. 1905 - 1914	32	501		384		30	18	2	1						17	2	45	2
	G. 1895 - 1904	33	835		568		78	31		7	2	2				43	2	93	11
	H. 1885 - 1894	34	228		147		12	11	1	2	1	1				18	1	28	7
	I. 1880 - 1884	35	117		68		3	9		3						9	1	12	12
	J. 1879 or Before	36	25		10		3	1								4	1	2	4
2. STRUCTURES IN NEED OF MINOR REPAIRS	Total	37	2321		1829	1	189	45	1	13						64	8	144	27
	X. No Report on Yr. Built	38																	
	A. 1935	39	135		128		1	2									1	3	
	B. 1930 - 1934	40	110		103		2	1								2		2	
	C. 1925 - 1929	41	103		94		6									2		1	
	D. 1920 - 1924	42	197		178		10	1		3						2		3	
	E. 1915 - 1919	43	133		109		8	3		1						4	1	7	
	F. 1905 - 1914	44	361		297		23	2								9	3	27	
	G. 1895 - 1904	45	841		643		84	18	1	4						21	2	62	6
	H. 1885 - 1894	46	306		199		42	12		4						14	1	23	11
	I. 1880 - 1884	47	120		71	1	12	4		1						6		15	10
	J. 1879 or Before	48	15		7		1	2								4		1	
3. STRUCTURES IN NEED OF MAJOR REPAIRS	Total	49	858		628		90	6		3						40	7	73	11
	X. No Report on Yr. Built	50																	
	A. 1935	51	7		6											1			
	B. 1930 - 1934	52	8		5											2		1	
	C. 1925 - 1929	53	15		14													1	
	D. 1920 - 1924	54	33		24		8											1	
	E. 1915 - 1919	55	16		15													1	
	F. 1905 - 1914	56	105		83		11									4	1	5	1
	G. 1895 - 1904	57	324		257		27			1						12	2	24	2
	H. 1885 - 1894	58	209		136		28	1		1						15	2	21	5
	I. 1880 - 1884	59	134		88		17	5		1						3	2	16	2
	J. 1879 or Before	60	7													3		3	1
4. STRUCTURES UNFIT FOR USE	Total	61	148		105		9	1			1	1				2	24	6	
	X. No Report on Yr. Built	62																	
	A. 1935	63	21		11												10		
	B. 1930 - 1934	64	10		6												4		
	C. 1925 - 1929	65	3		1												2		
	D. 1920 - 1924	66	9		8												1		
	E. 1915 - 1919	67	5		3												2		
	F. 1905 - 1914	68	5		4		1												
	G. 1895 - 1904	69	40		30		5	1			1	1						3	
	H. 1885 - 1894	70	22		15		3										3	1	
	I. 1880 - 1884	71	32		27											1	2	2	
	J. 1879 or Before	72	1													1			

6056

CITY Owensboro
STATE Kentucky
5-4-38

STRUCTURES BY TYPE OF STRUCTURE BY CONDITION
BY EXTERIOR MATERIAL

General Survey Tables

TABLE 6
Structures not under Construction

Number of Structures by Condition	Exterior Material	Line No.	Total Structures All Types	X. No Report on Type	1. Single Family Detached	2. Single Family Attached	3. Two Family Side by Side	4. Two Family Two Decker	5. Three Family Three Decker	6. Four Family Double 2 Decker	7. Apartment A. Total	B. 5 to 9 Units	C. 10 to 19 Units	D. 20 to 39 Units	E. 40 or more Units	8. Business with Dwelling Units	9. Other Non-Converted	10. Partially Converted	11. Completely Converted
			Number of Structures by Type of Structure																
TOTAL STRUCTURES-ALL CONDITIONS	Total	1	7030		5492	1	476	156	4	40	8	8				244	75	457	77
	X. No Report on Material	2																	
	Total Reports on Material	3	7030		5492	1	476	156	4	40	8	8				244	75	457	77
	1. Wood	4	6043		4826	1	447	117	2	20	3	3				122	45	409	51
	2. Brick	5	773		511		25	35	2	18	5	5				105	11	38	23
	3. Stone	6	41		31		1	1								2	1	3	2
	4. Stucco	7	24		19			1		1							2	1	
	5. Other	8	149		105		3	2		1						15	16	6	1
X. STRUCTURES WITH NO REPORT ON CONDITION	Total	9																	
	X. No Report on Material	10																	
	Total Reports on Material	11																	
	1. Wood	12																	
	2. Brick	13																	
	3. Stone	14																	
	4. Stucco	15																	
	5. Other	16																	
1. STRUCTURES IN GOOD CONDITION	Total	17	3703		2930		188	104	3	24	7	7				138	36	234	39
	X. No Report on Material	18																	
	Total Reports on Material	19	3703		2930		188	104	3	24	7	7				138	36	234	39
	1. Wood	20	2935		2380		172	74	1	7	2	2				52	16	203	19
	2. Brick	21	607		423		13	28	2	15	5	5				71	6	27	17
	3. Stone	22	27		20		1	1								2	1		2
	4. Stucco	23	19		16			1		1							1		
	5. Other	24	115		82		2			1						13	12	4	1
2. STRUCTURES IN NEED OF MINOR REPAIRS	Total	25	2321		1829	1	189	45	1	13						64	8	144	27
	X. No Report on Material	26																	
	Total Reports on Material	27	2321		1829	1	189	45	1	13						64	8	144	27
	1. Wood	28	2171		1736	1	180	39	1	11						42	4	135	22
	2. Brick	29	121		71		8	6		2						21	3	5	5
	3. Stone	30	12		10													2	
	4. Stucco	31	4		2												1	1	
	5. Other	32	13		10		1									1		1	
3. STRUCTURES IN NEED OF MAJOR REPAIRS	Total	33	858		628		90	6		3						40	7	73	11
	X. No Report on Material	34																	
	Total Reports on Material	35	858		628		90	6		3						40	7	73	11
	1. Wood	36	806		611		86	3		2						26	3	65	10
	2. Brick	37	41		13		4	1		1						13	2	6	1
	3. Stone	38	1															1	
	4. Stucco	39																	
	5. Other	40	10		4			2								1	2	1	
4. STRUCTURES UNFIT FOR USE	Total	41	148		105		9	1			1	1				2	24	6	
	X. No Report on Material	42																	
	Total Reports on Material	43	148		105		9	1			1	1				2	24	6	
	1. Wood	44	131		90		9	1			1	1				2	22	6	
	2. Brick	45	4		4														
	3. Stone	46	1		1														
	4. Stucco	47	1		1														
	5. Other	48	11		9												2		

5008 Rev. 6/9/38

CITY Owensboro

STATE Kentucky

DWELLING UNITS BY TYPE OF STRUCTURE BY NUMBER OF PERSONS PER ROOM BY NUMBER OF CHILDREN

General Survey Tables

TABLE 7A, All Occupied Units

Dwelling Units not under Construction

A complete set of tables includes: Table 7A, All Occupied Units; Table 7B, Owner Occupied Units; Table 7C, Tenant Occupied Units.

Persons per Room	Dwelling Units by Number of Children	Line No.	Total	Number of Dwelling Units by Type of Structure: X. No Report on Type	1. Single Family Detached	2. Single Family Attached	3. Two Family S. by Side	4. Two Family I Decker	5. Three Family I Decker	6. 4 Fam. Double I Decker	7. Apartment: A. Total	B. 5 to 9 Units	C. 10 to 19 Units	D. 20 to 39 Units	E. 40 or More	F. Business with Residential	G. Other Non-Converted	10. Par'lly Converted	11. Completely Converted
TOTAL - ALL PERSONS PER ROOM GROUPS	Total All Units	1	8468		5375	1	934	301	11	146	41	41				336	100	989	234
	No Report on Children	2																	
	Total Repts. on Children	3	8468		5375	1	934	301	11	146	41	41				336	100	989	234
	No Children	4	4505		2587	1	508	198	9	102	26	26				216	73	619	166
	1 Child	5	1835		1192		220	55	1	30	7	7				65	10	219	36
	2 Children	6	1105		795		118	35	1	11	4	4				23	11	88	19
	3 or 4 Children	7	801		615		70	12		3	4	4				27	5	54	11
	5 Children or More	8	222		186		18	1								5	1	9	2
X. NO REPORT ON PERSONS PER ROOM	Total All Units	9																	
	No Report on Children	10																	
	Total Repts. on Children	11																	
	No Children	12																	
	1 Child	13																	
	2 Children	14																	
	3 or 4 Children	15																	
	5 Children or More	16																	
A. UNITS WITH .50 PERSONS PER ROOM OR LESS	Total All Units	17	2023		1397		156	100	7	39	12	12				61	14	175	62
	No Report on Children	18																	
	Total Repts. on Children	19	2023		1397		156	100	7	39	12	12				61	14	175	62
	No Children	20	1866		1251		154	98	7	39	12	12				58	14	171	62
	1 Child	21	130		120		2	2								2		4	
	2 Children	22	25		24											1			
	3 or 4 Children	23	1		1														
	5 Children or More	24	1		1														
B. UNITS WITH .51 TO .75 PERSONS PER ROOM	Total All Units	25	2014		1338	1	193	92	1	47	7	7				77	10	211	37
	No Report on Children	26																	
	Total Repts. on Children	27	2014		1338	1	193	92	1	47	7	7				77	10	211	37
	No Children	28	1310		768	1	152	63	1	33	6	6				60	8	183	35
	1 Child	29	582		463		37	25		14	1	1				15		25	2
	2 Children	30	96		83		2	4								2	2	3	
	3 or 4 Children	31	25		23		2												
	5 Children or More	32	1		1														
C. UNITS WITH .76 TO 1.00 PERSONS PER ROOM	Total All Units	33	2106		1211		249	73	1	39	12	12				102	39	311	69
	No Report on Children	34																	
	Total Repts. on Children	35	2106		1211		249	73	1	39	12	12				102	39	311	69
	No Children	36	1004		405		154	33		27	8	8				73	32	218	54
	1 Child	37	606		380		82	19	1	7	3	3				19	5	77	13
	2 Children	38	382		320		12	18		5	1	1				8	2	14	2
	3 or 4 Children	39	111		103		1	3								2		2	
	5 Children or More	40	3		3														
D. UNITS WITH 1.01 TO 1.50 PERSONS PER ROOM	Total All Units	41	1264		773		188	26	1	17	5	5				48	10	159	37
	No Report on Children	42																	
	Total Repts. on Children	43	1264		773		188	26	1	17	5	5				48	10	159	37
	No Children	44	217		123		34	4		2						15	3	28	8
	1 Child	45	387		170		70	7		8	3	3				16	4	91	18
	2 Children	46	377		240		74	8	1	4	2	2				6	3	31	8
	3 or 4 Children	47	253		210		10	7		3						11		9	3
	5 Children or More	48	30		30														
E. UNITS WITH 1.51 TO 2.00 PERSONS PER ROOM	Total All Units	49	728		456		99	8	1	3	3	3				28	17	91	22
	No Report on Children	50																	
	Total Repts. on Children	51	728		456		99	8	1	3	3	3				28	17	91	22
	No Children	52	98		35		13		1	1						8	14	19	7
	1 Child	53	93		51		19	2								6	1	12	2
	2 Children	54	195		111		27	5		2	1	1				5	2	35	7
	3 or 4 Children	55	279		205		38				2	2				6		23	5
	5 Children or More	56	63		54		2	1								3		2	1
F. UNITS WITH 2.01 PERSONS PER ROOM OR MORE	Total All Units	57	333		200		49	2		1	2	2				20	10	42	7
	No Report on Children	58																	
	Total Repts. on Children	59	333		200		49	2		1	2	2				20	10	42	7
	No Children	60	10		5		1									2	2		
	1 Child	61	37		8		10			1						7		10	1
	2 Children	62	30		17		3									1	2	5	2
	3 or 4 Children	63	132		73		19	2			2	2				8	5	20	3
	5 Children or More	64	124		97		16									2	1	7	1

1920

CITY Owensboro

STATE Kentucky

DWELLING UNITS BY TYPE OF STRUCTURE BY CONDITION BY DURATION OF OCCUPANCY

General Survey Tables

TABLE 8 A, All Occupied Units

Dwelling Units not under Construction

A complete set of tables includes: Table 8A, All Occupied Units; Table 8B, Owner Occupied Units; Table 8C, Tenant Occupied Units.

Number of Dwelling Units by Condition	Duration of Occupancy	Line No.	Total	X. No Report on Type	1. Single Family Detached	2. Single Family Attached	3. Two Family S. by Side	4. Two Family S Decker	5. Three Family S Decker	6. 4 Fam. Double S Decker	7. Apartment A. Total	B. 5 to 9 Units	C. 10 to 19 Units	D. 20 to 39 Units	E. 40 or More	8. Remodeled with Residential	9. Other Non-Converted	10. Par'lly Converted	11. Compl'ly Converted
			Number of Dwelling Units by Type of Structure																
TOTAL UNITS - ALL CONDITION GROUPS	Total All Units	1	8468		5375	1	934	301	11	146	41	41				336	100	989	234
	X. No Report on Duration	2	1														1		
	Total Repts on Duration	3	8467		5375	1	934	301	11	146	41	41				336	99	989	234
	A. Less than 6 Months	4	1387		662		193	50	3	57	12	12				57	33	261	59
	B. 6 Mos. - 11 Months	5	778		412		107	31	2	22	7	7				44	10	111	32
	C. 1 Year - 1 Yr. 11 Mos	6	1281		796		188	28	2	21	5	5				47	16	143	35
	D. 2 Years - 2 Yrs. 11 Mos	7	877		533		117	37		14	6	6				43	11	91	25
	E. 3 Years - 4 Yrs. 11 Mos	8	1134		740		127	40	1	11	1	1				52	12	117	33
	F. 5 Years - 9 Yrs. 11 Mos	9	1161		839		88	44		14	5	5				48	8	97	18
	G. 10 Years - 19 Yrs. 11 Mos	10	1095		832		72	37		3	4	4				30	6	92	19
	H. 20 Years or More	11	754		561	1	42	34	3	4	1	1				15	3	77	13
X. UNITS WITH NO REPORT ON CONDITION	Total All Units	12																	
	X. No Report on Duration	13																	
	Total Repts on Duration	14																	
	A. Less than 6 Months	15																	
	B. 6 Mos. - 11 Months	16																	
	C. 1 Year - 1 Yr. 11 Mos	17																	
	D. 2 Years - 2 Yrs. 11 Mos	18																	
	E. 3 Years - 4 Yrs. 11 Mos	19																	
	F. 5 Years - 9 Yrs. 11 Mos	20																	
	G. 10 Years - 19 Yrs. 11 Mos	21																	
	H. 20 Years or More	22																	
1. UNITS IN GOOD CONDITION	Total All Units	23	4449		2866		368	195	9	88	36	36				184	47	506	120
	X. No Report on Duration	24	1														1		
	Total Repts on Duration	25	4448		2866		368	195	9	88	36	36				184	146	506	120
	A. Less than 6 Months	26	729		362		79	32	2	37	8	8				38	18	120	33
	B. 6 Mos. - 11 Months	27	398		221		43	18	2	13	7	7				24	5	51	14
	C. 1 Year - 1 Yr. 11 Mos	28	671		432		77	19	2	15	4	4				28	6	74	14
	D. 2 Years - 2 Yrs. 11 Mos	29	444		274		44	27		8	6	6				19	5	48	13
	E. 3 Years - 4 Yrs. 11 Mos	30	561		374		50	22	1	4	1	1				25	5	62	17
	F. 5 Years - 9 Yrs. 11 Mos	31	573		442		33	30		6	5	5				26	3	48	10
	G. 10 Years - 19 Yrs. 11 Mos	32	638		487		32	24		2	4	4				16	3	60	10
	H. 20 Years or More	33	404		304		10	23	2	3	1	1				8	1	43	9
2. UNITS NEEDING MINOR REPAIRS	Total All Units	34	2800		1802	1	370	90	2	46						87	13	308	81
	X. No Report on Duration	35																	
	Total Repts on Duration	36	2800		1802	1	370	90	2	46						87	13	308	81
	A. Less than 6 Months	37	444		215		78	16	1	17						8	6	86	17
	B. 6 Mos. - 11 Months	38	248		125		46	12		5						10		37	13
	C. 1 Year - 1 Yr. 11 Mos	39	411		267		62	8		5						9		44	16
	D. 2 Years - 2 Yrs. 11 Mos	40	293		184		43	10		5						15	1	27	8
	E. 3 Years - 4 Yrs. 11 Mos	41	386		262		46	11		6						20	2	27	12
	F. 5 Years - 9 Yrs. 11 Mos	42	413		304		37	12		7						11	1	34	7
	G. 10 Years - 19 Yrs. 11 Mos	43	359		268		32	11								12	2	27	7
	H. 20 Years or More	44	246		177	1	26	10	1	1						2	1	25	2
3. UNITS NEEDING MAJOR REPAIRS	Total All Units	45	1101		620		180	14		12						63	15	164	33
	X. No Report on Duration	46																	
	Total Repts on Duration	47	1101		620		180	14		12						63	15	164	33
	A. Less than 6 Months	48	181		68		32	2		3						11	15	51	9
	B. 6 Mos. - 11 Months	49	119		58		17	1		4						10	2	21	6
	C. 1 Year - 1 Yr. 11 Mos	50	172		84		45	1		1						10	3	23	5
	D. 2 Years - 2 Yrs. 11 Mos	51	126		71		26			1						9		15	4
	E. 3 Years - 4 Yrs. 11 Mos	52	163		89		28	6		1						7	2	26	4
	F. 5 Years - 9 Yrs. 11 Mos	53	160		111		18	2		1						10	2	15	1
	G. 10 Years - 19 Yrs. 11 Mos	54	86		68		8	1		1						1		5	2
	H. 20 Years or More	55	94		71		6	1								5	1	8	2
4. UNITS UNFIT FOR USE	Total All Units	56	148		87		16	2			5	5				2	25	11	
	X. No Report on Duration	57																	
	Total Repts on Duration	58	148		87		16	2			5	5				2	25	11	
	A. Less than 6 Months	59	33		17		4				4	4					4	4	
	B. 6 Mos. - 11 Months	60	13		8		1										3	1	
	C. 1 Year - 1 Yr. 11 Mos	61	27		13		4				1	1					7	2	
	D. 2 Years - 2 Yrs. 11 Mos	62	14		4		4										5	1	
	E. 3 Years - 4 Yrs. 11 Mos	63	23		15		3	1									3	1	
	F. 5 Years - 9 Yrs. 11 Mos	64	16		12											1	2	1	
	G. 10 Years - 19 Yrs. 11 Mos	65	12		9			1								1	1		
	H. 20 Years or More	66	10		9													1	

CITY Owensboro
STATE Kentucky
5-4-56

DWELLING UNITS BY NUMBER OF PERSONS IN UNIT BY TYPE OF STRUCTURE, HEATING EQUIPMENT, LIGHTING EQUIPMENT COOKING EQUIPMENT, REFRIGERATION EQUIPMENT, NUMBER OF ROOMERS, NUMBER OF PERSONS PER ROOM, AND PLUMBING EQUIPMENT
General Survey Tables

TABLE 9 A, All Occupied Units
Units not Under Construction
A complete set of tables includes: Table 9A, All Occupied Units; Table 9B, Owner Occupied Units; Table 9C, Tenant Occupied Units.

Number of Dwelling Units By:	Line No.	Total Number of Units	X. No Report on Persons	1 Person	2 Persons	3 Persons	4 Persons	5 Persons	6 Persons	7 Persons	8 Persons	9 Persons	10 Persons	11 Persons or More	Tot. No. of Per. in Units with 11 or more Persons
			Number of Dwelling Units by Number of Persons in Unit												
TOTAL NUMBER OF DWELLING UNITS	1	8468		520	2393	1979	1540	884	517	265	176	85	52	57	696
NUMBER OF UNITS BY TYPE OF STRUCTURE: X. No Report on Type	2														
Total Reports on Type	3	8468		520	2393	1979	1540	884	517	265	176	85	52	57	696
1. Single Family Detached	4	5375		172	1263	1245	1071	671	421	217	147	71	47	50	591
2. Single Family Attached	5	1				1									
3. Two Family Side by Side	6	934		88	317	223	165	74	29	17	13	5	1	2	23
4. Two Family Two Decker	7	301		15	112	78	58	26	7	3	1	1			
5. Three Family Three Decker	8	11		1	7		1	2							
6. Four Family Double Two Decker	9	146		15	68	36	22	3	2						
7. Apartment Units: Total	10	41		7	13	11	6	1	1	1		1			
8 - 9 Units	11	41		7	13	11	6	1	1	1		1			
10 - 19 Units	12														
20 - 39 Units	13														
40 Units or More	14														
8. Business with Dwelling Units	15	336		34	120	71	46	26	19	10	3	2	2	3	55
9. Other Non-Converted	16	100		27	35	15	12	5	4	1	1				
10. Partially Converted	17	989		122	372	252	125	65	27	13	8	3	1	1	11
11. Completely Converted	18	234		39	86	47	34	11	7	3	3	2	1	1	16
NUMBER OF UNITS BY HEATING EQUIPMENT: X. No Report on Heating	19														
Total Reports on Heating	20	8468		520	2393	1979	1540	884	517	265	176	85	52	57	696
1. Central Steam or Hot Water	21	802		69	243	201	158	62	37	12	9	2	2	7	107
2. Central Warm Air	22	1608		59	486	440	321	149	69	30	26	12	8	8	96
3. Other Installed	23	2945		184	822	654	517	328	199	98	64	37	23	19	217
4. None Installed	24	3113		208	842	684	544	345	212	125	77	34	19	23	274
NUMBER OF UNITS BY LIGHTING EQUIPMENT: X. No Report on Lighting	25	1			1										
Total Reports on Lighting	26	8467		520	2392	1979	1540	884	517	265	176	85	52	57	696
1. Electric	27	8042		458	2267	1890	1491	854	484	247	170	79	47	55	672
2. Gas	28	10			3	3	1	1		1			1		
3. Other	29	415		62	122	86	48	29	33	17	6	6	4	2	24
NUMBER OF UNITS BY COOKING EQUIPMENT: X. No Report on Cooking	30	5			1	1	2			1					
Total Reports on Cooking	31	8463		520	2392	1978	1538	884	517	264	176	85	52	57	696
1. Electric	32	94		10	19	26	21	7	6	2	2	1			
2. Gas	33	2956		142	967	767	534	257	136	54	43	24	13	19	247
3. Other Installed	34	1898		113	514	431	352	210	126	67	34	20	19	12	135
4. None Installed	35	3515		255	892	754	631	410	249	141	97	40	20	26	314
NUMBER OF UNITS BY REFRIGERATION EQUIPMENT: X. No Report on Refrigeration	36	3			1				1	1					
Total Reports on Refrigeration	37	8465		520	2392	1979	1540	884	516	264	176	85	52	57	696
1. Electric	38	3377		133	1005	915	643	330	157	74	50	29	18	23	282
2. Gas	39	105		5	30	22	24	11	9	3				1	11
3. Ice	40	3506		190	942	774	645	402	246	127	84	43	31	22	257
4. None	41	1477		192	415	268	228	141	104	60	42	13	3	11	146
NUMBER OF UNITS BY NUMBER OF ROOMERS IN UNIT: No Report on Roomers	42	7			6				1						
Total Reports on Roomers	43	8461		520	2387	1979	1540	884	516	265	176	85	52	57	696
No Roomers	44	7996		520	2362	1894	1438	796	465	236	132	66	45	42	483
1 Roomer	45	270			24	72	71	60	17	10	10	5	1		
2 Roomers	46	80			1	12	24	9	14	6	11	2		1	11
3 Roomers	47	30				1	4	10	7	3	3	1	1		
4 Roomers	48	40					3	9	10	4	11	2		1	13
5 Roomers	49	18							3	5	6	2		2	23
6 Roomers	50	7								1	2	3	1		
7 Roomers	51	6									1	4	1		
8 Roomers	52	4											3	1	16
9 Roomers	53	2												2	22
10 Roomers	54	4												4	59
11 Roomers or More	55	4												4	69
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED FROM RENT BY ROOM BY PERSONS ON TABLE: X. No Report on Persons per Room	56														
Total Reports on Persons per Room	57	8468		520	2393	1979	1540	884	517	265	176	85	52	57	696
A. .80 or Less	58	2023		425	1171	316	94	11	3		2	1			
B. .81 to .75	59	2014			717	895	249	107	35	6		5			
C. .76 to 1.00	60	2106		95	449	502	652	252	93	33	23	3	2	2	28
D. 1.01 to 1.50	61	1264			5	236	406	233	238	76	27	22	10	11	127
E. 1.51 to 2.00	62	728			51	5	131	231	124	65	72	17	20	12	152
F. 2.01 or More	63	333				25	8	50	24	85	52	37	20	32	387
NUMBER OF UNITS BY PLUMBING EQUIPMENT: X. No Report on Plumbing	64														
Total Reports on Plumbing	65	8468		520	2393	1979	1540	884	517	265	176	85	52	57	696
A. At least 2 Toilets & 2 Bath. Units	66	113		5	19	14	21	17	15	5	5	4	2	6	88
B. At least 2 Toilets & 1 Bath. Units	67	28			3	5	7	3	5	1	1	2		1	11
C. 1 Toilet & at least 1 Bath. Unit	68	4215		150	1181	1095	833	440	226	122	77	36	26	29	349
D. At least 1 Toilet Less than 1 Bath	69	1459		144	501	385	204	126	68	30	23	14	2	2	22
E. Shared Toilet and Running Water	70	61		6	21	19	8	3	1	2	1				
F. Shared Toilet but no Running Wat.	71	89		13	24	13	20	7	9	2				1	20
G. No Toilet but with Running Water	72	692		38	173	144	131	79	48	32	20	10	10	7	81
H. No Toilet and No Running Water	73	1811		164	471	344	316	209	145	71	49	19	12	11	125

P840

CITY Owensboro
STATE Kentucky
5-4-38

DWELLING UNITS BY NUMBER OF PERSONS IN UNIT BY TYPE OF STRUCTURE, HEATING EQUIPMENT, LIGHTING EQUIPMENT COOKING EQUIPMENT, REFRIGERATION EQUIPMENT, NUMBER OF ROOMERS, NUMBER OF PERSONS PER ROOM, AND PLUMBING EQUIPMENT
General Survey Tables

TABLE 9B, Owner Occupied Units
Units not under Construction
A complete set of tables includes Table 9A, All Occupied Units; Table 9B, Owner Occupied Units; Table 9C, Tenant Occupied Units.

Number of Dwelling Units By:	Line No.	Total Number of Units	X. No Report on Persons	1 Person	2 Persons	3 Persons	4 Persons	5 Persons	6 Persons	7 Persons	8 Persons	9 Persons	10 Persons	11 Persons or More	Tot. No. of Per. in Units with 11 or more Persons
			Number of Dwelling Units by Number of Persons in Unit												
TOTAL NUMBER OF DWELLING UNITS	1	3201		227	927	763	585	312	195	78	50	28	18	18	221
NUMBER OF UNITS BY TYPE OF STRUCTURE: X. No Report on Type	2														
Total Reports on Type	3	3201		227	927	763	585	312	195	78	50	28	18	18	221
1. Single Family Detached	4	2588		95	701	638	523	284	176	67	48	23	17	16	194
2. Single Family Attached	5	1				1									
3. Two Family Side by Side	6	128		30	55	24	10	3	1	3		2			
4. Two Family Two Decker	7	93		9	33	24	12	9	5			1			
5. Three Family Three Decker	8	3		1				2							
6. Four Family Double Two Decker	9	12		3	5	2	2								
7. Apartment Units: Total	10	5		2	1	1				1					
6 - 9 Units	11	5		2	1	1				1					
10 - 19 Units	12														
20 - 39 Units	13														
40 Units or More	14														
8. Business with Dwelling Units	15	89		7	33	20	13	4	7	4	1				
9. Other Non-Converted	16	24		7	11	4			1	1					
10. Partially Converted	17	225		64	78	44	21	9	5	2		1		1	11
11. Completely Converted	18	33		9	10	5	4	1			1	1	1	1	16
NUMBER OF UNITS BY HEATING EQUIPMENT: X. No Report on Heating	19														
Total Reports on Heating	20	3201		227	927	763	585	312	195	78	50	28	18	18	221
1. Central Steam or Hot Water	21	407		27	93	105	95	43	24	7	6	2	2	3	43
2. Central Warm Air	22	958		37	260	259	206	99	47	19	16	8	3	4	50
3. Other Installed	23	1481		125	454	326	234	147	98	40	24	13	12	8	91
4. None Installed	24	355		38	120	73	50	23	26	12	4	5	1	3	37
NUMBER OF UNITS BY LIGHTING EQUIPMENT: X. No Report on Lighting	25	1					1								
Total Reports on Lighting	26	3200		227	927	763	584	312	195	78	50	28	18	18	221
1. Electric	27	3099		208	894	744	574	305	186	74	50	28	18	18	221
2. Gas	28	5			2	1		1		1					
3. Other	29	96		19	31	18	10	6	9	3					
NUMBER OF UNITS BY COOKING EQUIPMENT: X. No Report on Cooking	30	2				1	1								
Total Reports on Cooking	31	3199		227	927	762	584	312	195	78	50	28	18	18	221
1. Electric	32	62		6	12	14	16	6	4	2	1	1			
2. Gas	33	1484		78	424	385	289	142	81	30	22	15	9	9	118
3. Other Installed	34	1287		90	367	295	228	140	89	34	20	10	8	6	66
4. None Installed	35	366		53	124	68	51	24	21	12	7	2	1	3	37
NUMBER OF UNITS BY REFRIGERATION EQUIPMENT: X. No Report on Refrigeration	36														
Total Reports on Refrigeration	37	3201		227	927	763	585	312	195	78	50	28	18	18	221
1. Electric	38	1813		71	498	484	370	187	98	36	31	16	11	11	140
2. Gas	39	61		3	18	17	7	5	7	3				1	11
3. Ice	40	1066		101	322	229	185	98	66	26	16	11	7	5	57
4. None	41	261		52	89	33	23	22	24	13	3	1		1	13
NUMBER OF UNITS BY NUMBER OF ROOMERS IN UNIT: No Report on Roomers	42														
Total Reports on Roomers	43	3201		227	927	763	585	312	195	78	50	28	18	18	221
No Roomers	44	2999		227	915	721	543	272	172	65	35	20	16	13	149
1 Roomer	45	113			11	35	29	24	7	4	3				
2 Roomers	46	36			1	7	11	5	6	2	2	1		1	11
3 Roomers	47	11					2	7	2						
4 Roomers	48	20						4	5	3	5	2		1	13
5 Roomers	49	11							3	3	3	2			
6 Roomers	50	3								1	1	1			
7 Roomers	51	4									1	2	1		
8 Roomers	52	1											1		
9 Roomers	53														
10 Roomers	54	2												2	27
11 Roomers or More	55	1												1	21
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED FROM RENT BY ROOM BY PERSONS ON TABLE: X. No Report on Persons per Room	56														
Total Reports on Persons per Room	57	3201		227	927	763	585	312	195	78	50	28	18	18	221
A. .50 or Less	58	1284		201	739	249	82	9	3			1			
B. .51 to .75	59	851			135	423	180	80	27	3		3			
C. .76 to 1.00	60	637		26	42	73	272	128	54	19	18	3	2		
D. 1.01 to 1.50	61	276				15	37	71	93	29				7	59
E. 1.51 to 2.00	62	113			11	1	14	22	17	12	15	6	8	7	94
F. 2.01 or More	63	40				2		2	1	15	5	6	3	6	68
NUMBER OF UNITS BY PLUMBING EQUIPMENT: X. No Report on Plumbing	64														
Total Reports on Plumbing	65	3201		227	927	763	585	312	195	78	50	28	18	18	221
A. At least 2 Toilets & 2 Bath. Units	66	91		5	17	12	20	11	12	5	4	3		2	34
B. At least 2 Toilets & 1 Bath. Unit	67	20			3	5	5	2	4			1			
C. 1 Toilet & at least 1 Bath. Unit	68	2160		87	613	570	434	227	114	44	33	15	12	11	130
D. At least 1 Toilet Less than 1 Bath	69	293		59	98	58	28	21	16	6	1	4	1	1	11
E. Shared Toilet and Running Water	70	9		3	3	2									
F. Shared Toilet but no Running Wat.	71	3		1	1	1									
G. No Toilet but with Running Water	72	221		18	65	40	37	19	22	6	6	3	3	2	24
H. No Toilet and No Running Water	73	404		54	127	75	61	32	27	16	6	2	2	2	22

7940

CITY: Owensboro
STATE: Kentucky
5-4-38

DWELLING UNITS BY NUMBER OF PERSONS IN UNIT BY TYPE OF STRUCTURE, HEATING EQUIPMENT, LIGHTING EQUIPMENT, COOKING EQUIPMENT, REFRIGERATION EQUIPMENT, NUMBER OF ROOMERS, NUMBER OF PERSONS PER ROOM, AND PLUMBING EQUIPMENT
General Survey Tables

TABLE 9 C, Tenant Occupied Units

Units not under Construction
A complete set of tables includes: Table 9A, All Occupied Units; Table 9B, Owner Occupied Units; Table 9C, Tenant Occupied Units.

Number of Dwelling Units By:	Line No.	Total Number of Units	X. No Report on Persons	1 Person	2 Persons	3 Persons	4 Persons	5 Persons	6 Persons	7 Persons	8 Persons	9 Persons	10 Persons	11 Persons or More	Tot. No. of Per. in Units with 11 or more Persons
			Number of Dwelling Units by Number of Persons in Unit												
TOTAL NUMBER OF DWELLING UNITS	1	5267		293	1466	1216	955	572	322	187	126	57	34	39	475
NUMBER OF UNITS BY TYPE OF STRUCTURE: X. No Report on Type	2														
Total Reports on Type	3	5267		293	1466	1216	955	572	322	187	126	57	34	39	475
1. Single Family Detached	4	2787		77	562	607	548	387	245	150	99	48	30	34	397
2. Single Family Attached	5														
3. Two Family Side by Side	6	806		58	262	199	155	71	28	14	13	3	1	2	23
4. Two Family Two Decker	7	208		6	79	54	46	17	2	3	1				
5. Three Family Three Decker	8	8			7		1								
6. Four Family Double Two Decker	9	134		12	63	34	26	3	2						
7. Total Apartments	10	36		5	12	10	6	1	1			1			
8 - 9 Units	11	36		5	12	10	6	1	1			1			
10 - 19 Units	12														
20 - 39 Units	13														
40 Units or More	14														
8. Business with Dwelling Units	15	247		27	87	51	33	22	12	6	2	2	2	3	55
9. Other Non-Converted	16	76		20	24	11	12	5	3		1				
10. Partially Converted	17	764		58	294	208	104	56	22	11	8	2	1		
11. Completely Converted	18	201		30	76	42	30	10	7	3	2	1			
NUMBER OF UNITS BY HEATING EQUIPMENT: X. No Report on Heating	19														
Total Reports on Heating	20	5267		293	1466	1216	955	572	322	187	126	57	34	39	475
1. Central Steam or Hot Water	21	395		42	150	96	63	19	13	5	3			4	60
2. Central Warm Air	22	650		20	227	182	114	51	22	11	10	4	5	4	46
3. Other Installed	23	1464		59	386	328	283	181	101	58	41	23	11	11	132
4. None Installed	24	2758		172	721	610	495	321	186	113	72	30	18	20	237
NUMBER OF UNITS BY LIGHTING EQUIPMENT: X. No Report on Lighting	25	1			1										
Total Reports on Lighting	26	5266		293	1465	1216	955	572	322	187	126	57	34	39	475
1. Electric	27	4942		249	1373	1146	916	550	297	174	120	51	29	37	451
2. Gas	28	5			1	2	1						1		
3. Other	29	319		44	91	68	38	22	25	13	6	6	4	2	24
NUMBER OF UNITS BY COOKING EQUIPMENT: X. No Report on Cooking	30	3			1		1			1					
Total Reports on Cooking	31	5264		293	1465	1216	954	572	322	186	126	57	34	39	475
1. Electric	32	32		4	7	12	5	1	2		1				
2. Gas	33	1472		64	543	382	245	115	55	24	21	9	4	10	129
3. Other Installed	34	611		23	147	137	124	70	37	33	13	10	11	6	70
4. None Installed	35	3149		202	768	685	580	386	228	129	91	38	19	23	276
NUMBER OF UNITS BY REFRIGERATION EQUIPMENT: X. No Report on Refrigeration	36	3			1				1	1					
Total Reports on Refrigeration	37	5264		293	1465	1216	955	572	321	186	126	57	34	39	475
1. Electric	38	1564		62	507	431	273	143	59	38	19	13	7	12	148
2. Gas	39	44		2	12	5	17	6	2						
3. Ice	40	2440		89	620	545	460	304	180	101	68	32	24	17	202
4. None	41	1216		140	326	235	205	119	80	47	39	12	3	10	123
NUMBER OF UNITS BY NUMBER OF ROOMERS IN UNIT: No Report on Roomers	42	7			6				1						
Total Reports on Roomers	43	5260		293	1460	1216	955	572	321	187	126	57	34	39	475
No Roomers	44	4997		293	1447	1175	894	523	292	171	98	46	29	29	835
1 Roomer	45	157			13	37	42	36	10	6	7	5	1		
2 Roomers	46	44				4	14	4	8	4	9	1			
3 Roomers	47	19					2	4	5	3	3	1	1		
4 Roomers	48	20					3	5	5	1	6				
5 Roomers	49	7							1	2	2			2	23
6 Roomers	50	4									1	2	1		
7 Roomers	51	2										2			
8 Roomers	52	3											2	1	16
9 Roomers	53	2												2	22
10 Roomers	54	2												2	32
11 Roomers or More	55	3												3	47
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED FROM RENT BY ROOM BY PERSONS ON TABLE): X. No Report on Persons per Room	56														
Total Reports on Persons per Room	57	5267		293	1466	1216	955	572	322	187	126	57	34	39	475
A. .50 or Less	58	739		224	432	67	12	2			2				
B. .51 to .75	59	1163			582	472	69	27	8	3		2			
C. .76 to 1.00	60	1469		69	407	429	380	124	39	14	5			2	28
D. 1.01 to 1.50	61	988			5	221	369	162	145	47	15	13	5	6	68
E. 1.51 to 2.00	62	615			40	4	117	209	107	53	57	11	12	5	58
F. 2.01 or More	63	293				23	8	48	23	70	47	31	17	26	221
NUMBER OF UNITS BY PLUMBING EQUIPMENT: X. No Report on Plumbing	64														
Total Reports on Plumbing	65	5267		293	1466	1216	955	572	322	187	126	57	34	39	475
A. At least 2 Toilets & 2 Bath. Units	66	22			2	2	1	6	3		1	1	2	4	54
B. At least 2 Toilets & 2 Bath. Units	67	8					2	1	1	1	1	1		1	11
C. 1 Toilet & at least 1 Bath. Unit	68	2055		63	568	525	399	213	112	78	44	21	14	18	215
D. At least 1 Toilet Less than 1 Bath	69	1166		85	404	287	176	105	52	23	22	10	1	1	11
E. Shared Toilet and Running Water	70	52		3	18	17	8	3	1	1	1			1	20
F. Shared Toilet but no Running Wat.	71	86		12	22	12	20	7	9	3				5	57
G. No Toilet but with Running Water	72	471		20	108	104	94	60	26	26	14	7	7	7	107
H. No Toilet and No Running Water	73	1407		110	344	269	255	177	118	55	43	17	10	7	107

T940

CITY Owensboro
STATE Kentucky
5-4-35

DWELLING UNITS BY MONTHLY RENT BY PLUMBING EQUIPMENT, HEATING EQUIPMENT, LIGHTING EQUIPMENT, REFRIGERATION EQUIPMENT, YEAR BUILT, NUMBER OF ROOMERS, AND RACE OF HOUSEHOLD
General Survey Tables

TABLE 10 A, all Dwelling Units
Units not under Construction
A Complete set of tables includes: Table 10A, All Dwelling Units; Table 10B, Owner Occupied Units; Table 10C, Tenant Occupied Units; Table 10D, Vacant Units

Number of Dwelling Units By:		Line No.	Total All Units	Number of Dwelling Units by Monthly Rent: X. No Report on Rent	A. $4.99 and Less	B. $5.00 to $9.99	C. $10.00 to $14.99	D. $15.00 to $19.99	E. $20.00 to $24.99	F. $25.00 to $29.99	G. $30.00 to $39.99	H. $40.00 to $49.99	I. $50.00 to $74.99	J. $75.00 to $99.99	K. $100.00 to $149.99	L. $150.00 and Over
TOTAL NUMBER OF DWELLING UNITS		1	8721	46	152	1548	2158	1237	843	612	1084	573	386	64	16	2
NUMBER OF UNITS BY PLUMBING EQUIPMENT	X. No Report on Plumbing	2	1				1									
	Total Reports on Plumbing	3	8720	46	152	1548	2157	1237	843	612	1084	573	386	64	16	2
	A. At Least 2 Toilets & 2 Bathing Units	4	114	2		1	1		1	1	12	31	45	18	2	
	B. At Least 2 Toilets & 1 Bathing Unit	5	28							1	2	10	12	3		
	C. 1 Toilet and at Least 1 Bath. Unit	6	4361	14	3	40	514	762	662	503	971	514	320	42	14	2
	D. At least 1 Toilet Less than 1 Bath	7	1512	2	17	276	629	276	133	75	79	16	8	1		
	E. Shared Toilet & Running Water	8	61		6	16	26	8	1	2	2					
	F. Shared Toilet but No Running Water	9	94		11	47	33	2	1							
	G. No Toilet but with Running Water	10	698	2	12	229	320	93	22	13	7					
	H. No Toilet and No Running Water	11	1852	26	103	939	634	96	23	17	11	2	1			
NUMBER OF UNITS BY HEATING EQUIPMENT	X. No Report on Heating	12	6	4			1	1								
	Total Reports on Heating	13	8715	42	152	1548	2157	1236	843	612	1084	573	386	64	16	2
	1. Central Steam or Hot Water	14	844	1		10	51	55	99	96	240	155	107	25	5	
	2. Central Warm Air	15	1676	7	1	11	53	84	141	197	567	338	235	31	9	2
	3. Other Installed	16	2994	11	32	476	903	642	379	227	213	61	40	8	2	
	4. None Installed	17	3201	23	119	1051	1150	455	224	92	64	19	4			
NUMBER OF UNITS BY LIGHTING EQUIPMENT	X. No Report on Lighting	18	7		1	1	3	2								
	Total Reports on Lighting	19	8714	45	152	1547	2155	1235	843	612	1084	573	386	64	16	2
	1. Electric	20	8270	34	90	1286	2081	1220	836	605	1080	571	385	64	16	2
	2. Gas	21	10				1	1	2	2	3	1				
	3. Other	22	434	11	62	26	73	14	5	5	1	1	1			
NUMBER OF UNITS BY COOKING EQUIPMENT	X. No Report on Cooking	23	28	4		4	5	8	1	2	3		1			
	Total Reports on Cooking	24	8693	42	152	1544	2153	1229	842	610	1081	573	385	64	16	2
	1. Electric	25	97	1	1	1	8	6	12	8	17	10	24	8	1	
	2. Gas	26	3066	9	2	27	178	345	416	381	813	493	332	54	14	2
	3. Other Installed	27	1908	10	22	285	604	395	219	127	170	50	24	2		
	4. None Installed	28	3622	22	127	1231	1363	483	195	94	81	20	5		1	
NUMBER OF UNITS BY REFRIGERATION EQUIPMENT	X. No Report on Refrigeration	29	199	14	3	25	40	25	27	16	34	11	4			
	Total Reports on Refrigeration	30	8522	32	149	1523	2118	1212	816	596	1050	562	382	64	16	2
	1. Electric	31	3387	7	1	62	317	462	437	394	809	483	337	61	15	2
	2. Gas	32	105			4	4	9	13	9	31	18	15	1	1	
	3. Ice	33	3372	13	29	731	1367	628	326	170	175	47	25	1		
	4. None	34	1519	12	119	726	431	113	40	23	35	14	5	1		
NUMBER OF UNITS BY YEAR BUILT	X. No Report on Year Built	35	3		3											
	Total Reports on Year Built	36	8718	46	149	1548	2158	1237	843	612	1084	573	386	64	16	2
	A. 1935	37	1098	5	23	62	124	132	119	123	275	137	85	11	2	
	B. 1930 - 1934	38	481	3	8	61	103	52	40	34	91	53	31	4	1	
	C. 1925 - 1929	39	476	1	6	37	101	76	53	34	74	50	40	2	2	
	D. 1920 - 1924	40	695	3	13	99	198	87	65	56	91	37	40	5	1	
	E. 1915 - 1919	41	351	3	6	56	89	49	38	29	34	20	18	7	2	
	F. 1905 - 1914	42	1183	4	13	228	309	200	140	63	109	65	46	4	1	1
	G. 1895 - 1904	43	2653	13	45	564	791	409	242	155	233	125	55	18	3	
	H. 1885 - 1894	44	1097	8	25	299	274	137	71	90	106	52	27	6	2	
	I. 1860 - 1884	45	610	4	10	131	159	75	67	30	59	27	40	6	2	
	J. 1859 or Before	46	74	2		11	11	14	7	3	14	7	3	1		1
NUMBER OF UNITS BY NUMBER OF ROOMERS IN UNIT	No Report on Roomers	47	28	6		3	6	3	5	2	3					
	Total Reports on Roomers	48	8461	32	149	1522	2104	1204	807	589	1036	556	380	64	16	2
	No Roomers	49	7996	32	145	1480	2018	1135	764	549	959	507	338	55	14	
	1 Roomer	50	270		2	35	65	42	28	23	35	19	18	3		
	2 Roomers	51	80			7	14	18	10	8	12	8	2			
	3 or 4 Roomers	52	70		1		6	7	5	4	20	10	14	2	1	
	5 to 10 Roomers	53	41		1		1	2		5	10	11	6	4		1
	11 Roomers or More	54	4									1	2		1	
NUMBER OF UNITS BY RACE OF HOUSEHOLD	X. No Report on Race	55	23	6		3	5		3	2	3		1			
	Total Reports on Race	56	8466	32	149	1522	2105	1207	809	589	1036	556	379	64	16	2
	1. White	57	7582	27	123	1078	1784	1152	790	582	1029	556	379	64	16	2
	2. Negro	58	884	5	26	444	321	55	19	7	7					
7941	3. Other	59														

CITY Owensboro
STATE Kentucky
3-4-38

DWELLING UNITS BY MONTHLY RENT BY PLUMBING EQUIPMENT, HEATING EQUIPMENT, LIGHTING EQUIPMENT, REFRIGERATION EQUIPMENT, YEAR BUILT, NUMBER OF ROOMERS, AND RACE OF HOUSEHOLD
General Survey Tables

TABLE 10 B, Owner Occupied Units
Units not Under Construction
A complete set of tables includes: Table 10A, All Dwelling Units; Table 10B, Owner Occupied Units; Table 10C, Tenant Occupied Units; Table 10D, Vacant Units

Number of Dwelling Units By:		Line No.	Total All Units	X. No Report on Rent	A. $4.99 and Less	B. $5.00 to $9.99	C. $10.00 to $14.99	D. $15.00 to $19.99	E. $20.00 to $24.99	F. $25.00 to $29.99	G. $30.00 to $39.99	H. $40.00 to $49.99	I. $50.00 to $74.99	J. $75.00 to $99.99	K. $100.00 to $149.99	L. $150.00 and Over
				Number of Dwelling Units by Monthly Rent												
TOTAL NUMBER OF DWELLING UNITS		1	3201	14	29	175	486	433	332	325	609	403	316	61	16	2
NUMBER OF UNITS BY PLUMBING EQUIPMENT	X. No Report on Plumbing	2														
	Total Reports on Plumbing	3	3201	14	29	175	486	433	332	325	609	403	316	61	16	2
	A. At Least 2 Toilets & 2 Bathing Units	4	91			1				1	7	25	37	18	2	
	B. At Least 2 Toilets & 1 Bathing Unit	5	20							1	1	6	9	3		
	C. 1 Toilet and at Least 1 Bath. Unit	6	2160	5		7	165	242	261	256	544	361	264	39	14	2
	D. At least 1 Toilet Less than 1 Bath	7	293		2	15	76	65	35	43	41	10	5	1		
	E. Shared Toilet & Running Water	8	9			1	3	2	1	1	1					
	F. Shared Toilet but No Running Water	9	3				2	1								
	G. No Toilet but with Running Water	10	221	2	1	26	97	60	17	12	6					
	H. No Toilet and No Running Water	11	404	7	26	125	143	63	18	11	9	1	1			
NUMBER OF UNITS BY HEATING EQUIPMENT	X. No Report on Heating	12														
	Total Reports on Heating	13	3201	14	29	175	486	433	332	325	609	403	316	61	16	2
	1. Central Steam or Hot Water	14	407			3	12	11	24	39	109	103	77	24	5	
	2. Central Warm Air	15	958	2		2	8	15	48	98	305	238	202	29	9	2
	3. Other Installed	16	1481	9	12	127	377	331	213	155	163	49	35	8	2	
	4. None Installed	17	355	3	17	43	89	76	47	33	32	13	2			
NUMBER OF UNITS BY LIGHTING EQUIPMENT	X. No Report on Lighting	18	1					1								
	Total Reports on Lighting	19	3200	14	29	175	486	432	332	325	609	403	316	61	16	2
	1. Electric	20	3099	11	16	140	459	421	329	321	607	401	315	61	16	2
	2. Gas	21	5					1	1	1	1	1				
	3. Other	22	96	3	13	35	27	10	2	3	1	1	1			
NUMBER OF UNITS BY COOKING EQUIPMENT	X. No Report on Cooking	23	2					1					1			
	Total Reports on Cooking	24	3199	14	29	175	486	432	332	325	609	403	315	61	16	2
	1. Electric	25	62		1		1	2	5	6	10	7	22	8		
	2. Gas	26	1484	2		3	27	68	121	173	443	341	269	51	14	2
	3. Other Installed	27	1287	9	13	119	356	285	170	113	151	46	23	2		
	4. None Installed	28	366	3	15	53	102	77	36	33	35	9	1		2	
NUMBER OF UNITS BY REFRIGERATION EQUIPMENT	X. No Report on Refrigeration	29														
	Total Reports on Refrigeration	30	3201	14	29	175	486	433	332	325	609	403	316	61	16	2
	1. Electric	31	1813	2		13	103	142	179	214	459	346	280	58	15	2
	2. Gas	32	61				1	2	6	5	16	16	13	1	1	
	3. Ice	33	1066	6	7	91	312	246	138	91	118	35	21	1		
	4. None	34	261	6	22	71	70	43	9	15	16	6	2	1		
NUMBER OF UNITS BY YEAR BUILT	X. No Report on Year Built	35	3		3											
	Total Reports on Year Built	36	3198	14	26	175	486	433	332	325	609	403	316	61	16	2
	A. 1935	37	635	4	9	20	40	51	70	82	176	99	71	11	2	
	B. 1930 - 1934	38	220	2	5	10	25	16	17	20	57	37	26	4	1	
	C. 1925 - 1929	39	229		1	5	27	33	31	18	40	38	32	2	2	
	D. 1920 - 1924	40	259	1	2	12	47	30	23	27	53	25	33	5	1	
	E. 1915 - 1919	41	145	1		9	24	18	17	12	25	16	15	6	2	
	F. 1905 - 1914	42	419	1	2	21	63	74	62	42	59	50	39	4	1	1
	G. 1895 - 1904	43	809	3	6	57	169	147	83	81	116	82	44	18	3	
	H. 1885 - 1894	44	281	2	1	27	48	41	12	33	55	32	24	4	2	
	I. 1860 - 1884	45	184			14	43	21	15	8	25	19	31	6	2	
	J. 1859 or Before	46	17					2	2	2	3	5	1	1		1
NUMBER OF UNITS BY NUMBER OF ROOMERS IN UNIT	No Report on Roomers	47														
	Total Reports on Roomers	48	3201	14	29	175	486	433	332	325	609	403	316	61	16	2
	No Roomers	49	2999	14	28	167	458	414	321	305	562	372	290	54	14	
	1 Roomer	50	113		1	6	21	10	10	12	24	13	14	2		
	2 Roomers	51	36			2	6	5	1	4	10	6	1			1
	3 or 4 Roomers	52	31				1	2		2	9	6	8	2	1	
	5 to 10 Roomers	53	21					2		2	4	6	3	3		1
	11 Roomers or More	54	1												1	
NUMBER OF UNITS BY RACE OF HOUSEHOLD	X. No Report on Race	55	1										1			
	Total Reports on Race	56	3200	14	29	175	486	433	332	325	609	403	315	61	16	2
	1. White	57	2959	13	28	107	384	393	316	318	603	403	315	61	16	2
	2. Negro	58	241	1	1	68	102	40	16	7	6					
	3. Other	59														

9941

CITY Owensboro

STATE Kentucky

8-4-56

DWELLING UNITS BY MONTHLY RENT BY PLUMBING EQUIPMENT, HEATING EQUIPMENT, LIGHTING EQUIPMENT, REFRIGERATION EQUIPMENT, YEAR BUILT, NUMBER OF ROOMERS, AND RACE OF HOUSEHOLD
General Survey Tables

TABLE 10 C Tenant Occupied Units

Units not under Construction
A complete set of tables includes: Table 10A, All Dwelling Units; Table 10B, Owner Occupied Units; Table 10C, Tenant Occupied Units; Table 10D, Vacant Units

Number of Dwelling Units By:	Line No.	Total All Units	X. No Report on Rent	A. $4.99 and Less	B. $5.00 to $9.99	C. $10.00 to $14.99	D. $15.00 to $19.99	E. $20.00 to $24.99	F. $25.00 to $29.99	G. $30.00 to $39.99	H. $40.00 to $49.99	I. $50.00 to $74.99	J. $75.00 to $99.99	K. $100.00 to $149.99	L. $150.00 and Over
			Number of Dwelling Units by Monthly Rent												
TOTAL NUMBER OF DWELLING UNITS	1	5267	18	120	1347	1620	774	477	264	427	153	64	3		
NUMBER OF UNITS BY PLUMBING EQUIPMENT: X. No Report on Plumbing	2														
Total Reports on Plumbing	3	5267	18	120	1347	1620	774	477	264	427	153	64	3		
A. At Least 2 Toilets & 2 Bathing Units	4	22	2			1		1		5	5	8			
B. At least 2 Toilets & 1 Bathing Unit	5	8								1	4	3			
C. 1 Toilet and at Least 1 Bath. Unit	6	2055	5	3	32	334	503	373	229	385	137	51	3		
D. At least 1 Toilet Less than 1 Bath	7	1166		15	257	534	198	94	27	32	7	2			
E. Shared Toilet & Running Water	8	52		6	15	23	6		1	1					
F. Shared Toilet but No Running Water	9	86		10	47	27	1	1							
G. No Toilet but with Running Water	10	471		11	200	220	33	5	1	1					
H. No Toilet and No Running Water	11	1407	11	75	796	481	33	3	6	2					
NUMBER OF UNITS BY HEATING EQUIPMENT: X. No Report on Heating	12														
Total Reports on Heating	13	5267	18	120	1347	1620	774	264	427	153	64	3			
1. Central Steam or Hot Water	14	395	1		7	35	41	68	51	114	49	28	1		
2. Central Warm Air	15	650	3	1	9	42	65	82	92	236	89	29	2		
3. Other Installed	16	1464	2	18	343	515	300	158	66	47	10	5			
4. None Installed	17	2758	12	101	988	1028	368	169	55	30	5	2			
NUMBER OF UNITS BY LIGHTING EQUIPMENT: X. No Report on Lighting	18	1					1								
Total Reports on Lighting	19	5266	18	120	1347	1620	773	477	264	427	153	64	3		
1. Electric	20	4942	14	73	1128	1577	770	474	260	426	153	64	3		
2. Gas	21	5				1		1	2	1					
3. Other	22	319	4	47	219	42	3	2	2						
NUMBER OF UNITS BY COOKING EQUIPMENT: X. No Report on Cooking	23	3				1	1		1						
Total Reports on Cooking	24	5264	18	120	1347	1619	773	477	263	427	153	64	3		
1. Electric	25	32	1		1	5	4	6	2	7	3	3			
2. Gas	26	1472	4	2	24	146	266	278	191	360	140	58	3		
3. Other Installed	27	611	1	8	116	244	107	49	13	19	3	1			
4. None Installed	28	3149	12	110	1156	1224	396	144	57	41	7	2			
NUMBER OF UNITS BY REFRIGERATION EQUIPMENT: X. No Report on Refrigeration	29	3				2			1						
Total Reports on Refrigeration	30	5264	18	120	1347	1618	774	477	263	427	153	64	3		
1. Electric	31	1564	5	1	49	214	319	257	175	347	137	57	3		
2. Gas	32	44			4	3	7	7	4	15	2	2			
3. Ice	33	2440	7	22	640	1052	381	188	79	56	11	4			
4. None	34	1216	6	97	654	349	67	25	5	9	3	1			
NUMBER OF UNITS BY YEAR BUILT: X. No Report on Year Built	35														
Total Reports on Year Built	36	5267	18	120	1347	1618	774	477	263	427	153	64	3		
A. 1935	37	422	1	14	42	80	79	44	38	82	29	13			
B. 1930 - 1934	38	254	1	3	50	78	34	19	14	34	17	4			
C. 1925 - 1929	39	234	1	5	31	71	47	22	9	30	12	6			
D. 1920 - 1924	40	423	2	11	86	149	56	37	28	37	11	6			
E. 1915 - 1919	41	198	1	5	47	64	30	21	15	8	3	3	1		
F. 1905 - 1914	42	735	1	11	201	242	121	73	19	45	15	7			
G. 1895 - 1904	43	1765	3	39	496	608	252	150	66	100	40	11			
H. 1885 - 1894	44	778	4	22	268	212	91	58	53	47	17	4	2		
I. 1860 - 1884	45	402	3	10	115	105	52	48	21	33	7	8			
J. 1859 or Before	46	56	1		11	11	12	5	1	11	2	2			
NUMBER OF UNITS BY NUMBER OF ROOMERS IN UNIT: No Report on Roomers	47	7				2	3	2							
Total Reports on Roomers	48	5260	18	120	1347	1618	771	475	264	427	153	64	3		
No Roomers	49	4997	18	117	1313	1560	721	443	244	397	135	48	1		
1 Roomer	50	157		1	29	44	32	18	11	11	6	4	1		
2 Roomers	51	44			5	8	13	9	4	2	2	1			
3 or 4 Roomers	52	39		1		5	5	5	2	11	4	6			
5 to 10 Roomers	53	20		1		1			3	6	5	3	1		
11 Roomers or More	54	3									1	2			
NUMBER OF UNITS BY RACE OF HOUSEHOLD: X. No Report on Race	55	1				1									
Total Reports on Race	56	5266	18	120	1347	1619	774	477	264	427	153	64	3		
1. White	57	4623	14	95	971	1400	759	474	264	426	153	64	3		
2. Negro	58	643	4	25	376	219	15	3							
3. Other	59														

7941

CITY: Owensboro
STATE: Kentucky

8-4-38

NUMBER OF DWELLING UNITS BY MONTHLY RENT, BY NUMBER OF ROOMS, BY TYPE OF STRUCTURE, NUMBER OF PERSONS, FURNITURE INCLUDED IN RENT, DURATION OF OCCUPANCY, NUMBER OF CHILDREN, EXTRA FAMILIES, NUMBER OF PERSONS IN EXTRA FAMILIES, AND CONDITION
General Survey Tables

TABLE II A. Page 1, all Units

A complete set of tables includes: Table 114, All Units; Table 115, Owner Occupied Units; Table 116, Tenant Occupied Units

For each table there will be pages for the following rent groups: Page 1, Total, No Report on Rent; Page 2, $4.99 or Less; $5 to $9.99; Page 3, $10 to $14.99, $15 to $19.99; Page 4, $20 to $24.99, $25 to $29.99; Page 5, $30 to $39.99, $40 to $49.99; Page 6, $50 to $74.99; $75 to $99.99; Page 7, $100 to $149.99, $150 or More.

Number of Dwelling Units By:		Line No.	Monthly Rent of Total: Total	No Rept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More	Monthly Rent of No Reports: Total	No Rept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
TOTAL NUMBER OF DWELLING UNITS		1	8721	2	193	1113	2311	2192	1492	728	339	431	46	2	6	8	7	9	4	5	2	3
NUMBER OF UNITS BY TYPE OF STRUCTURE	X. No Report on Type	2																				
	Total Reports on Type	3	8721	2	193	1113	2311	2192	1492	728	339	431	46	2	6	8	7	9	4	5	2	3
	1. Single Family Detached	4	5491	2	22	254	1180	1604	1116	605	308	400	29	2	1	4	6	8	2	3	1	2
	2. Single Family Attached	5	1						1													
	3. Two Family Side by Side	6	951		19	269	442	143	51	19	5	3	2			1	1					
	4. Two Family Two Decker	7	316		1	23	52	102	89	35	9	5	1						1			
	5. Three Family Three Decker	8	12		1		1	3	4	3												
	6. Four Family Double Two Decker	9	159		1	31	56	57	11	3												
	V. Apartment: Total	10	46			17	12	10	6	1												
	V. Apartment: 5 - 9 Units	11	46			17	12	10	6	1												
	V. Apartment: 10 - 19 Units	12																				
	V. Apartment: 20 - 39 Units	13																				
	V. Apartment: 40 Units or More	14																				
	8. Business with Dwelling Units	15	356		33	76	91	78	42	20	6	10	1					1				
	9. Other Non-Converted	16	106		36	39	19	4	5	1		2	7		4	2						1
	10. Partially Converted	17	1033		60	334	382	144	64	30	10	9	4		1	1			1		1	
	11. Completely Converted	18	250		20	70	76	47	23	11	1	2	2							2		
NUMBER OF UNITS BY NUMBER OF PERSONS	No Report on Persons	19																				
	Total Reports on Persons	20	8468		188	1065	2251	2123	1377	707	332	425	32		6	5	5	6	3	2	2	3
	1 Person	21	520		97	151	135	64	42	14	5	12	5		5							
	2 Persons	22	2393		52	448	715	572	347	140	57	62	9		1	2	2	2	1	1		
	3 Persons	23	1979		25	236	502	541	365	174	67	69	4			1	1					2
	4 Persons	24	1540		9	131	404	399	261	164	82	90	2						1		1	
	5 Persons	25	884		4	46	233	233	165	87	50	66	6			1	2	2		1	1	
	6 Persons	26	517			25	126	153	83	62	30	38	3			1		1				1
	7 Persons	27	265		1	21	65	64	51	25	15	23										
	8 Persons	28	176			6	46	45	28	16	11	24										
	9 Persons	29	85			1	10	27	17	11	4	15						1	1			
	10 Persons	30	52				6	13	10	10	4	9										
	11 Persons or More	31	57				9	12	8	4	7	17										
NUMBER OF PERSONS IN UNITS WITH 11 OR MORE PERSONS		32	696				103	137	93	49	89	225										
NUMBER OF UNITS BY FURNITURE INCLUDED IN RENT	No Report on Furniture	33	13	2		1	1	5	2	1		1	7	2		1		2		1		1
	Total Reports on Furniture	34	5507		153	994	1961	1331	635	252	94	87	25		1	7	2	4	3	6		2
	Furniture Included in Rent	35	260		37	100	69	26	17	4	1	6	1									1
	Furniture not Included in Rent	36	5247		116	894	1892	1305	618	248	93	81	24		1	7	2	4	3	6		1
NUMBER OF UNITS BY DURATION OF OCCUPANCY	X. No Report on Duration	37	1		1								1		1							
	Total Reports on Duration	38	8467		187	1065	2251	2123	1377	707	332	425	31		5	5	5	6	3	2	2	3
	A. Less than 6 Months	39	1387		74	358	424	276	157	60	24	14	5		1	1		1			1	1
	B. 6 Months - 11 Months	40	778		32	136	268	173	96	36	14	23										
	C. 1 Year - 1 Year 11 Months	41	1282		25	189	407	348	188	66	28	31	2			1						1
	D. 2 Years - 2 Yrs. 11 Months	42	877		15	111	270	226	153	59	24	19	3		2					1		
	E. 3 Years - 4 Yrs. 11 Months	43	1134		23	105	339	310	179	95	42	41	4			1	2			1		
	F. 5 Years - 9 Yrs. 11 Months	44	1162		7	87	271	329	234	114	60	60	5		1	1	1	2				
	G. 10 Years - 19 Yrs. 11 Months	45	1093		8	51	171	269	222	170	86	116	6		1	1	1	1	1			1
	H. 20 Years or More	46	754		3	28	101	192	148	107	54	121	6				1	2	2		1	
NUMBER OF UNITS BY NUMBER OF CHILDREN 14 YEARS OF AGE OR LESS IN UNIT	No Report on Children	47																				
	Total Reports on Children	48	8468		188	1065	2251	2123	1377	707	332	425	32		6	5	5	6	3	2	2	3
	No Children	49	4505		147	655	1131	1037	707	390	180	258	11		6	2	1	2	1	2	1	2
	1 Child	50	1835		24	230	483	481	316	152	74	75	2				2					
	2 Children	51	1105		9	104	311	313	193	84	38	53	5			1		1	1		1	1
	3 or 4 Children	52	801		7	61	256	231	126	61	31	28	7			2	2	2	1			
	5 Children or More	53	222		1	15	70	61	35	20	9	11	1					1				
NUMBER OF UNITS BY NUMBER OF EXTRA FAMILIES IN UNIT	No Report on Extra Families	54	7		1	5		1														
	Total Reports on Extra Families	55	8461		187	1060	2251	2123	1377	707	332	425	32		6	5	5	6	3	2	2	3
	No Extra Families	56	8315		187	1057	2223	2084	1350	690	320	399	32		6	5	5	6	3	2	2	3
	1 Extra Family	57	141			2	28	30	27	17	11	26										
	2 or more Extra Families	58	5			1		3			1											
NUMBER OF EXTRA FAMILIES BY NUMBER OF PERSONS IN EXTRA FAMILIES	Total Number of Extra Families	59	151			4	28	36	26	17	14	26										
	Extra Families, No Report on Persons	60																				
	Extra Families of 1 Person	61	15			1	6	3	1	2		2										
	Extra Families of 2 Persons	62	82			3	14	21	13	11	7	13										
	Extra Families of 3 Persons	63	33				6	7	9	3	4	4										
	Extra Families of 4 Persons	64	18				1	5	3	1	3	5										
	Extra Families of 5 Persons or More	65	3				1					2										
NUMBER OF UNITS BY CONDITION	X. No Report on Condition	66																				
	Total Reports on Condition	67	8721	2	193	1113	2311	2192	1412	728	339	431	46	2	6	8	7	9	4	5	2	3
	1. Good Condition	68	4565	1	56	387	899	1267	962	487	250	316	15	1	1	1	2	2	2	1	2	3
	2. Minor Repairs	69	2867	1	58	380	901	741	385	202	83	110	14	1	1	2	3	1	2	4		
	3. Major Repairs	70	1117		48	274	459	227	63	35	6	5	2			1		1				
	4. Unfit for Use	71	172		31	72	46	17	2	4			15		4	4	2	5				

CITY Owensboro
STATE Kentucky

8-4-38

NUMBER OF DWELLING UNITS WITH MONTHLY RENT, BY NUMBER OF ROOMS, BY TYPE OF STRUCTURE, NUMBER OF PERSONS, FURNITURE INCLUDED IN RENT, DURATION OF OCCUPANCY, NUMBER OF CHILDREN, EXTRA FAMILIES, NUMBER OF PERSONS IN EXTRA FAMILIES, AND CONDITION
General Survey Tables

TABLE II B 2 Owner Occupied Units

A complete set of tables includes Table 11A, All Units; Table 11B, Owner Occupied Units; Table 11C, Tenant Occupied Units

For each table there will be pages for the following rent groups: Page 1, Total, No Report on Rent; Page 2, $4.99 or Less, $5 to $9.99; Page 3, $10 to $14.99, $15 to $19.99; Page 4, $20 to $24.99, $25 to $29.99; Page 5, $30 to $39.99, $40 to $49.99; Page 6, $50 to $74.99; $75 to $99.99; Page 7, $100 to $149.99, $150 or More.

Number of Dwelling Units By:	Line No.	Monthly Rent of _____ Total	No Rept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More	Monthly Rent of _____ Total	No Kept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
TOTAL NUMBER OF DWELLING UNITS	1	3201		40	118	349	856	775	475	243	343	14		3	2	4	2	1		2	
NUMBER OF UNITS BY TYPE OF STRUCTURE: X. No Report on Type	2																				
Total Reports on Type	3	3201		40	118	349	856	775	475	245	343	14		3	2	4	2	1		2	
1. Single Family Detached	4	2588		6	42	219	702	659	409	227	324	9			2	4	1	1		1	
2. Single Family Attached	5	1						1													
3. Two Family Side by Side	6	128		1	18	42	39	15	8	3	2										
4. Two Family Two Decker	7	93				2	26	38	19	5	3										
5. Three Family Three Decker	8	3					1	1	1												
6. Four Family Double Two Decker	9	12			1	1	6	2	2												
7. Apartment: Total	10	5				1	2	1	1												
5 - 9 Units	11	5				1	2	1	1												
10 - 19 Units	12																				
20 - 39 Units	13																				
40 Units or More	14																				
8. Business with Dwelling Units	15	89		2	9	20	22	20	8	2	6	1					1				
9. Other Non-Converted	16	24		18	1	2		2	1			3		3							
10. Partially Converted	17	225		12	43	56	51	28	21	8	6	1								1	
11. Completely Converted	18	33		1	4	6	7	8	5		2										
NUMBER OF UNITS BY NUMBER OF PERSONS: No Report on Persons	19																				
Total Reports on Persons	20	3201		40	118	349	856	775	475	245	343	14		3	2	4	2	1		2	
1 Person	21	227		26	41	55	46	30	12	5	12	2		2							
2 Persons	22	927		11	42	129	306	237	99	49	54	4		1		2	1				
3 Persons	23	763		2	14	72	214	213	135	54	59	1				1					
4 Persons	24	585			14	36	134	141	117	63	80	1								1	
5 Persons	25	312			2	24	71	78	50	34	53	3			1	1				1	
6 Persons	26	195			1	17	55	37	31	24	30	2			1		1				
7 Persons	27	78		1	4	10	12	18	11	8	14										
8 Persons	28	50				5	7	8	8	4	18										
9 Persons	29	28					6	6	5		11	1						1			
10 Persons	30	18					2	5	3	2	6	1									
11 Persons or More	31	18				1	3	2	4	2	6										
NUMBER OF PERSONS IN UNITS WITH 11 OR MORE PERSONS	32	221				11	35	22	49	24	80										
NUMBER OF UNITS BY FURNITURE INCLUDED IN RENT: No Report on Furniture	33																				
Total Reports on Furniture	34																				
Furniture Included in Rent	35																				
Furniture not Included in Rent	36																				
NUMBER OF UNITS BY DURATION OF OCCUPANCY: X. No Report on Duration	37	1		1										1							
Total Reports on Duration	38	3200		39	118	349	856	775	475	245	343	13		2	2	4	2	1		2	
A. Less than 6 Months	39	186		11	9	23	51	55	21	8	8	2					1			1	
B. 6 Months - 11 Months	40	111		1	7	7	33	31	13	8	11										
C. 1 Year - 1 Year 11 Months	41	294		4	9	23	107	85	33	14	19										
D. 2 Years - 2 Yrs. 11 Months	42	221		5	10	23	66	61	29	15	12	2		2							
E. 3 Years - 4 Yrs. 11 Months	43	381		7	22	45	103	96	55	27	26	3			1	2					
F. 5 Years - 9 Yrs. 11 Months	44	474		2	12	53	120	126	75	43	43	2			1	1					
G. 10 Years - 19 Yrs. 11 Months	45	863		6	28	100	206	187	146	81	109	1				1					
H. 20 Years or More	46	670		3	21	75	170	134	103	49	115	3					1	1		1	
NUMBER OF UNITS BY NUMBER OF CHILDREN 14 YEARS OF AGE OR LESS IN UNIT: No Report on Children	47																				
Total Reports on Children	48	3201		40	118	349	856	775	475	245	343	14		3	2	4	2	1		2	
No Children	49	2003		37	95	236	534	452	285	151	213	6		3		1	1			1	
1 Child	50	595		1	10	50	154	169	99	52	60	2				2					
2 Children	51	341		1	7	32	98	93	47	23	40	1								1	
3 or 4 Children	52	210			6	23	60	50	34	15	22	3			2	1					
5 Children or More	53	52		1		8	10	11	10	4	8	2					1	1			
NUMBER OF UNITS BY NUMBER OF EXTRA FAMILIES IN UNIT: No Report on Extra Families	54																				
Total Reports on Extra Families	55	3201		40	118	349	856	775	475	245	343	14		3	2	4	2	1		2	
No Extra Families	56	3139		40	118	344	846	765	466	237	323	14		3	2	4	2	1		2	
1 Extra Family	57	60				5	9	10	9	7	20										
2 or more Extra Families	58	2					1														
NUMBER OF EXTRA FAMILIES BY NUMBER OF PERSONS IN EXTRA FAMILIES: Total Number of Extra Families	59	65				5	11	10	9	10	20										
Extra Families, No Report on Persons	60																				
Extra Families of 1 Person	61	5				2	1		1		1										
Extra Families of 2 Persons	62	36				1	5	8	6	6	10										
Extra Families of 3 Persons	63	12				2	2	1	2	2	3										
Extra Families of 4 Persons	64	10					3	1		2	4										
Extra Families of 5 Persons or More	65	2									2										
NUMBER OF UNITS BY CONDITION: X. No Report on Condition	66																				
Total Reports on Condition	67	3201		40	118	349	856	775	475	245	343	14		3	2	4	2	1		2	
1. Good Condition	68	2088		18	60	151	512	565	341	187	254	9		1	1	2	2	1		2	
2. Minor Repairs	69	888		9	36	130	269	187	116	56	85	3			1	2					
3. Major Repairs	70	195		6	14	58	71	23	17	2	4										
4. Unfit for Use	71	30		7	8	10	4		1			2		2							

CITY Owensboro
STATE Kentucky

3-4-38

NUMBER OF DWELLING UNITS BY MONTHLY RENT, BY NUMBER OF ROOMS, BY TYPE OF STRUCTURE, NUMBER OF PERSONS, FURNITURE INCLUDED IN RENT, DURATION OF OCCUPANCY, NUMBER OF CHILDREN, EXTRA FAMILIES, NUMBER OF PERSONS IN EXTRA FAMILIES, AND CONDITION

General Survey Tables

A complete set of tables includes Table 11A, All Units; Table 11B, Owner Occupied Units; Table 11C, Tenant Occupied Units

TABLE II C, 3 Tenant Occupied Units

For each table there will be pages for the following rent groups: Page 1, Total, No Report on Rent; Page 2, $4.99 or Less, $8 to $9.99; Page 3, $10 to $14.99, $15 to $19.99; page 4, $20 to $24.99, $25 to $29.99; Page 5, $30 to $39.99, $40 to $49.99; Page 6, $50 to $74.99; $75 to $99.99; Page 7, $100 to $149.99, $150 or More.

Monthly Rent of _____

Number of Dwelling Units By:	Line No.	Total	No Rept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
TOTAL NUMBER OF DWELLING UNITS	1	5267		148	947	1902	1267	602	232	87	82
NUMBER OF UNITS BY TYPE OF STRUCTURE: I. No Report on Type	2										
Total Reports on Type	3	5267		148	947	1902	1267	602	232	87	82
1. Single Family Detached	4	2787		16	203	948	858	438	180	24	70
2. Single Family Attached	5										
3. Two Family Side by Side	6	806		18	241	397	100	36	11	2	1
4. Two Family Two Decker	7	208		1	22	49	70	45	15	4	2
5. Three Family Three Decker	8	8		1			2	3	2		
6. Four Family Double Two Decker	9	134		1	29	47	47	9	1		
7. Apartment: Total	10	36			13	11	8	4			
6 - 9 Units	11	36			13	11	8	4			
10 - 19 Units	12										
20 - 39 Units	13										
40 Units or More	14										
8. Business with Dwelling Units	15	247		30	64	63	50	21	11	4	4
9. Other Non-Converted	16	76		17	34	16	4	3			2
10. Partially Converted	17	764		47	280	307	88	29	8	2	3
11. Completely Converted	18	201		17	61	64	40	14	4	1	
NUMBER OF UNITS BY NUMBER OF PERSONS: No Report on Persons	19										
Total Reports on Persons	20	5267		148	947	1902	1267	602	232	87	82
1 Person	21	293		71	110	80	18	12	2		
2 Persons	22	1466		41	406	586	266	110	41	8	8
3 Persons	23	1216		23	222	430	327	152	39	13	10
4 Persons	24	955		9	117	368	265	120	47	19	10
5 Persons	25	572		4	44	209	162	87	37	16	13
6 Persons	26	322			24	109	98	46	31	6	8
7 Persons	27	187			17	55	52	33	14	7	9
8 Persons	28	126			6	41	38	20	8	7	6
9 Persons	29	57			1	10	21	11	6	4	4
10 Persons	30	34				6	11	5	7	2	3
11 Persons or More	31	39				8	9	6		5	11
NUMBER OF PERSONS IN UNITS WITH 11 OR MORE PERSONS	32	475				102	92	71		65	145
NUMBER OF UNITS BY FURNITURE INCLUDED IN RENT: No Report on Furniture	33	2				1					1
Total Reports on Furniture	34	5265		148	947	1901	1267	602	232	87	81
Furniture Included in Rent	35	233		34	89	61	23	15	4	1	6
Furniture not Included in Rent	36	5032		114	858	1840	1240	587	228	86	75
NUMBER OF UNITS BY DURATION OF OCCUPANCY: I. No Report on Duration	37										
Total Reports on Duration	38	5267		148	947	1902	1267	602	232	87	82
A. Less than 6 Months	39	1201		63	349	491	225	102	39	16	6
B. 6 Months - 11 Months	40	667		31	129	261	140	65	23	6	12
C. 1 Year - 1 Year 11 Months	41	988		21	180	384	241	103	33	14	12
D. 2 Years - 2 Yrs. 11 Months	42	656		10	101	247	160	92	30	9	7
E. 3 Years - 4 Yrs. 11 Months	43	753		16	83	294	207	83	40	15	15
F. 5 Years - 9 Yrs. 11 Months	44	688		5	75	218	209	108	39	17	17
G. 10 Years - 19 Yrs. 11 Months	45	230		2	23	71	63	35	24	5	7
H. 20 Years or More	46	84			7	26	22	14	4	5	6
NUMBER OF UNITS BY NUMBER OF CHILDREN 14 YEARS OF AGE OR LESS IN UNIT: No Report on Children	47										
Total Reports on Children	48	5267		148	947	1902	1267	602	232	87	82
No Children	49	2502		110	560	895	503	255	105	29	45
1 Child	50	1240		23	220	443	327	147	53	22	15
2 Children	51	763		8	97	278	215	106	37	15	13
3 or 4 Children	52	592		7	55	234	171	76	27	16	6
5 Children or More	53	170			15	62	51	24	10	5	3
NUMBER OF UNITS BY NUMBER OF EXTRA FAMILIES IN UNIT: No Report on Extra Families	54	7		1	5		1				
Total Reports on Extra Families	55	5260		147	942	1902	1266	602	232	87	82
No Extra Families	56	5176		147	938	1879	1243	586	224	83	76
1 Extra Family	57	81			3	23	21	16	8	4	6
2 or more Extra Families	58	3			1		2				
NUMBER OF EXTRA FAMILIES BY NUMBER OF PERSONS IN EXTRA FAMILIES: Total Number of Extra Families	59	86			4	23	25	16	8	4	6
Extra Families, No Report on Persons	60										
Extra Families of 1 Person	61	10			1	4	2	1	1		1
Extra Families of 2 Persons	62	46			3	13	16	6	5		3
Extra Families of 3 Persons	63	21				4	5	7	1	3	1
Extra Families of 4 Persons	64	8				1	2	2	1	1	1
Extra Families of 5 Persons or More	65	1				1					
NUMBER OF UNITS BY CONDITION: I. No Report on Condition	66	5									
Total Reports on Condition	67	5267		148	947	1902	1267	602	232	87	82
1. Good Condition	68	2331		35	309	715	657	376	129	58	58
2. Minor Repairs	69	1912		47	332	759	451	191	84	25	23
3. Major Repairs	70	906		42	252	397	153	34	18	4	1
4. Unfit for Use	71	118		24	54	31	6	2	1		

Number of Dwelling Units By:	Line No.	Total	No Rept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
TOTAL NUMBER OF DWELLING UNITS	1	18		3	3	1	4	2	2		3
NUMBER OF UNITS BY TYPE OF STRUCTURE: I. No Report on Type	2										
Total Reports on Type	3	18		3	3	1	4	2	2		3
1. Single Family Detached	4	11		1	1		4	1	2		2
2. Single Family Attached	5										
3. Two Family Side by Side	6	1				1					
4. Two Family Two Decker	7	1						1			
5. Three Family Three Decker	8										
6. Four Family Double Two Decker	9										
7. Apartment: Total	10										
6 - 9 Units	11										
10 - 19 Units	12										
20 - 39 Units	13										
40 Units or More	14										
8. Business with Dwelling Units	15										
9. Other Non-Converted	16	3		1	1						1
10. Partially Converted	17	2		1	1						
11. Completely Converted	18										
NUMBER OF UNITS BY NUMBER OF PERSONS: No Report on Persons	19										
Total Reports on Persons	20	18		3	3	1	4	2	2		3
1 Person	21	3		3							
2 Persons	22	5			2		1	1	1		
3 Persons	23	3			1						2
4 Persons	24	1						1			
5 Persons	25	4				1	2		1		
6 Persons	26	1									1
7 Persons	27										
8 Persons	28										
9 Persons	29	1					1				
10 Persons	30										
11 Persons or More	31										
NUMBER OF PERSONS IN UNITS WITH 11 OR MORE PERSONS	32										
NUMBER OF UNITS BY FURNITURE INCLUDED IN RENT: No Report on Furniture	33	1									1
Total Reports on Furniture	34	17		3	3	1	4	2	2		2
Furniture Included in Rent	35	1									1
Furniture not Included in Rent	36	16		3	3	1	4	2	2		1
NUMBER OF UNITS BY DURATION OF OCCUPANCY: I. No Report on Duration	37										
Total Reports on Duration	38	18		3	3	1	4	2	2		3
A. Less than 6 Months	39	3		1	1						1
B. 6 Months - 11 Months	40										
C. 1 Year - 1 Year 11 Months	41	2			1						1
D. 2 Years - 2 Yrs. 11 Months	42	1							1		
E. 3 Years - 4 Yrs. 11 Months	43	1							1		
F. 5 Years - 9 Yrs. 11 Months	44	3		1			2				
G. 10 Years - 19 Yrs. 11 Months	45	5		1	1		1	1			1
H. 20 Years or More	46	3				1	1	1			
NUMBER OF UNITS BY NUMBER OF CHILDREN 14 YEARS OF AGE OR LESS IN UNIT: No Report on Children	47										
Total Reports on Children	48	18		3	3	1	4	2	2		3
No Children	49	11		3	2		1	1	2		2
1 Child	50										
2 Children	51	4			1		1	1	1		1
3 or 4 Children	52	2				1	1				
5 Children or More	53	1					1				
NUMBER OF UNITS BY NUMBER OF EXTRA FAMILIES IN UNIT: No Report on Extra Families	54										
Total Reports on Extra Families	55	18		3	3	1	4	2	2		3
No Extra Families	56	18		3	3	1	4	2	2		3
1 Extra Family	57										
2 or more Extra Families	58										
NUMBER OF EXTRA FAMILIES BY NUMBER OF PERSONS IN EXTRA FAMILIES: Total Number of Extra Families	59										
Extra Families, No Report on Persons	60										
Extra Families of 1 Person	61										
Extra Families of 2 Persons	62										
Extra Families of 3 Persons	63										
Extra Families of 4 Persons	64										
Extra Families of 5 Persons or More	65										
NUMBER OF UNITS BY CONDITION: I. No Report on Condition	66										
Total Reports on Condition	67	18		3	3	1	4	2	2		3
1. Good Condition	68	4						1			3
2. Minor Repairs	69	7		1	1	1	1	1	2		
3. Major Repairs	70	2			1		1				
4. Unfit for Use	71	5		2	1		2				

CITY Owensboro
STATE Kentucky
5-4-55

VACANT DWELLING UNITS BY MONTHLY RENT, BY NUMBER OF ROOMS, BY TYPE OF STRUCTURE, FURNITURE INCLUDED IN RENT DURATION OF VACANCY, AND CONDITION
General Survey Tables

TABLE II-D / VACANT UNITS, Total

For this table there will be pages for the following rent groups: Page 1, Total, No Report on Rent; Page 2, $4.99 or Less, $5 to $9.99; Page 3, $10 to $14.99, $15 to $19.99; Page 4, $20 to $24.99, $25 to $29.99; Page 5, $30 to $39.99, $40 to $49.99; Page 6, $50 to $74.99, $75 to $99.99; Page 7, $100 to $149.99, $150 or More

Number of Dwelling Units By:		Line No.	Monthly Rent of Total: Total	No Rept on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
TOTAL NUMBER OF DWELLING UNITS		1	253	2	5	48	60	69	35	21	7	6
NUMBER OF UNITS BY TYPE OF STRUCTURE	X. No Report on Type	2										
	Total Reports on Type	3	253	2	5	48	60	69	35	21	7	6
	1. Single Family Detached	4	116	2		9	13	44	19	16	7	6
	2. Single Family Attached	5										
	3. Two Family Side by Side	6	17			10	3	4				
	4. Two Family Two Decker	7	15			1	1	6	6	1		
	5. Three Family Three Decker	8	1				1					
	6. Four Family Double Two Decker	9	13			1	8	4				
	7. Apartment Total	10	5			4			1			
	5 - 9 Units	11	5			4			1			
	10 - 19 Units	12										
	20 - 39 Units	13										
	40 Units or More	14										
	8. Business with Dwelling Units	15	20		1	3	8	6	1	1		
	9. Other Non-converted	16	6		1	4	1					
	10. Partially Converted	17	44		1	11	19	5	7	1		
	11. Completely Converted	18	16		2	5	6		1	2		
NUMBER OF UNITS BY FURNITURE INCLUDED IN RENT	No Report on Furniture	19	11	2		1		5	2	1		
	Total Reports on Furniture	20	242		5	47	60	64	33	20	7	6
	Furniture Included in Rent	21	27		3	11	8	3	2			
	Furniture not Included in Rent	22	215		2	36	52	61	31	20	7	6
NUMBER OF UNITS BY DURATION OF VACANCY	I. No Report on Duration	23	14	1		4	3	4	1	1		
	Total Reports on Duration	24	239	1	5	44	57	65	34	20	7	6
	J. Less than 1 Month	25	19		2	4	3	5	3		1	1
	K. 1 Month	26	132	1	1	22	30	40	17	13	6	2
	L. 2 Months	27	38		1	5	8	10	9	2		3
	M. 3 - 5 Months	28	23			6	9	2	3	3		
	N. 6 - 8 Months	29	8			1	3	2	1	1		
	O. 9 - 11 Months	30	2				2					
	P. 1 Year - 1 Yr. 11 Mos.	31	6		1	1		3	1			
	Q. 2 Years - 2 Yrs. 11 Mos.	32	3			3						
	R. 3 Years or More	33	8			2	2	3		1		
NUMBER OF UNITS BY CONDITION	X. No Report on Condition	34										
	Total Reports on Condition	35	253	2	5	48	60	69	35	21	7	6
	1. Good Condition	36	146	1	3	18	33	38	27	17	5	4
	2. Minor Repairs	37	67	1	2	12	18	21	7	2	2	2
	3. Major Repairs	38	16			8	4	3	1			
	4. Unfit for Use	39	24			10	5	7		2		

Monthly Rent of _____: Total | No Rept on Rooms | 1 Room | 2 Rooms | 3 Rooms | 4 Rooms | 5 Rooms | 6 Rooms | 7 Rooms | 8 Rooms or More

1908

CITY Owensboro
STATE Kentucky
5-4-35

DWELLING UNITS BY OCCUPANCY, BY CONDITION, BY PLUMBING EQUIPMENT, AND NUMBER OF CHILDREN

General Survey Tables

TABLE 12
Units not under Construction

Number of Dwelling Units By:		Line	All Dwelling Units: Total	Number of Units by Condition: X. No Report on Condition	1. Good Condition	2. Minor Repairs	3. Major Repairs	4. Unfit for Use	Vacant Units: Total	Number of Units by Condition: X. No Report on Condition	1. Good Condition	2. Minor Repairs	3. Major Repairs	4. Unfit for Use
TOTAL ALL UNITS		1	8721		4565	2867	1117	172	253		146	67	16	24
NUMBER OF UNITS BY PLUMBING EQUIPMENT	X. No Report on Plumbing	2	1		1				1		1			
	Total Reports on Plumbing	3	8720		4564	2867	1117	172	252		145	67	16	24
	A. At least 2 Toilets and 2 Bathing Units	4	114		87	27			1		1			
	B. At least 2 Toilets and 1 Bathing Unit	5	28		25	3								
	C. 1 Toilet and at least 1 Bathing Unit	6	4361		3070	1174	115	2	146		113	32	1	
	D. At least 1 Toilet but less than 1 Bath	7	1512		756	538	216	2	53		27	22	4	
	E. Shared Toilet and Running Water	8	61		12	32	17							
	F. Shared Toilet but no Running Water	9	94		23	49	22		5		2	2	1	
	G. No Toilet but with Running Water	10	698		236	323	113	26	6		1	2	3	
	H. No Toilet and no Running Water	11	1852		355	721	634	142	41		1	9	7	24
TOTAL ALL OCCUPIED UNITS		12	8468		4419	2800	1064	148						
NUMBER OF UNITS BY NUMBER OF CHILDREN IN UNIT	No Report on Children	13												
	Total Reports on Children	14	8468		4419	2800	1101	148						
	No Children	15	4505		2494	1353	567	91						
	1 Child	16	1835		1006	609	200	20						
	2 Children	17	1105		532	412	150	11						
	3 or 4 Children	18	801		314	338	129	20						
	5 Children or More	19	222		73	88	55	6						

Number of Dwelling Units By:		Line No.	Owner Occupied Units: Total	Number of Units by Condition: X. No Report on Condition	1. Good Condition	2. Minor Repairs	3. Major Repairs	4. Unfit for Use	Tenant Occupied Units: Total	Number of Units by Condition: X. No Report on Condition	1. Good Condition	2. Minor Repairs	3. Major Repairs	4. Unfit for Use
TOTAL ALL UNITS		20	3201		2088	888	195	30	5267		2331	1912	906	118
NUMBER OF UNITS BY PLUMBING EQUIPMENT	X. No Report on Plumbing	21												
	Total Reports on Plumbing	22	3201		2088	888	195	30	5267		2331	1912	906	118
	A. At least 2 Toilets and 2 Bathing Units	23	91		69	22			22		17	5		
	B. At least 2 Toilets and 1 Bathing Unit	24	20		19	1			8		6	2		
	C. 1 Toilet and at least 1 Bathing Unit	25	2160		1584	528	46	2	2055		1373	614	68	
	D. At least 1 Toilet but less than 1 Bath	26	293		175	100	18		1166		554	416	194	2
	E. Shared Toilet and Running Water	27	9		3	3	3		52		9	29	14	
	F. Shared Toilet but no Running Water	28	3		1	1	1		86		20	46	20	
	G. No Toilet but with Running Water	29	221		103	90	19	9	471		132	231	91	17
	H. No Toilet and no Running Water	30	404		134	143	108	19	1407		220	569	519	99
NUMBER OF UNITS BY NUMBER OF CHILDREN IN UNIT	No Report on Children	31												
	Total Reports on Children	32	3201		2088	888	195	30	5267		2331	1912	906	118
	No Children	33	2003		1313	528	140	22	2502		1181	825	427	69
	1 Child	34	595		407	161	24	3	1240		599	448	176	17
	2 Children	35	342		220	104	17	1	763		312	308	133	10
	3 or 4 Children	36	209		118	78	10	3	592		196	260	119	17
	5 Children or More	37	52		30	17	4	1	170		43	71	51	5

7944

CITY Greensboro
STATE Kentucky
8-4-56

DWELLING UNITS BY PERSONS PER ROOM
BY CONDITION BY NUMBER OF ROOMERS AND
NUMBER OF PERSONS BY AGE

General Survey Tables

TABLE 13 A, All Occupied Units
Units not under Construction
A complete set of tables includes: Table 13A, All Occupied Units; Table 13B, Owner Occupied Units; Table 13C, Tenant Occupied Units.

Number of Units by Condition	Number of Persons per Room	Line No.	Total Number of Dwel. Units	Number of Units by Number of Roomers in Unit: No Rept on Room'rs	No Roomers	1 Roomer	2 Roomers	3 or 4 Roomers	5 to 10 Roomers	11 R'mers or More	Number of Units: No Rept on Age of Per.	Tot. Repts. on Age of Per.	Number of Persons by Age Group: Total Persons	Pers. under 1 Year	Pers. 1 to 4 Yrs.	Pers. 5 to 9 Yrs.	Pers. 10 to 14 Yrs.	Pers. 15 to 19 Yrs.	Pers. 20 to 64 Yrs.	P. 65 Yrs and Over
TOTAL NUMBER OF UNITS - ALL CONDITION	Total	1	8468	7	7996	270	80	70	41	4		8468	30163	595	2101	2670	2588	2503	18446	1260
	X. No Rept on Persons per Room	2																		
	Total Repts on Persons per Room	3	8468	7	7996	270	80	70	41	4		8468	30163	595	2101	2670	2588	2503	18446	1260
	A. .80 or Less	4	2023		1971	40	8	2	2			2023	4186	4	44	62	77	141	3413	445
	B. .81 to .75	5	2014		1903	74	16	17	4			2014	5947	69	242	264	282	377	4417	296
	C. .76 to 1.00	6	2106	5	1973	67	20	24	16	1		2106	7412	128	499	534	574	618	4769	290
	D. 1.01 to 1.50	7	1264	1	1148	62	16	22	15			1264	6109	182	562	715	696	628	3199	127
	E. 1.51 to 2.00	8	728	1	683	20	17	4	2	1		728	4075	116	457	643	552	460	1781	66
	F. 2.01 or More	9	333		318	7	3	1	2	2		333	2434	96	297	452	407	279	867	36
X. NO REPORT ON CONDITION	Total	10																		
	X. No Rept on Persons per Room	11																		
	Total Repts on Persons per Room	12																		
	A. .80 or Less	13																		
	B. .81 to .75	14																		
	C. .76 to 1.00	15																		
	D. 1.01 to 1.50	16																		
	E. 1.51 to 2.00	17																		
	F. 2.01 or More	18																		
1. GOOD CONDITION	Total	19	4419	6	4163	131	45	49	21	4		4419	15189	274	920	1194	1122	1203	9942	534
	X. No Rept on Persons per Room	20																		
	Total Repts on Persons per Room	21	4419	6	4163	131	45	49	21	4		4419	15189	274	920	1194	1122	1203	9942	534
	A. .80 or Less	22	1314		1279	27	5	1	2			1314	2844	2	35	45	52	101	2365	224
	B. .81 to .75	23	1224		1159	40	10	13	2			1224	3780	51	164	194	185	253	2796	137
	C. .76 to 1.00	24	1050	5	976	29	15	18	6	1		1050	3999	70	287	332	325	345	2529	111
	D. 1.01 to 1.50	25	540		480	27	7	16	10			540	2765	92	250	334	313	294	1439	43
	E. 1.51 to 2.00	26	225	1	205	8	8	1	1	1		225	1300	38	131	202	171	153	591	14
	F. 2.01 or More	27	66		64					2		66	501	21	53	87	76	57	202	5
2. MINOR REPAIRS	Total	28	2800	1	2634	103	29	16	17			2800	10500	218	846	1010	991	895	6054	486
	X. No Rept on Persons per Room	29																		
	Total Repts on Persons per Room	30	2800	1	2634	103	29	16	17			2800	10500	218	846	1010	991	895	6054	486
	A. .80 or Less	31	521		507	10	3	1				521	1048	2	9	15	21	33	806	162
	B. .81 to .75	32	601		564	28	4	3	2			601	1716	16	76	59	82	105	1269	109
	C. .76 to 1.00	33	737		689	30	5	5	8			737	2552	48	178	170	200	209	1638	109
	D. 1.01 to 1.50	34	495	1	450	25	8	6	5			495	2384	61	239	289	271	234	1234	56
	E. 1.51 to 2.00	35	314		300	6	7	1				314	1802	54	227	296	245	192	754	34
	F. 2.01 or More	36	132		124	4	2		2			132	998	37	117	181	172	122	353	16
3. MAJOR REPAIRS	Total	37	1101		1057	32	5	5	2			1101	4018	92	300	423	421	369	2205	208
	X. No Rept on Persons per Room	38																		
	Total Repts on Persons per Room	39	1101		1057	32	5	5	2			1101	4018	92	300	423	421	369	2205	208
	A. .80 or Less	40	166		164	2						166	269			2	4	7	204	52
	B. .81 to .75	41	175		166	6	2	1				175	446	2	1	11	12	18	323	49
	C. .76 to 1.00	42	273		262	8		1	2			273	775	10	34	32	47	58	540	54
	D. 1.01 to 1.50	43	208		197	10	1					208	883	28	66	86	100	94	484	25
	E. 1.51 to 2.00	44	166		158	5	1	2				166	870	20	91	130	123	104	388	14
	F. 2.01 or More	45	113		110	1	1	1				113	805	32	108	162	135	88	266	14
4. UNFIT FOR USE	Total	46	148		142	4	1		1			148	456	11	35	43	54	36	245	32
	X. No Rept. on Persons per Room	47																		
	Total Repts on Persons per Room	48	148		142	4	1		1			148	456	11	35	43	54	36	245	32
	A. .80 or Less	49	22		21	1						22	25						18	7
	B. .81 to .75	50	14		14							14	35		1		3	1	29	1
	C. .76 to 1.00	51	46		46							46	86				2	6	62	16
	D. 1.01 to 1.50	52	21		21							21	77	1	7	6	12	6	42	3
	E. 1.51 to 2.00	53	23		20	1	1		1			23	103	4	8	15	13	11	48	4
	F. 2.01 or More	54	22		20	2						22	130	6	19	22	24	12	46	1

8009

CITY Owensboro
STATE Kentucky
6-4-38

DWELLING UNITS BY PERSONS PER ROOM
BY CONDITION BY NUMBER OF ROOMERS AND
NUMBER OF PERSONS BY AGE

General Survey Tables

TABLE 13B, Owner Occupied

Units not under Construction

A complete set of tables includes: Table 13A, All Occupied Units; Table 13B, Owner Occupied Units; Table 13C, Tenant Occupied Units.

Number of Units by Condition	Number of Persons per Room	Line No.	Total Number of Dwel. Units	Number of Units by Number of Roomers in Unit: No Rept on Rooms	No Roomers	1 Roomer	2 Roomers	3 or 4 Roomers	5 to 10 Roomers	11 Rooms or More	Number of Units: No Rept on Age of Pers	Pct. Rept. on Age of Pers	Number of Persons by Age Group: Total Persons	Pers. under 1 Year	Pers. 1 to 4 Yrs.	Pers. 5 to 9 Yrs.	Pers. 10 to 14 Yrs.	Pers. 15 to 19 Yrs.	Pers. 20 to 64 Yrs.	P. 65 Yrs. and Over
TOTAL NUMBER OF UNITS - ALL CONDITION	Total	1	3201		2999	113	36	31	21	1		3201	11039	117	509	772	874	978	7086	703
	X. No Rept on Persons per Room	2																		
	Total Repts on Persons per Room	3	3201		2999	113	36	31	21	1		3201	11039	117	509	772	874	978	7086	703
	A. .50 or Less	4	1284		1244	32	6	1	1			1284	2826	2	28	48	61	113	2229	345
	B. .51 to .75	5	851		791	35	11	12	2			851	2869	30	120	141	159	232	2004	183
	C. .76 to 1.00	6	637		577	28	10	10	12			637	2705	42	153	212	260	282	1640	116
	D. 1.01 to 1.50	7	276		246	14	5	7	4			276	1595	19	113	208	221	206	785	43
	E. 1.51 to 2.00	8	113		104	3	3	1	1	1		113	725	15	65	109	107	100	319	10
	F. 2.01 or More	9	40		37	1	1		1			40	319	9	30	54	66	45	109	6
2. NO REPORT ON CONDITION	Total	10																		
	X. No Rept on Persons per Room	11																		
	Total Repts on Persons per Room	12																		
	A. .50 or Less	13																		
	B. .51 to .75	14																		
	C. .76 to 1.00	15																		
	D. 1.01 to 1.50	16																		
	E. 1.51 to 2.00	17																		
	F. 2.01 or More	18																		
1. GOOD CONDITION	Total	19	2088		1972	56	22	27	10	1		2088	7167	77	321	487	522	625	4770	365
	X. No Rept on Persons per Room	20																		
	Total Repts on Persons per Room	21	2088		1972	56	22	27	10	1		2088	7167	77	321	487	522	625	4770	365
	A. .50 or Less	22	903		876	21	4	1	1			903	2039	2	24	35	43	87	1654	194
	B. .51 to .75	23	576		542	17	7	9	1			576	1993	22	86	106	114	168	1402	95
	C. .76 to 1.00	24	380		347	10	9	10	4			380	1691	26	98	146	166	177	1020	58
	D. 1.01 to 1.50	25	158		142	6	1	6	3			158	943	14	71	128	128	125	463	14
	E. 1.51 to 2.00	26	53		47	2	1	1	1	1		53	348	10	30	45	41	43	176	3
	F. 2.01 or More	27	18		18							18	153	3	12	27	30	25	55	1
2. MINOR REPAIRS	Total	28	888		819	45	12	3	9			888	3177	34	168	239	291	291	1891	263
	X. No Rept on Persons per Room	29																		
	Total Repts on Persons per Room	30	888		819	45	12	3	9			888	3177	34	168	239	291	291	1891	263
	A. .50 or Less	31	303		293	8	2					303	649		4	12	15	25	473	120
	B. .51 to .75	32	229		208	15	3	2	1			229	756	8	34	33	43	58	511	69
	C. .76 to 1.00	33	206		183	16	1		6			206	853	15	53	63	80	84	512	46
	D. 1.01 to 1.50	34	97		86	6	3	1	1			97	545	5	39	67	76	67	270	21
	E. 1.51 to 2.00	35	39		37		2					39	264	4	27	50	52	40	87	4
	F. 2.01 or More	36	14		12		1		1			14	110	2	11	14	25	17	38	3
3. MAJOR REPAIRS	Total	37	195		181	9	2	1	2			195	615	4	15	38	55	57	378	68
	X. No Rept on Persons per Room	38																		
	Total Repts on Persons per Room	39	195		181	9	2	1	2			195	615	4	15	38	55	57	378	68
	A. .50 or Less	40	71		69	2						71	128			1	3	1	94	29
	B. .51 to .75	41	41		36	3	1	1				41	109			2	1	6	82	18
	C. .76 to 1.00	42	42		38	2			2			42	144	1	2	3	13	19	96	10
	D. 1.01 to 1.50	43	19		16	2	1					19	101		2	13	17	13	49	7
	E. 1.51 to 2.00	44	16		16							16	91	1	6	9	12	15	46	2
	F. 2.01 or More	45	6		6							6	42	2	5	10	9	3	11	2
4. UNFIT FOR USE	Total	46	30		27	3						30	80	2	5	8	6	5	47	7
	X. No Rept. on Persons per Room	47																		
	Total Repts on Persons per Room	48	30		27	3						30	80	2	5	8	6	5	47	7
	A. .50 or Less	49	7		6	1						7	10						8	2
	B. .51 to .75	50	5		5							5	11				1		9	1
	C. .76 to 1.00	51	9		9							9	17				1	2	12	2
	D. 1.01 to 1.50	52	2		2							2	6		1			1	3	1
	E. 1.51 to 2.00	53	5		4	1						5	22		2	5	2	2	10	1
6809	F. 2.01 or More	54	2		1	1						2	14	2	2	3	2		5	

CITY Owensboro
STATE Kentucky
5-4-58

DWELLING UNITS BY PERSONS PER ROOM
BY CONDITION BY NUMBER OF ROOMS AND
NUMBER OF PERSONS BY AGE

General Survey Tables

TABLE 13 C Tenant Occupied Units

Units not under Construction
A complete set of tables includes: Table 13A, All Occupied Units; Table 13B, Owner Occupied Units; Table 13C, Tenant Occupied Units.

Number of Units by Condition	Number of Persons per Room	Line No.	Total Number of Dwel. Units	Number of Units by Number of Rooms in Unit: No Rept on Room's	No Rooms	1 Room	2 Rooms	3 or 4 Rooms	5 to 10 Rooms	11 R'ms or More	Number of Units: No Rept on Ages of Per.	Tot. Rept. on Ages of Per.	Number of Persons by Age Group: Total Persons	Pers. under 1 Year	Pers. 1 to 4 Yrs.	Pers. 5 to 9 Yrs.	Pers. 10 to 14 Yrs.	Pers. 15 to 19 Yrs.	Pers. 20 to 64 Yrs.	P. 65 Yrs. and Over
TOTAL NUMBER OF UNITS - ALL CONDITION	Total	1	5267	7	4997	157	44	39	20	3		5267	19124	478	1592	1898	1714	1525	11350	557
	X. No Rept on Persons per Room	2																		
	Total Rept. on Persons per Room	3	5267	7	4997	157	44	39	20	3		5267	19124	478	1592	1898	1714	1525	11350	557
	A. .50 or Less	4	739		727	8	2	1	1			739	1360	2	16	14	16	28	1184	100
	B. .51 to .75	5	1163		1112	39	5	5	2			1163	3078	39	122	123	123	145	2443	113
	C. .76 to 1.00	6	1469	5	1396	39	10	14	4	1		1469	4707	86	346	322	314	336	3129	174
	D. 1.01 to 1.50	7	988	1	902	48	11	15	11			988	4514	163	449	507	475	422	2414	84
	E. 1.51 to 2.00	8	615	1	579	17	14	3	1			615	3350	101	392	534	445	360	1462	56
	F. 2.01 or More	9	293		281	6	2	1	1	2		293	2115	87	267	398	341	234	758	30
X. NO REPORT OF CONDITION	Total	10																		
	X. No Rept on Persons per Room	11																		
	Total Rept. on Persons per Room	12																		
	A. .50 or Less	13																		
	B. .51 to .75	14																		
	C. .76 to 1.00	15																		
	D. 1.01 to 1.50	16																		
	E. 1.51 to 2.00	17																		
	F. 2.01 or More	18																		
1. GOOD CONDITION	Total	19	2331	6	2191	75	23	22	11	3		2331	8022	197	599	707	600	578	5172	169
	X. No Rept on Persons per Room	20																		
	Total Rept. on Persons per Room	21	2331	6	2191	75	23	22	11	3		2331	8022	197	599	707	600	578	5172	169
	A. .50 or Less	22	411		403	6	1		1			411	805		11	10	9	14	731	30
	B. .51 to .75	23	648		617	23	3	4	1			648	1787	29	78	88	71	85	1394	42
	C. .76 to 1.00	24	670	5	629	19	6	8	2	1		670	2308	44	189	186	159	168	1509	53
	D. 1.01 to 1.50	25	382		338	21	6	10	7			382	1822	78	179	206	185	169	976	29
	E. 1.51 to 2.00	26	172	1	158	6	7					172	952	28	101	157	130	110	415	11
	F. 2.01 or More	27	48		46					2		48	348	18	41	60	46	32	147	4
2. MINOR REPAIRS	Total	28	1902	1	1805	58	17	13	8			1902	7323	184	678	971	700	604	4463	223
	X. No Rept on Persons per Room	29																		
	Total Rept. on Persons per Room	30	1902	1	1805	58	17	13	8			1902	7323	184	678	971	700	604	4463	223
	A. .50 or Less	31	218		214	2	1	1				218	399	2	5	3	6	8	333	42
	B. .51 to .75	32	372		357	13	1	1	1			372	960	8	42	26	39	47	758	40
	C. .76 to 1.00	33	531		506	14	4	5	2			531	1699	33	125	107	120	125	1126	63
	D. 1.01 to 1.50	34	398	1	364	19	5	5	4			398	1839	56	200	222	185	167	964	35
	E. 1.51 to 2.00	35	275		263	6	5	1				275	1538	50	200	246	193	152	667	30
	F. 2.01 or More	36	118		112	4	1		1			118	888	35	106	167	147	105	315	13
3. MAJOR REPAIRS	Total	37	906		876	23	3	4				906	3403	88	285	385	366	312	1827	140
	X. No Rept on Persons per Room	38																		
	Total Rept. on Persons per Room	39	906		876	23	3	4				906	3403	88	285	385	366	312	1827	140
	A. .50 or Less	40	95		95							95	141			1	1	6	110	23
	B. .51 to .75	41	134		130	3	1					134	307	2	1	9	11	12	241	31
	C. .76 to 1.00	42	231		224	6		1				231	631	9	32	29	34	39	444	44
	D. 1.01 to 1.50	43	189		181	8						189	782	28	64	73	83	81	435	18
	E. 1.51 to 2.00	44	150		142	5	1	2				150	779	19	85	121	111	89	342	12
	F. 2.01 or More	45	107		104	1	1	1				107	763	30	103	152	126	85	255	12
4. UNFIT FOR USE	Total	46	118		115	1	1		1			118	376	9	30	35	48	31	198	25
	X. No Rept. on Persons per Room	47																		
	Total Rept. on Persons per Room	48	118		115	1	1		1			118	376	9	30	35	48	31	198	25
	A. .50 or Less	49	15		15							15	15						10	5
	B. .51 to .75	50	9		9							9	24		1		2	1	20	
	C. .76 to 1.00	51	37		37							37	69				1	4	50	14
	D. 1.01 to 1.50	52	19		19							19	71	1	6	6	12	5	39	2
	E. 1.51 to 2.00	53	18		16		1		1			18	81	4	6	10	11	9	38	3
	F. 2.01 or More	54	20		19	1						20	116	4	17	19	22	12	41	1

CITY Owensboro
STATE Kentucky
4-4-35

DWELLING UNITS BY OCCUPANCY, BY NUMBER OF PERSONS PER ROOM, BY NUMBER OF EXTRA FAMILIES

General Survey Tables

TABLE 14
Units not under Construction

Occupancy	Number of Units by Number of Extra Families in Unit	Line No.	Total	Number of Units by Number of Persons per Room						
				X. No Report on Persons per Room	A. .50 or Less	B. .51 to .75	C. .76 to 1.00	D. 1.01 to 1.50	E. 1.51 to 2.00	F. 2.01 or More
TOTAL - ALL OCCUPIED UNITS	Total	1	8468		2023	2014	2106	1264	728	333
	No Report on Extra Families	2	7				5	1	1	
	Total Reports on Extra Families	3	8461		2023	2014	2101	1263	727	333
	No Extra Families	4	8315		2016	1985	2057	1231	706	320
	1 Extra Family	5	141		7	29	44	31	20	10
	2 or more Extra Families	6	5					1	1	3
ALL OWNER OCCUPIED UNITS	Total	7	3201		1284	851	637	276	113	40
	No Report on Extra Families	8								
	Total Reports on Extra Families	9	3201		1284	851	637	276	113	40
	No Extra Families	10	3139		1287	831	617	266	111	36
	1 Extra Family	11	60		6	20	20	9	2	3
	2 or more Extra Families	12	2					1		1
ALL TENANT OCCUPIED UNITS	Total	13	5267		739	1163	1469	988	615	293
	No Report on Extra Families	14	7				5	1	1	
	Total Reports on Extra Families	15	5260		739	1163	1464	987	614	293
	No Extra Families	16	5176		738	1154	1440	965	595	284
	1 Extra Family	17	81		1	9	24	22	18	7
	2 or more Extra Families	18	3						1	2

(9945)

CITY Owensboro
STATE Kentucky
6-5-36

DWELLING UNITS BY OCCUPANCY, BY NUMBER OF PERSONS PER ROOM, BY ROOMS AND MONTHLY RENT GROUPS
Derived from Table 11B and Table 11C
General Survey Tables

TABLE 15
Units Not Under Construction

Occupancy	Number of Units by Number of Rooms in Unit and by Monthly Rent	Line No.	Total	Number of Units by Number of Persons per Room: X. No Report on Persons per Room	A. .50 or Less	B. .51 to .75	C. .76 to 1.00	D. 1.01 to 1.50	E. 1.51 to 2.00	F. 2.01 or More
Total All Occupied Units		1	8468		2023	2014	2106	1264	728	333
TOTAL ALL OCCUPIED UNITS	No Report on Rooms	2								
	Total Reports on Rooms	3	8468		2023	2014	2106	1264	728	333
	1 Room	4	188		3		95		52	38
	2 Rooms	5	1065		151	3	448	237	128	98
	3 Rooms	6	2251		137	714	504	405	357	134
	4 Rooms	7	2123		639	536	397	389	111	51
	5 Rooms	8	1377		387	366	422	137	57	8
	6 Rooms	9	707		329	166	146	52	14	
	7 Rooms	10	332		130	129	45	20	7	1
	8 Rooms or More	11	425		247	100	49	24	2	3
	X. No Report on Monthly Rent	12	32		6	5	10	4	4	3
	Total Reports on Monthly Rent	13	8436		2017	2009	2096	1260	724	330
	A. $4.99 and Less	14	149		17	6	65	11	26	24
	B. $5.00 - $9.99	15	1522		170	213	405	334	251	149
	C. $10.00 - $14.99	16	2106		290	460	551	411	273	121
	D. $15.00 - $19.99	17	1207		235	327	310	218	91	26
	E. $20.00 - $24.99	18	809		201	217	234	113	40	4
	F. $25.00 - $29.99	19	589		196	158	154	63	15	3
	G. $30.00 - $39.99	20	1036		366	338	235	76	21	
	H. $40.00 - $49.99	21	555		271	176	81	23	3	1
	I. $50.00 - $74.99	22	381		213	100	54	10	2	2
	J. $75.00 - $99.99	23	64		46	11	6	1		
	K. $100.00 - $149.99	24	16		11	3	1		1	
	L. $150.00 or More	25	2		1				1	
Total All Owner Occupied Units		26	3201		1284	851	637	276	113	40
ALL OWNER OCCUPIED UNITS	No Report on Rooms	27								
	Total Reports on Rooms	28	3201		1284	851	637	276	113	40
	1 Room	29	40				26		11	3
	2 Rooms	30	118		41		42	14	14	7
	3 Rooms	31	349		55	131	72	36	39	16
	4 Rooms	32	856		352	214	133	127	19	11
	5 Rooms	33	775		265	213	219	56	20	2
	6 Rooms	34	475		246	119	79	24	7	
	7 Rooms	35	246		109	96	31	7	2	
	8 Rooms or More	36	343		216	78	35	12	1	1
	X. No Report on Monthly Rent	37	14		1	4	3	1	3	2
	Total Reports on Monthly Rent	38	3187		1283	847	634	275	110	38
	A. $4.99 and Less	39	29		1	1	12	2	9	4
	B. $5.00 - $9.99	40	175		43	30	52	19	20	11
	C. $10.00 - $14.99	41	486		148	120	107	69	33	9
	D. $15.00 - $19.99	42	433		145	105	93	63	17	10
	E. $20.00 - $24.99	43	332		115	98	69	40	8	2
	F. $25.00 - $29.99	44	325		137	88	68	22	9	1
	G. $30.00 - $39.99	45	609		240	188	130	40	11	
	H. $40.00 - $49.99	46	403		208	122	59	12	1	1
	I. $50.00 - $74.99	47	316		189	82	38	7		
	J. $75.00 - $99.99	48	61		45	10	5	1		
	K. $100.00 - $149.99	49	16		11	3	1		1	
	L. $150.00 or More	50	2		1				1	
Total All Tenant Occupied Units		51	5267		739	1163	1469	988	615	293
ALL TENANT OCCUPIED UNITS	No Report on Rooms	52								
	Total Reports on Rooms	53	5267		739	1163	1469	988	615	293
	1 Room	54	148		3		69		41	35
	2 Rooms	55	947		110	3	406	223	114	91
	3 Rooms	56	1902		82	583	432	369	318	118
	4 Rooms	57	1267		287	322	264	262	92	40
	5 Rooms	58	602		122	153	203	81	37	6
	6 Rooms	59	232		83	47	67	28	7	
	7 Rooms	60	87		21	33	14	13	5	1
	8 Rooms or More	61	82		31	22	14	12	1	2
	X. No Report on Monthly Rent	62	18		5	1	7	3	1	1
	Total Reports on Monthly Rent	63	5249		734	1162	1462	985	614	292
	A. $4.99 and Less	64	120		16	5	53	9	17	20
	B. $5.00 - $9.99	65	1347		127	183	353	315	231	138
	C. $10.00 - $14.99	66	1620		142	340	444	342	240	112
	D. $15.00 - $19.99	67	774		90	222	217	155	74	16
	E. $20.00 - $24.99	68	477		86	121	165	73	32	2
	F. $25.00 - $29.99	69	264		59	70	86	41	6	2
	G. $30.00 - $39.99	70	427		126	150	105	36	10	
	H. $40.00 - $49.99	71	152		63	54	22	11	2	
	I. $50.00 - $74.99	72	65		24	18	16	3	2	2
	J. $75.00 - $99.99	73	3		1	1	1			
	K. $100.00 - $149.99	74								
	L. $150.00 or More	75								

8975

CITY Owensboro
STATE Kentucky
6-F-56

DWELLING UNITS BY OCCUPANCY, BY RACE, BY NUMBER OF ROOMS, BY MONTHLY RENT, NUMBER OF PERSONS, CONDITION, AND NUMBER OF PERSONS PER ROOM; AND DWELLING UNITS BY NUMBER OF PERSONS IN UNIT, BY NUMBER OF PERSONS PER ROOM
General Survey Tables

TABLE 16, A, all Occupied Units,
Units Not Under Construction
A complete set of tables for each base group posted includes: Table 16 A, All Occupied Units; Table 16 B, Owner Occupied Units; Table 16 C, Tenant Occupied Units.

Number of Dwelling Units By		Line No.	Total	No Report on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
			Number of Units by Number of Rooms									
Total No. of Dwelling Units		1	8468		188	1065	2251	2123	1377	707	332	425
NUMBER OF UNITS BY MONTHLY RENT	X. No Report on Monthly Rent	2	32		6	5	5	6	3	2	2	3
	Total Reports on Monthly Rent	3	8436		182	1060	2246	2117	1374	705	330	422
	A. $4.99 and Less	4	149		87	44	12	2		3	1	
	B. $5.00 - $9.99	5	1522		47	632	686	122	24	9		2
	C. $10.00 - $14.99	6	2106		29	194	964	728	140	40	8	3
	D. $15.00 - $19.99	7	1207		10	65	284	493	242	82	25	6
	E. $20.00 - $24.99	8	809		2	68	105	307	212	76	26	13
	F. $25.00 - $29.99	9	589			35	72	184	160	86	34	18
	G. $30.00 - $39.99	10	1036		5	17	84	208	359	190	101	72
	H. $40.00 - $49.99	11	555			4	26	49	155	129	73	119
	I. $50.00 - $74.99	12	381		2	1	11	24	68	82	60	133
	J. $75.00 - $99.99	13	64				2		6	7	5	44
	K. $100.00 - $149.99	14	16						3		2	11
	L. $150.00 or More	15	2							1		1
NUMBER OF UNITS BY NUMBER OF PERSONS	No Report on Persons	16										
	Total Reports on Persons	17	8468		188	1065	2251	2123	1377	707	332	425
	1 Person	18	520		97	151	135	64	42	14	5	12
	2 Persons	19	2393		52	448	715	572	347	140	57	62
	3 Persons	20	1979		25	236	502	541	365	174	67	69
	4 Persons	21	1540		9	131	404	399	261	164	82	90
	5 Persons	22	884		4	46	233	233	165	87	50	66
	6 Persons	23	517		25	126	153	83	62	30	38	
	7 Persons	24	265		1	21	65	64	51	25	15	23
	8 Persons	25	176			6	46	45	28	16	11	24
	9 Persons	26	85			1	10	27	17	11	4	15
	10 Persons	27	52				6	13	10	10	4	9
	11 Persons or More	28	57				9	12	8	4	7	17
Number of Persons in Units with 11 or more Persons		29	685				103	137	82	49	89	225
NUMBER OF UNITS BY CONDITION	X. No Report on Condition	30										
	Total Reports on Condition	31	8468		188	1065	2251	2123	1377	707	332	425
	1. Good Condition	32	4419		53	369	866	1169	935	470	245	312
	2. Minor Repairs	33	2800		56	368	889	720	378	200	81	108
	3. Major Repairs	34	1101		48	266	455	224	62	35	6	5
	4. Unfit for Use	35	148		31	62	41	10	2	2		
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED)	X. No Report on Persons per Room	36										
	Total Reports on Persons per Room	37	8468		188	1065	2251	2123	1377	707	332	425
	A. .50 or Less	38	2023		3	151	137	639	387	329	130	247
	B. .51 to .75	39	2014			3	714	536	366	166	129	100
	C. .76 to 1.00	40	2106		95	448	504	504	397	422	146	49
	D. 1.01 to 1.50	41	1264			237	405	389	137	52	20	24
	E. 1.51 to 2.00	42	728		52	128	357	111	57	14	7	2
	F. 2.01 or More	43	333		38	98	134	51	8		1	3

Number of Dwelling Units By		Line No.	Total Number of Units	X. No Report on Persons	1 Person	2 Persons	3 Persons	4 Persons	5 Persons	6 Persons	7 Persons	8 Persons	9 Persons	10 Persons	11 Persons or More
				Number of Dwelling Units by Number of Persons in Unit											
Total Number of Units		44	8468		520	2393	1979	1540	884	517	265	176	85	52	57
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED)	X. No Report on Persons per Room	45													
	Total Reports on Persons per Room	46	8468		520	2393	1979	1540	884	517	265	176	85	52	57
	A. .50 or Less	47	2023		425	1172	316	93	11	3		2	1		
	B. .51 to .75	48	2014			716	894	250	107	36	6		5		
	C. .1. to 1.00	49	2106		95	449	503	652	252	92	33	23	3	2	2
	D. 1.01 to 1.50	50	1264			5	236	406	233	238	76	27	22	10	11
	E. 1.51 to 2.00	51	728			51	5	131	231	124	65	72	17	20	12
	F. 2.01 or More	52	333				25	8	50	24	85	52	37	20	32

8975

CITY Owensboro
STATE Kentucky
6-F-36

DWELLING UNITS BY OCCUPANCY, BY RACE, BY NUMBER OF ROOMS, BY MONTHLY RENT, NUMBER OF PERSONS, CONDITION, AND NUMBER OF PERSONS PER ROOM AND DWELLING UNITS BY NUMBER OF PERSONS IN UNIT, BY NUMBER OF PERSONS PER ROOM
General Survey Tables

TABLE 16, B Owner Occupied Units,
Units Not Under Construction
A complete set of tables for each race group posted includes: Table 16 A, All Occupied Units; Table 16 B, Owner Occupied Units; Table 16 C, Tenant Occupied Units.

Number of Dwelling Units By		Line No.	Total	No Report on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
Total No. of Dwelling Units		1	3201		40	118	349	856	775	475	245	343
NUMBER OF UNITS BY MONTHLY RENT	X. No Report on Monthly Rent	2	14		3	2	4	2	1		2	
	Total Reports on Monthly Rent	3	3187		37	116	345	854	774	475	243	343
	A. $4.99 and Less	4	29		22	4	3					
	B. $5.00 - $9.99	5	175		10	50	65	41	4	3		2
	C. $10.00 - $14.99	6	486		3	31	138	236	59	16	3	
	D. $15.00 - $19.99	7	433		1	12	59	179	115	48	14	5
	E. $20.00 - $24.99	8	332		1	5	22	137	108	44	9	6
	F. $25.00 - $29.99	9	325			5	16	107	95	55	24	13
	G. $30.00 - $39.99	10	609			5	18	111	224	126	70	50
	H. $40.00 - $49.99	11	403			3	18	122	102	106	63	94
	I. $50.00 - $74.99	12	316			1	9	21	48	69	53	115
	J. $75.00 - $99.99	13	61				2		6	7	5	41
	K. $100.00 - $149.99	14	16						3		2	11
	L. $150.00 or More	15	2							1		1
NUMBER OF UNITS BY NUMBER OF PERSONS	No Report on Persons	16										
	Total Reports on Persons	17	3201		40	118	349	856	775	475	245	343
	1 Person	18	227		26	41	55	46	30	12	5	12
	2 Persons	19	892		13	42	116	291	231	97	48	54
	3 Persons	20	762		1	14	72	214	213	135	54	59
	4 Persons	21	585			14	36	134	141	117	63	80
	5 Persons	22	312			2	24	71	78	50	34	53
	6 Persons	23	195			1	17	55	37	31	24	30
	7 Persons	24	78		1	4	10	12	18	11	8	14
	8 Persons	25	45				5	6	6	7	4	17
	9 Persons	26	26					5	4	4	1	12
	10 Persons	27	18					2	5	3	2	6
	11 Persons or More	28	18				1	3	2	4	2	6
Number of Persons in Units with 11 or More Persons		29										
NUMBER OF UNITS BY CONDITION	X. No Report on Condition	30										
	Total Reports on Condition	31	3201		40	118	349	856	775	475	245	343
	1. Good Condition	32	2088		18	60	151	512	565	341	187	254
	2. Minor Repairs	33	888		9	36	130	269	187	116	56	85
	3. Major Repairs	34	195		6	13	52	68	32	16	4	4
	4. Unfit for Use	35	30		7	8	10	4		1		
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO THE NEAREST TENTH)	X. No Report on Persons per Room	36										
	Total Reports on Persons per Room	37	3201		40	118	349	856	775	475	245	343
	A. .50 or Less	38	1284			41	55	352	265	246	109	216
	B. .51 to .75	39	851				131	214	213	119	96	78
	C. .76 to 1.00	40	637		26	42	72	133	219	79	31	35
	D. 1.01 to 1.50	41	276			14	36	127	56	24	7	12
	E. 1.51 to 2.00	42	113		11	14	39	19	20	7	2	1
	F. 2.01 or More	43	40		3	7	16	11	2			1

Number of Dwelling Units By		Line No.	Total Number of Units	X. No Report on Persons	1 Person	2 Persons	3 Persons	4 Persons	5 Persons	6 Persons	7 Persons	8 Persons	9 Persons	10 Persons	11 Persons or More
Total Number of Units		44	3201		227	927	763	585	312	195	78	50	28	18	18
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO THE NEAREST TENTH)	X. No Report on Persons per Room	45													
	Total Reports on Persons per Room	46	3201		227	927	763	585	312	195	78	50	28	18	18
	A. .50 or Less	47	1284		201	739	249	82	9	1		2	1		
	B. .51 to .75	48	851			135	423	180	80	27	3		3		
	C. .76 to 1.00	49	637		26	42	73	272	128	54	19	18	3	2	
	D. 1.01 to 1.50	50	276				15	37	71	93	29	12	9	5	5
	E. 1.51 to 2.00	51	113			11	1	14	22	17	12	15	6	8	7
	F. 2.01 or More	52	40				2		2	1	15	5	6	3	6

CITY Owensboro
STATE Kentucky
8-F-86

DWELLING UNITS BY OCCUPANCY, BY RACE, BY NUMBER OF ROOMS, BY MONTHLY RENT, NUMBER OF PERSONS, CONDITION, AND NUMBER OF PERSONS PER ROOM; AND DWELLING UNITS BY NUMBER OF PERSONS IN UNIT, BY NUMBER OF PERSONS PER ROOM
General Survey Tables

TABLE 16, C, Tenant Occupied Units
Units Not Under Construction

A complete set of tables for each Race group posted includes: Table 16 A, All Occupied Units; Table 16 B, Owner Occupied Units; Table 16 C, Tenant Occupied Units.

Number of Dwelling Units By		Line No.	Total	Number of Units by Number of Rooms: No Report on Rooms	1 Room	2 Rooms	3 Rooms	4 Rooms	5 Rooms	6 Rooms	7 Rooms	8 Rooms or More
Total No. of Dwelling Units		1	5267		148	947	1902	1267	602	232	87	82
NUMBER OF UNITS BY MONTHLY RENT	X. No Report on Monthly Rent	2	18		3	3	1	4	2	2		3
	Total Reports on Monthly Rent	3	5249		145	944	1901	1263	600	230	87	79
	A. $4.99 and Less	4	120		65	40	9	2		3	1	
	B. $5.00 - $9.99	5	1347		37	582	621	81	20	6		
	C. $10.00 - $14.99	6	1620		26	163	826	492	81	24	5	3
	D. $15.00 - $19.99	7	744		9	53	225	314	127	34	11	1
	E. $20.00 - $24.99	8	477		1	63	83	170	104	32	17	7
	F. $25.00 - $29.99	9	263			30	56	77	54	31	10	5
	G. $30.00 - $39.99	10	427		5	12	66	97	140	64	26	17
	H. $40.00 - $49.99	11	152			1	13	27	54	23	10	24
	I. $60.00 - $74.99	12	65		2		2	3	20	13	7	18
	J. $75.00 - $99.99	13	4									4
	K. $100.00 - $149.99	14										
	L. $150.00 or More	15										
NUMBER OF UNITS BY NUMBER OF PERSONS	No Report on Persons	16										
	Total Reports on Persons	17	5267		148	947	1902	1267	602	232	87	82
	1 Person	18	293		71	110	80	18	12	2		
	2 Persons	19	1466		41	406	586	266	110	41	8	8
	3 Persons	20	1216		23	222	430	327	152	39	13	10
	4 Persons	21	955		9	117	368	265	120	47	18	11
	5 Persons	22	572		4	44	209	162	87	37	16	13
	6 Persons	23	322			24	109	98	46	31	6	8
	7 Persons	24	187			17	55	52	33	14	6	10
	8 Persons	25	126			6	42	39	19	7	9	4
	9 Persons	26	57			1	10	21	11	6	4	4
	10 Persons	27	34				5	10	6	8	2	3
	11 Persons or More	28	39				8	9	6		5	11
Number of Persons in Units with 11 or more Persons		29	464				92	102	61		65	145
NUMBER OF UNITS BY CONDITION	X. No Report on Condition	30										
	Total Reports on Condition	31	5267		148	947	1902	1267	602	232	87	82
	1. Good Condition	32	2331		35	309	715	657	370	129	58	58
	2. Minor Repairs	33	1912		47	332	759	451	191	84	25	23
	3. Major Repairs	34	906		42	252	397	153	39	18	4	1
	4. Unfit for Use	35	118		24	54	31	6	2	1		
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED)	X. No Report on Persons per Room	36										
	Total Reports on Persons per Room	37	5267		148	947	1902	1267	602	232	87	82
	A. .50 or Less	38	739		3	110	82	287	122	83	21	31
	B. .51 to .75	39	1163			3	583	322	153	47	33	22
	C. .76 to 1.00	40	1469		69	406	432	264	203	67	14	14
	D. 1.01 to 1.50	41	988			223	369	262	81	28	13	12
	E. 1.51 to 2.00	42	615		41	114	318	92	37	7	5	1
	F. 2.01 or More	43	293		35	91	118	40	6		1	2

Number of Dwelling Units By		Line No.	Total Number of Units	Number of Dwelling Units by Number of Persons in Unit: X. No Report on Persons	1 Person	2 Persons	3 Persons	4 Persons	5 Persons	6 Persons	7 Persons	8 Persons	9 Persons	10 Persons	11 Persons or More
Total Number of Units		44	5267		293	1467	1217	954	572	321	187	126	57	34	39
NUMBER OF UNITS BY NUMBER OF PERSONS PER ROOM (TO BE DERIVED)	X. No Report on Persons per Room	45													
	Total Reports on Persons per Room	46	5267		293	1467	1217	954	572	321	187	126	57	34	39
	A. .50 or Less	47	739		224	433	67	11	2			2			
	B. .51 to .75	48	1163			582	472	69	27	8	3		2		
	C. .76 to 1.00	49	1469		69	407	430	380	124	38	14	5			2
	D. 1.01 to 1.50	50	988			5	221	369	162	145	47	15	13	5	6
	E. 1.51 to 2.00	51	615			40	4	117	209	107	53	57	11	12	5
	F. 2.01 or More	52	293				23	8	48	23	70	47	31	17	26

8975

TABLE NO. 1

STRUCTURES UNDER CONSTRUCTION BY TYPE OF STRUCTURE,
DWELLING UNITS UNDER CONSTRUCTION,
BY TYPE OF STRUCTURE, BY NUMBER OF ROOMS AND MONTHLY RENT

At the time of the survey, July 1938 to Jan. 1940, there were 88 structures under construction, containing 96 dwelling units. 80 of these structures were of single family type with 4, 5 and 6 room capacity and renting from $30.00 to $50.00 per month. This would indicate that approximately 90% of the homes under construction are in the middle class group.

TABLE NO. 2

CONVERTED STRUCTURES BY TYPE OF CONVERSION
AND BY YEAR CONVERTED

A study of the converted structures shows that 457 have been converted partially and 77 completely converted. During the period from 1885 to 1904 only 6 homes were recorded as being converted. From 1930 to 1934 there were 84 homes converted and during the period from 1935 to 1939 a total of 227 structures were either partially or completely converted. This large increase during the past four years is no doubt due to a faster growing Owensboro and to the demand for apartments developing from the Oil Industry.

TABLE NO. 3

STRUCTURES BY TYPE OF STRUCTURE BY NUMBER OF
STORIES, BASEMENT, GARAGE AND YEAR BUILT

The tabulation reports show a total of 7030 dwelling structures classed as follows:

5492 of which are of single family type
1 of which is of single family type attached.
632 of which are of two family type
44 of which are of three to four family type.
8 of which are of five or more family type.

TABLE NO. 3 - Cont.

4444 structures are one story construction.
4955 structures have no basement
2072 structures have basements
3670 structures have no garage.

During the period from 1895 to 1904 there was a total of 2040 homes constructed and in the period from 1935 to 1939 a total of 1026 homes was constructed. During the time between these two periods a yearly average of 100 homes is recorded as being built. These figures indicate that Owensboro has had two periods of intensive home construction. The building of new homes is still going on at a very satisfactory rate indicating that that from 1935 on will be the best five years the building industry has seen.

TABLE NO. 5

OWNER OCCUPIED STRUCTURES BY VALUE OF PROPERTY, BY TYPE OF STRUCTURE, BY CONDITION, DEBT STATUS, AND NUMBER OF ROOMS IN STRUCTURE.

The total number of owner occupied homes is 2588. The average value of these homes is $3220.00. Out of this total of 2588 homes 1697 are in good condition, 714 need minor repairs, 153 need major repairs and 24 are unfit for use.

715 of these owner occupied homes are mortgaged and 1864 are free of encumbrances.

TABLE NO. 5

STRUCTURES BY TYPE OF STRUCTURE, BY CONDITION AND BY YEAR BUILT.

Tabulation reports on 7030 dwelling structures show the following physical conditions:

3703 are in good condition
2321 need minor repairs
858 need major repairs
148 are unfit for use

TABLE NO. 6

STRUCTURES BY TYPE OF STRUCTURE, BY CONDITION,
BY EXTERIOR MATERIAL

6043 Dwelling structures are of Wood construction.
773 Dwelling structures are of Brick construction.
41 Dwelling structures are of Stone construction.
24 Dwelling structures are of Stucco construction.
148 Dwelling structures are of other construction.

TABLE NO. 7

DWELLING UNITS BY TYPE OF STRUCTURE, BY NUMBER
OF PERSONS PER ROOM, BY NUMBER OF CHILDREN.

A total of 8468 units reported shows that

4505 units have no children
1835 units have 1 child
1105 units have 2 children
801 units have 3 to 4 children
222 units have 5 or more children

TABLE NO. 8

DWELLING UNITS BY TYPE OF STRUCTURE, BY CONDITION,
BY DURATION OF OCCUPANCY.

From a total of 8468 reports we find that:

1387 units have been occupied 6 months or less.
778 units have been occupied 6 to 11 months.
1287 units have been occupied 1 year to 1 year and 11 months.
887 units have been occupied 2 years to 2 years and 11 months.
1134 units have been occupied 3 years to 4 years and 11 months.
1161 units have been occupied 5 years to 9 years and 11 months.
1095 units have been occupied 10 years to 19 years and 11 months.
754 units have been occupied 20 years or longer.

These figures refer to continuous occupancy by one occupant.

TABLE NO. 9

DWELLING UNITS BY NUMBER OF PERSONS IN UNIT, BY TYPE OF STRUCTURE, HEATING EQUIPMENT, LIGHTING EQUIPMENT, COOKING EQUIPMENT, REFRIGERATION EQUIPMENT, NUMBER OF ROOMERS, NUMBER OF PERSONS PER ROOM AND PLUMBING EQUIPMENT

From a total of 8468 units reported the following figures are deduced:

Units with central steam or hot water heating	802
Units with central hot air	1608
Units with some other type installed	2945
Units with no heating installed	3113
Units with Electric lighting	8042
Units with Gas lighting	10
Units with no lighting installed	415
Units with Electric cooking	94
Units with Gas cooking	2956
Units with some other type installed	1898
Units with no cooking facilities installed	3515
Units with no roomers	7996
Units with roomers, from 1 to 11 roomers	465
Units with less than 1.50 persons per room	7407
Units with more than 1.50 persons per room	1061
Units with at least 2 toilets and 2 baths	113
Units with 2 toilets and 1 bath	28
Units with 1 toilet and 1 bath	4215
Units with 1 toilet and no bath	1459
Units with shared toilet and running water	61
Units with shared toilet but no running water	89
Units with no toilet but running water	692
Units with no toilet and no running water	1811

TABLE NO. 10

DWELLING UNITS BY MONTHLY RENT, BY PLUMBING EQUIPMENT, HEATING EQUIPMENT, LIGHTING EQUIPMENT, YEAR BUILT, REFRIGERATION, NUMBER OF ROOMERS AND RACE OF HOUSEHOLD.

A total of 8721 reports give the following information relative to rentals:

152	Dwelling Units rent for	4.99 or less per month
1548	Dwelling Units rent for	5.00 to 9.99 per month
2158	Dwelling Units rent for	10.00 to 14.99 per month
1237	Dwelling Units rent for	15.00 to 19.99 per month
843	Dwelling Units rent for	20.00 to 24.99 per month
612	Dwelling Units rent for	25.00 to 29.99 per month
1084	Dwelling Units rent for	30.00 to 39.99 per month
573	Dwelling Units rent for	40.00 to 49.99 per month
386	Dwelling Units rent for	50.00 to 74.99 per month
82	Dwelling Units rent for	75.00 and up per month.

These rental figures include all owner occupied dwelling units and are set up as the rental price they would ask if they decided to rent that unit.

TABLE NO. 11

NUMBER OF DWELLING UNITS BY MONTHLY RENT, BY NUMBER OF ROOMS, NUMBER OF PERSONS, FURNITURE INCLUDED IN RENT, DURATION OF OCCUPANCY, NUMBER OF CHILDREN, EXTRA FAMILIES, NUMBER OF PERSONS IN EXTRA FAMILIES

Most of the data in this table is included in the previous tables and has been commented on, so it was not considered necessary to include the table in this summary.

TABLE NO. 12

DWELLING UNITS BY OCCUPANCY, BY CONDITION,
BY PLUMBING EQUIPMENT AND BY NUMBER OF CHILDREN.

Tabulated data on 8721 reported units shows:

No Units	Condition	Sanitary Facilities
87	Good condition	2 toilets - 2 baths
27	Minor repairs	2 toilets - 2 baths
25	Major repairs	2 toilets - 2 baths
3	Unfit for use	2 toilets - 2 baths
3070	Good condition	1 toilet - 1 bath
1174	Minor repairs	1 toilet - 1 bath
115	Major repairs	1 toilet - 1 bath
2	Unfit for use	1 toilet - 1 bath
756	Good condition	1 toilet- no bath
538	Minor repairs	1 toilet - no bath
216	Major repairs	1 toilet - no bath
2	Unfit for use	1 toilet - no bath
12	Good condition	Shared toilet - running water
32	Minor repairs	Shared toilet - running water
17	Major repairs	Shared toilet - running water
23	Good condition	Shared toilet - no running water
49	Minor repairs	Shared toilet - no running water
22	Major repairs	Shared toilet - no running water
236	Good condition	No toilet - running water
323	Minor repairs	No toilet - running water
113	Major repairs	No toilet - running water
26	Unfit for use	No toilet - running water
355	Good condition	No toilets or running water
721	Minor repairs	No toilets or running water
634	Major repairs	No toilets or running water
142	Unfit for use	No toilets or running water

TABLE NO. 13

DWELLING UNITS BY PERSONS PER ROOM, BY CONDITION, BY NUMBER OF ROOMERS AND NUMBER OF PERSONS BY AGE

This table shows a total of 8468 dwelling units occupied by 30,163 persons, divided by age as follows

595 persons 1 year or younger
2101 persons 2 to 4 years of age
2670 persons 5 to 9 years of age
2588 persons 10 to 14 years of age
2503 persons 15 to 19 years of age
18,446 persons 20 to 64 years of age
1260 persons 65 years or older.

TABLE NO. 14

DWELLING UNITS BY OCCUPANCY, BY NUMBER OF PERSONS PER ROOM, BY NUMBER OF EXTRA FAMILIES

8315 Dwelling units report no extra families
141 dwelling units report 1 extra family
5 Dwelling units report 2 or more extra families.

TABLE NO. 15

DWELLING UNITS BY OCCUPANCY, BY NUMBER OF PERSONS, BY ROOMS AND BY MONTHLY RENT GROUPS

A total report shows 8469 units.

149	Units rent for	$ 4.99 or less
1522	Units rent for	5.00 to $ 9.99
2106	Units rent for	10.00 to 14.99
1207	Units rent for	15.00 to 19.99
809	Units rent for	20.00 to 24.99
589	Units rent for	25.00 to 29.99
1036	Units rent for	30.00 to 39.99
555	Units rent for	40.00 to 49.99
381	Units rent for	50.00 to 74.99
82	Units rent for	75.00 and up

TABLE NO. 16

DWELLING UNITS BY OCCUPANCY, BY RACE, BY NUMBER OF ROOMS, BY MONTHLY RENT, NUMBER OF PERSONS, CONDITIONS NUMBER OF PERSONS PER ROOM, DWELLING UNITS BY NUMBER OF PERSONS IN UNIT AND BY NUMBER OF PERSONS PER ROOM.

The following figures show the number of persons occupying each dwelling unit by size:

339	Persons	occupying	188	one room units
2861	Persons	occupying	1065	two room units
7681	Persons	occupying	2251	three room units
7826	Persons	occupying	2123	four room units
5122	Persons	occupying	1317	five room units
2826	Persons	occupying	707	six room units
1627	Persons	occupying	332	seven room units
2026	Persons	occupying	425	eight or more room units.

LIBRARY
U OF KY

DEPOSITORY
UNIV. OF KENTUCKY LIBRARIES

UNIVERSITY OF KENTUCKY
[redacted]
3 0425 0863743 2

*
HD
7303
.K4
U5S10
1940

Call No. 331.83
Un32o

Accession No. 226609

LIBRARY
UNIVERSITY OF KENTUCKY

DEMCO